



PLANNING COMMISSION MEETING AGENDA

Department of Community and Economic Development
Meeting Date: May 4, 2022

NOTICE is hereby given that the Cottonwood Heights Planning Commission will hold a Work Session Meeting, beginning at 5:00 p.m. in Room 124 (Council Workroom) and a Business Meeting, beginning at 6:00 p.m. in Room 5 (Council Chambers) at 2277 E. Bengal Blvd., Cottonwood Heights, UT 84121, on **Wednesday, May 4, 2022**. The meeting will also be broadcast electronically on Zoom, via the below links. Those interested in attending the meeting and/or making public comments may attend either in person or electronically. The public may remotely hear the open portions of the meeting through live broadcast by connecting to <http://mixlr.com/chmeetings>.

To View the Work Session: Each citizen desiring to view the Work Session must register in advance to view the online video broadcast at the following link:

https://cwh.zoom.us/webinar/register/WN_SOFpxSNRRGKS9CHsoAsTJA

To View or Participate in the Business Meetings: Citizens will be able to make live verbal comments during the “General Public Comment” or public hearing portions through the City’s online video broadcast via Zoom. Each citizen desiring to make a citizen comment must register in advance to view or participate in the online video broadcast at the following link:

https://cwh.zoom.us/webinar/register/WN_CWQJ4TWgSqiMvt-YCNsiEQ

5:00 p.m. WORK MEETING

1.0. Review Business Meeting Agenda

The Commission will review and discuss agenda items.

1.1. Additional Discussion Items

The Commission may discuss the status of pending applications and matters before the Commission and new applications and matters that may be considered by the Commission in the future.

6:00 p.m. BUSINESS MEETING

1.0 Welcome and Acknowledgements

1.1 Ex parte communications or conflicts of interest to disclose.

2.0 General Public Comment

(Please note: In order to be considerate of everyone attending the meeting and to more closely follow the published agenda times, public comments will be limited to three minutes per person per item. A spokesperson who has been asked by a group that is present to summarize their concerns will be allowed five minutes to speak. Comments which cannot be made within these limits should be submitted in writing to the Senior Planner at ahulka@ch.utah.gov prior to noon the day before the meeting.)

3.0 Business Items

3.1 Project ZTA-19-001

A public hearing to receive comments on a proposed ordinance update relating to the Sensitive Lands Evaluation & Development Standards (SLEDS) ordinance (Section 19.72 of the zoning ordinance).

4.0 Consent Agenda

4.1 Approval of Planning Commission Minutes

4.1.1 April 6, 2022 Planning Commission Minutes

5.0 Adjourn

Meeting Procedures

Items will generally be heard in the following order:

1. Staff Presentation
2. Applicant Presentation
3. Open Public Hearing (if item has been noticed for public hearing). Written public comment received prior to the meeting will be distributed to the Planning Commission.
4. Close Public Hearing
5. Planning Commission Deliberation
6. Planning Commission Motion and Vote

Planning Commission applications may be tabled if: 1) Additional information is needed in order to act on the item; OR 2) The Planning Commission feels there are unresolved issues that may need further attention before the Commission is ready to make a motion. **NO agenda item will begin after 9 pm** without a unanimous vote of the Commission. The Commission may carry over agenda items, scheduled late in the evening and not heard, to the next regularly scheduled meeting.

Submission of Written Public Comment

If you are interested in making a public comment, but are unable to attend the meeting, written comments on any agenda item may be submitted to the Cottonwood Heights Community and Economic Development Department up to 12:00 p.m. on the day before the meeting date. Comments should be emailed to ahulka@ch.utah.gov. Comments received by this deadline will be entered into the record and distributed to the Planning Commission prior to the meeting. Comments received after 12:00 p.m. on the day before the meeting date will be distributed to the Commission members after the meeting.

Notice of Compliance with the Americans with Disabilities Act (ADA)

In compliance with the Americans with Disabilities Act, individuals needing special accommodations or assistance during this meeting shall notify the City Recorder at (801) 944-7021 at least 24 hours prior to the meeting. TDD number is (801) 270-2425 or call Relay Utah at #711.

Confirmation of Public Notice

On Friday, April 29th, 2022, a copy of the foregoing notice was posted in conspicuous view in the front foyer of the Cottonwood Heights City Offices. The agenda was also posted on the City's website at www.cottonwoodheights.utah.gov and the Utah public notice website at <http://pmn.utah.gov>.

DATED THIS 29th DAY OF APRIL 2022, Paula Melgar, City Recorder



PLANNING COMMISSION STAFF MEMO

Sensitive Lands Ordinance Amendments

Meeting Date: May 4, 2022

Staff Contact: Andy Hulka, Senior Planner
(801-944-7065, ahulka@ch.utah.gov)

Summary

Project #:

ZTA-19-001

Action Requested:

Receive public comments and give feedback on the Sensitive Lands Evaluation & Development Standards (SLEDS) ordinance (Section 19.72 of the zoning ordinance).

Recommendation:

Discussion and feedback requested

Background

The city is in the process of updating the Sensitive Lands Evaluation & Development Standards (SLEDS) ordinance with current engineering best practices for natural hazard assessment and mitigation, and to improve the overall usability of the code. This project was first introduced to the Planning Commission in May 2021 and then reintroduced on January 19, 2022. An additional work session discussion was held on April 6, 2022. A notice was included in the city newsletter inviting the public to attend the May 4th public hearing.

Recent Updates

Several notable changes have been made to the proposed ordinance since the April 6th Planning Commission meeting.

Avalanche Hazards

While avalanches could be a hazard requiring study for some properties in Cottonwood Heights, the conditions required for an avalanche hazard to exist are not common within city boundaries. The latest draft ordinance lists snow avalanches as one of the hazards that the Development Review Committee (DRC) can require additional studies for (19.72.060.B), but no longer includes the avalanche appendix.

Steep Slopes (19.72.050.A)

To help clarify the intent of the slope development exceptions and make the rules less ambiguous, some language was added to or changed in certain sections. *"They are clearly isolated from other areas that exceed 30 percent"* has been changed to *"The slope is not part of a larger, contiguous slope that exceeds 30 percent."* *"This exception shall not apply to natural slope areas in excess of 30% connected to the Wasatch Mountain Range"* has been changed to *"This exception shall not apply to natural slope areas in excess of 30% east of Wasatch Blvd."*

Vegetation and Re-vegetation (19.72.050.I)

Vegetation plans are required in sensitive lands areas for projects that require the re-vegetation of a trail, open space, or hillside. This draft includes an added requirement for vegetation plans to be stamped by a licensed landscape architect.

Streets and Ways (19.72.050.L)

To maintain consistency with the street design requirements contained in Title 14 of the City Code (Highways, Sidewalks, and Public Places), the maximum grade section has been removed. The maximum grade of streets in sensitive lands areas will be the same as all other streets in the city (8%).

Land Disturbance Permit (19.72.100.C)

Most of this section was initially removed in an effort to simplify the process for receiving a land disturbance permit, but after a close review with the Public Works Department, these requirements have been left in the ordinance, with clarification added that they will apply to sites larger than one acre, as well as sites smaller than one acre if they are a phase or part of a larger development project that is over one acre.

Review of Geologic Hazard Reports (19.72.160)

The City Attorney has concerns that setting a hard deadline of 45 days for a review could be an issue. This draft includes the language that the city will *“endeavor to complete each review in a reasonable time frame within forty-five (45) days.”*

Other Changes

The previous month’s staff report will be attached for reference. Most of the other changes previously proposed, with the exception of those that have been altered as outlined above, are still included in the latest draft ordinance. Staff anticipates additional changes will be made after a full review by the city’s geotechnical and geologic hazard consultant is complete and after public comments are received.

Staff Recommendation

Staff recommends that the Planning Commission review the attached materials, receive public comments, and provide feedback on the proposal so a final draft may be presented at the following meeting for recommendation to the City Council. This item has been scheduled for public comment only.

Model Motions

Move to Continue

Based on the feedback provided to staff, I move we continue this item to the June 1st, 2022 Planning Commission meeting.

Attachments

1. April 6, 2022 Staff Memo
2. Draft SLEDS Ordinance

19.72

SENSITIVE LANDS EVALUATION AND DEVELOPMENT STANDARDS (SLEDS)

19.72.010 Purpose

~~19.72.020 Scope And Application~~

~~19.72.030-020 Definitions~~

~~19.72.030 Conflict Regulations~~

~~19.72.040 Applicability~~

~~19.72.040-050 Development Standards And Controls~~

~~19.72.050-060 Responsibility For Geologic Hazard And Other Studies~~

~~19.72.070 Minimum Acceptable Qualifications Of The Engineering Geologist~~

~~19.72.080 Minimum Acceptable Qualifications Of The Geotechnical Engineer~~

~~19.72.060-090 Minimum Acceptable Qualifications Of Other Professionals~~

~~19.72.070-100 Procedure Preliminary Activities~~

~~19.72.080-110 Geologic Hazards Study Area Maps~~

~~19.72.090-120 Geologic Hazard Studies And Reports Required~~

~~19.72.130 Building Permits On Lots Recorded Prior To The Effective Date Of These Ordinances~~

~~19.72.100-140 Geologic Hazard Reports~~

~~19.72.150 Submittal Of Geologic Hazard Reports~~

~~19.72.110-160 Review Of Geologic Hazard Reports~~

~~19.72.120-170 Disclosure When A Geologic Hazard Report Is Required~~

~~19.72.130-180 Warning And Disclaimer~~

~~19.72.140-190 Change Of Use~~

~~19.72.150 Conflicting Regulations~~

~~19.72.160-200 Maps And Appendices~~

19.72.010 Purpose

The city deems it appropriate that sensitive land areas in the city be protected through their inclusion in a sensitive lands district to ensure that development is regulated in a manner that will minimize the potential impact from natural and man-made hazards and will reasonably preserve natural scenic beauty and ecological integrity. To the greatest extent practicable, the objectives to be achieved by the designation of a sensitive lands district include, without limitation, the following:

- ~~A. The protection of the public from natural hazards, such as land slide, rock fall, debris flow, earthquake ground rupture, liquefaction, shallow ground water, snow melt/storm water runoff and erosion.~~
- ~~B. The minimization of the threat of and consequential damage from fire in wildland interface areas.~~
- ~~C. The preservation of significant geological features, hydrologic features, wildlife habitat and migration corridors, and open space, including retention of natural topographic features such as drainage channels, streams, ridge lines, rock outcroppings, vistas, trees and other natural geologic and plant formations.~~
- ~~D. The preservation of appropriate public access to mountain areas and natural drainage channels for recreation.~~

- ~~E. The consideration, preservation and enhancement of environmental quality.~~
- ~~F. The master planning of an adequate transportation system for the total hillside area, including consideration of the city's master plan for streets, trails, bikes and pedestrians and consideration of densities and topography, with minimal cuts, fills, or other visible scars.~~
- ~~G. The use of terrain adaptive architecture to ensure compatibility with the natural terrain, to preserve natural open spaces and vistas, and to minimize impact from geologically hazardous areas.~~
- ~~H. The placement of building sites in such a manner as to permit ample room for landscaping compatible with the natural vegetation and surface drainage.~~
- ~~I. The requirement that development:
 - ~~1. Pay special regard to the view of the hillsides from areas outside the development, and~~
 - ~~2. Protect such viewsheds to the greatest extent reasonably practicable through terrain sensitive building practices, increased ridgeline setbacks, use of the natural topography to shield man-made structures from the view of the valley, current best practices for clustering structures, and optimizing setbacks between structures to consolidate the building envelope of a property.~~~~
- A. The purpose of this chapter is to protect and promote the health, safety, and welfare of the citizens of Cottonwood Heights City, to encourage wise land use, to protect Cottonwood Heights City's infrastructure and financial health, and to minimize potential adverse effects of geologic hazards to public health, safety, and property.
- B. This chapter and its appendices address surface fault rupture, slope stability and landslide, liquefaction, debris flow, and rock fall hazards and present minimum standards and methods for evaluating geologic hazards.
- C. Appendix A presents geologic hazards study area maps as well as supplemental maps reflecting geological concerns, pertaining to development within Cottonwood Heights City. The maps incorporate data obtained from numerous publications and previous geologic hazard studies. The city's official maps shall be amended by the city from time to time.
- D. Site specific geologic hazard assessments performed by qualified engineering geologists shall be required prior to developing projects located within a geologic hazards study area. The results of geologic hazard investigations shall comply with this chapter and its appendices. The standards set forth in the appendices to this chapter are the city's minimum requirements. More detailed and in-depth evaluations than outlined herein may be required for specific projects if evidence becomes available that suggests more stringent requirements are appropriate. In addition, the appendices shall not supersede other more stringent requirements that may be required by other regulatory agencies or governmental entities that have jurisdiction.
- E. The provisions of this chapter shall apply to areas in the Cottonwood Heights City located in any area designated as a sensitive lands district on the city's official geologic hazards study area maps contained in Appendix A of this chapter. The provisions of this chapter also shall apply to an area outside of a designated sensitive lands district if, based on competent evidence complying with the requirements of this chapter, the subject area qualifies as a sensitive area under this chapter, the subject area qualifies as a sensitive area under this chapter.

19.72.020 Scope And Application

A. Application.

- ~~1. The provisions of this chapter shall apply to all lands in the city located in any area designated as a sensitive lands district on the city's official maps contained in Appendix A of this chapter. The provisions of this chapter also shall apply to an area outside of a designated sensitive lands district if the director expressly determines in writing before issuance of a building permit, based on competent evidence complying with the requirements of this chapter, that the subject area qualifies as a sensitive area under this chapter.~~
- ~~2. The provisions of this chapter shall not apply to an area within a previously designated sensitive lands district if, upon analyzing an otherwise compliant development proposal, the director expressly determines in writing, based on competent evidence, that the proposed development area does not qualify as a sensitive area under this chapter with respect to the proposed site specific development.~~
- ~~3. The city's official maps shall be amended from time to time by the director to clarify to location of sensitive lands districts in the city, as reasonably deemed appropriate by the director based on competent evidence. Determinations by the director under this subsection shall be made in consultation with the DRC and such other qualified consultants as the director may deem appropriate.~~
- ~~4. All approved subdivision plats that lie wholly or partially in a sensitive lands district shall be recorded with such designation shown on the official plat.~~

~~B. Supplemental and Conflicting Provisions. Unless otherwise specifically provided, the regulations contained in this chapter are in addition to the standards applicable to the underlying zones, or overlay zones, provided elsewhere in this title or any other applicable title, code, ordinance or law. In the event of conflict between the standards, guidelines and criteria of this chapter and the requirements of the underlying zoning district, the city's subdivision ordinance or any other requirements of this code, the more restrictive provision shall apply.~~

~~C. Geologic hazard studies. Project developers and their consultants shall present the results of geologic hazard studies in compliance with this chapter and its appendices. The standards set forth in the appendices to this chapter are the city's minimum requirements, but may be made more stringent (in specific, fact sensitive circumstances) by the DRC based on recommendations of the city engineer or city geologist if evidence becomes available that suggests more stringent requirements are appropriate. In addition, the appendices shall not supersede other more stringent requirements that may be required by other regulatory agencies or governmental entities that have jurisdiction.~~

~~D. Appendix A. Appendix A presents study area maps reflecting geological, hydrologic, infrastructure and other natural and man-made hazard concerns, as well as supplemental maps pertaining to development in the city's sensitive lands districts. The maps incorporate data obtained from numerous publications, previous geologic hazard studies and other expert sources such as FEMA, UGS, USGS, AGRC, etc. Updated versions of the maps will be added as they become available.~~

E. Appendix B.

- ~~1. Appendix B presents the minimum standards for surface fault rupture hazard studies conducted in the city and describes the accepted minimum requirements~~

~~for planning, conducting and reporting the results of surface fault rupture hazard studies. Site specific surface fault rupture hazard studies performed by qualified engineering geologists shall be required prior to developing projects located in the Surface Fault Rupture Hazard Study Area as delineated on Map 1 in Appendix A of this chapter. The information contained in Appendix B was compiled from numerous published and unpublished sources and presents the current standard of care for surface fault rupture hazard studies in the city.~~

- ~~2. The requirements of Appendix B are subject to modification at any time by the city as recommended by the DRC. If, due to additional evidence, a surface fault rupture hazard becomes known or suspected in an area subject to a development application, which hazard is not depicted on the Surface Fault Rupture Hazard Study Area Map, the DRC shall require the developer to submit applicable studies as recommended by the city engineer and the city geologist and the process outlined in this chapter shall be followed.~~

F. Appendix C:

- ~~1. Appendix C presents the minimum standards for slope stability and landslide hazard studies conducted in the city and describes the accepted minimum requirements for planning, conducting and reporting the results of slope stability and landslide hazard studies. Site specific slope stability and landslide hazard studies performed by qualified engineering geologists and geotechnical engineers shall be required prior to developing projects located in the Slope Stability and Landslide Hazard Study Area as delineated on Map 2 in Appendix A of this chapter. The information contained in Appendix C was compiled from numerous published and unpublished sources and presents the current standard of care for slope stability and landslide hazard studies in the city.~~
- ~~2. The requirements of Appendix C are subject to modification at any time by the city as recommended by the DRC. If, due to additional evidence, a slope stability and/or landslide hazard becomes known or suspected in an area subject to a development application, which hazard is not depicted on the Slope Stability and Landslide Hazard Study Area Map, the DRC shall require the developer to submit applicable studies as recommended by the city engineer and the city geologist and the process outlined in this chapter shall be followed. At a minimum, a special, site specific slope stability analysis is required for all development in zones with moderate to very high hazard of landslides (Map 2).~~

G. Appendix D:

- ~~1. Appendix D presents the minimum standards for liquefaction hazard studies conducted in the city and describes the accepted minimum requirements for planning, conducting and reporting the results of liquefaction hazard studies. Site specific liquefaction hazard studies performed by qualified engineering geologists and geotechnical engineers shall be required prior to developing projects located in the Liquefaction Hazard Study Area as delineated on Map 3 in Appendix A of this chapter. The information contained in Appendix D was compiled from numerous published and unpublished sources and presents the current standard of care for liquefaction hazard studies in the city.~~
- ~~2. The requirements of Appendix D can be modified at any time by the city as recommended by the DRC. If, due to additional evidence, a liquefaction hazard~~

becomes known or suspected in an area subject to a development application, which hazard is not depicted on the Liquefaction Hazard Study Area Map, the DRC shall require the developer to submit applicable studies as recommended by the city engineer and the city geologist and the process outlined in this chapter shall be followed. At a minimum, a special, site-specific liquefaction hazard analysis is required for all development in zones of moderate to high liquefaction potential (Map 3) for the following International Building Code (IBC) occupancy groups: Assembly Group A, Business Group B, Factory Group F-1, Educational Group E, High Hazard Group H, Institutional Group I, and Residential Groups R-1, R-2, and R-4.

H. Appendix E.

1. Appendix E presents the minimum standards for debris flow/alluvial fan flooding hazard studies conducted in the city and describes the accepted minimum requirements for planning, conducting and reporting the results of debris flow/alluvial fan flooding hazard studies. Site-specific debris flow/alluvial fan flooding hazard studies performed by qualified engineering geologists and geotechnical engineers shall be required prior to developing projects located in the Debris Flow/alluvial fan flooding Hazard Study Area as delineated on Map 4 in Appendix A of this chapter. The information contained in Appendix E was compiled from numerous published and unpublished sources and presents the current standard of care for debris flow/alluvial fan flooding hazard studies in the city.
2. The requirements of Appendix E can be modified at any time by the city as recommended by the DRC. If, due to additional evidence, a debris flow/alluvial fan flooding hazard becomes known or suspected in an area subject to a development application, which hazard is not depicted on the Debris Flow/Alluvial Fan Flooding Hazard Study Area Map, the DRC shall require the developer to submit applicable studies as recommended by the city engineer and the city geologist and the process outlined in this chapter shall be followed. At a minimum, a special, site-specific debris flow/alluvial fan flooding hazard analysis is required for all development in zones with moderate to high debris flow/alluvial fan flooding hazard (Map 4).

I. Appendix F.

1. Appendix F presents the minimum standards for rockfall hazard studies conducted in the city and describes the accepted minimum requirements for planning, conducting and reporting the results of rockfall hazard studies. Site-specific rockfall hazard studies performed by qualified engineering geologists and geotechnical engineers shall be required prior to developing projects located in the Rockfall Hazard Study Area as delineated on Map 5 in Appendix A of this chapter. The information contained in Appendix F was compiled from numerous published and unpublished sources and presents the current standard of care for rockfall hazard studies in the city.
2. The requirements of Appendix F can be modified at any time by the city as recommended by the DRC. If, due to additional evidence, a rockfall hazard becomes known or suspected in an area subject to a development application, which hazard is not depicted on the Rockfall Hazard Study Area Map, the DRC

shall require the developer to submit applicable studies as recommended by the city engineer and the city geologist and the process outlined in this chapter shall be followed. At a minimum, a special, site-specific rockfall hazard analysis is required for all development in zones with moderate to high rockfall hazard (Map 5).

~~J. Appendix G. Appendix G presents the source protection zones that require special regulations for the storage, handling, use or production of hazardous or toxic substances in order to protect, preserve and maintain existing and future public drinking water sources. The source protection zones are generally located upgradient of wells or near proposed points of diversion for the development of groundwater. Groundwater recharge zones are located in permeable and/or sensitive areas that have a critical impact on the groundwater quality and quantity of supply. The protection of source protection zones and groundwater recharge areas is essential to the health, safety and welfare of city residents and visitors. At a minimum, observations of excavations will be required in the following instances:~~

~~1. Observations of excavations by qualified engineers and/or geologists for all development within active fault special study zones (Map 1), areas with moderate to very high slope stability hazard (Map 2), areas with moderate to high liquefaction potential (Map 3), and areas with groundwater at depths of less than ten feet (Map 11).~~

~~2. Observations of excavations by qualified engineers and/or geologists for all development, even outside of the zones specified above, for the following IBC occupancy groups: Assembly Group A, Educational Group E, High-Hazard Group H, Institutional Group I, and Residential Groups R-1, R-2, and R-4.~~

~~K. Appendix H. Appendix H presents the foundation excavation observations that are required for all new structures or additions that are built in the city. The DRC shall require the owner to submit a foundation excavation observation report, prepared in accordance with the process outlined in this chapter, prior to the construction of any structural footing or foundation for all buildings in the city.~~

~~L. Appendix I. Appendix I presents the riparian corridor and watershed protections adopted to minimize erosion and stabilize stream banks, improve water quality, preserve fish and wildlife habitat, regulate stream temperatures, reduce potential for flood damage, preserve natural aesthetic value of streams and protect the prime groundwater recharge areas of the city. These requirements are intended to provide protection for the following above-ground streams, stream corridors and recharge areas: Little Cottonwood Creek and its tributaries, Big Cottonwood Creek and its tributaries, foothill drainage basins and Ferguson Canyon. Where these streams flow through areas that are already developed, the riparian corridor and watershed protection requirements are intended to achieve a reasonable balance between natural streams and developed land uses.~~

19.72.030-020 Definitions

As used in this chapter:

“*Acceptable and reasonable risk*” means no loss of or significant injury to occupants, no release of hazardous or toxic substances, and ~~structural damage but no collapse of structures~~minimal

structural damage to buildings or infrastructure during a hazard event allowing occupants egress outside.

“*Accessory building*” means any structure not designed for human occupancy, which may include detached garages with no habitable space, tool or storage sheds, gazebos, and swimming pools. Accessory dwelling units and businesses located in accessory buildings must comply with all requirements for buildings designed for human occupancy.

“*Activity class of faults*” means the activity level of a fault is based on the latest Western States Seismic Policy Council policy recommendation defining surface faulting (<https://www.wsspc.org/public-policy/adopted-recommendations/>). Currently, Policy Recommendation 21-3 states that based on the time of most recent movement: latest Pleistocene-Holocene faults are defined as movement in the past 15,000 years, late Quaternary faults are defined as movement in the past 130,000 years, and Quaternary faults are defined as movement in the past 2,600,000 years. “*Active fault*” means a fault displaying evidence of displacement along one or more of its traces during Holocene time, which is approximately 10,000 years ago to the present.

“*Alluvial fan*” means a fan shaped deposit where a fast-flowing stream flattens, slows, and spreads, typically at the exit of a canyon onto a flatter plain.

“*AGRC*” means the Utah State Automated Geographic Reference Center.

“*Avalanche*” means a large mass of snow, ice, soil, organic debris, or rock, or a mixture of these materials, falling, sliding, or flowing rapidly down a hillside or mountainside under the force of gravity.

“*Buildable area*” means that, based on an accepted engineering geology report, the portion of a site not impacted by geologic hazards, or the portion of a site where it is concluded the identified geologic hazards can be mitigated to a level where risk to human life, property and city infrastructure is minimized and where structures may be safely sited. Buildable areas must be clearly marked on approved site plans and/or final approved plats, as appropriate.

“*City*” means the city of Cottonwood Heights and its public works director, city engineer, community development director, planning manager, building official, or other Cottonwood Heights officer, employee, or agent, as applicable.

“*City council*” means the Cottonwood Heights city council.

“*Cluster development*” means development in which a number of dwelling units are placed in closer proximity than usual, or are attached, with the purpose of retaining or enlarging an open space area.

“*Community development department*” means the city’s community and economic development department.

“*Conservation area*” means an area that has high open space value for recreation, aesthetic and/or biological purposes. Conservation areas have the highest priority of protection from development.

“*Critical facilities*” means essential, hazardous, special occupancy facilities, and ~~Occupancy Risk~~ Categories III and IV as defined in the currently adopted International Building Code, and lifelines such as major utility, transportation, and communication facilities and their connections to critical facilities.

“*Curriculum vitae*” or “*CV*” means a written account of the professional life comprising one’s education, accomplishments, work experience, publications, etc.

“*Debris flow*” means a slurry of rock, soil, organic material, and water transported in an extremely fast and destructive flow down channels and onto and across alluvial fans; including a continuum of sedimentation events and processes such as debris flows, debris floods, mudflows, clear-water floods, sheet flooding, and alluvial-fan flooding.

“*Development*” means all critical facilities, subdivisions, single- and multi-family dwellings, commercial and industrial buildings; also additions to or intensification of existing buildings, storage facilities, pipelines and utility conveyances, roads, and other land uses.

“*Development review committee*” or “*DRC*” means a committee of city staff members that reviews proposed development projects for compliance with this code, consisting of the director and others designated from time to time by the director ~~and approved by the city council~~, such as the city engineer, one or more of city planning staff members, the city’s fire inspector, a representative of the city’s public works ~~provider~~department, the city attorney, and/or others.

“*Director*” means the director of the city’s community and economic development department.

“*Engineering geologist*” or “*geologist*” means a Utah-licensed geologist, who, through education, training, and experience, practices in the field of engineering geology and geologic hazards meeting the qualification standards of this ordinance.~~is competent in applying geologic data, geologic techniques, and geologic principles, which includes conducting field investigations, so that geologic conditions and geologic factors affecting engineered works, ground-water resources, and land-use planning are recognized, adequately interpreted, and clearly presented for use in engineering practice, land-use planning, and for the protection of the public, and who utilizes specialized geologic training and experience to provide quantitative geologic information and recommendations and also works with and for land-use planners, environmental specialists, architects, public policy makers, and property owners to provide geologic information on which decisions can be made.~~

“*Engineering geology*” means geologic work that is relevant to engineering and environmental concerns, and the public health, safety, and welfare. Engineering geology is the application of geological data, principles, and interpretation ~~so that geological factors~~ affecting the planning, design, construction, and maintenance of engineered works, land use planning and ground-water

~~issues, resources are adequately recognized and properly interpreted for use in engineering, land-use planning, and related practice.~~

“*Essential facility*” means buildings and other structures intended to remain operational in the event of an adverse catastrophic event, including all structures ~~defined in Table 4~~ with an occupancy greater than 1,000 shall also be considered IBC Risk Category III when not meeting the criteria for IBC Risk Category IV; and IBC Risk Category IV buildings and other structures are designated as essential (critical) facilities.

“*Fault*” means a fracture in the earth’s crust forming a boundary between rock and/or soil masses that have moved relative to each other, due to tectonic forces. When the fracture extends to the Earth’s surface, it is known as surface fault rupture, or a fault trace.

~~“*Fault scarp*” means a steep slope or cliff formed by movement along a fault.~~

“*Fault setback*” means ~~an area~~ area specified distance on either side of a fault within which structures for human occupancy or critical facilities ~~or~~ and their structural supports are not permitted.

~~“*Fault scarp*” means a steep slope or cliff formed by movement along a fault.~~

“*Fault trace*” means the intersection of a fault plane with the ground surface, often present as a fault scarp, or detected as a lineament on aerial photographs or other imagery.

“*Fault zone*” means a corridor of variable width along one or more fault traces, within which ground deformation of soil and rock units has occurred due to movement of the fault traces as a result of fault movement.

“*FEMA*” means the Federal Emergency Management Agency.

“*Geologic hazard*” means a geologic condition that presents a risk to life, of substantial loss of real property, or of substantial damage to real property and includes, but not limited to surface fault rupture, liquefaction, landslides, slope stability, debris flows, rockfalls, avalanches, radon gas, and other hazards (see Utah Code 10-9a-103(18)). ~~surface fault rupture, liquefaction, slope instability, landslide, debris flow, rock fall, or other geologic process or condition that may present a risk to life or property.~~

“*Geologic hazard study area*” means a potentially hazardous area as defined in this chapter, including hazard areas as shown on the geologic hazard study area maps within which hazard investigations are required prior to development.

“*Geotechnical engineer*” means a professional, Utah-licensed engineer who, through education, training, and experience, is competent in the field of geotechnical or geological engineering meeting the qualification standards of this chapter.

“*Geotechnical engineering*” means the investigation and engineering evaluation of earth materials including soil, rock, and man-made materials and their interaction with earth retention systems, foundations, and other civil engineering works. The practice involves the fields of soil mechanics, rock mechanics, and earth sciences and requires knowledge of engineering laws, formulas, construction techniques, and performance evaluation of engineering.

“*Governing body*” means the Cottonwood Heights city council or its designee.

“*Hazardous fault*” means a fault with movement in the past 2,600,000 years (Quaternary).

“*Infrastructure*” means improvements which are required to be installed and guaranteed in conjunction with an approved subdivision or other land use approval. Infrastructure may be public or private, on site or off site, depending on development design, and may include streets, curb, gutter, sidewalk, water and sanitary sewer lines, storm sewers, flood control facilities, and other similar facilities.

“*Improvement*” means any building, structure, fence, gate, wall, landscaping, planted tree, work of art, or other man-made physical feature of real property, or any part of such feature which is not a natural feature.

“*Landslide*” means the down-slope movement of a mass of soil, surficial deposits, and/or bedrock, including a continuum of processes between landslides, earth-flows, debris flows, ~~and~~ debris avalanches, and rock falls.

“*Liquefaction*” means a sudden, large decrease in shear strength of a saturated, cohesionless soil (generally sand and silt) caused by a collapse of soil structure and temporary increase in pore water pressure during earthquake ground shaking. May lead to ground failure, including lateral spreads and flow-type landslides. ~~process by which certain water-saturated soils lose bearing strength because of earthquake-related ground shaking and subsequent increase of groundwater pore pressure.~~

“*Natural drainage channel*” means naturally occurring features such as open swales, open channels, or open creek beds that help collect and convey stormwater over natural terrain to a determinate downstream point of discharge.

“*Natural feature*” means any naturally-occurring tree, plant life, habitat, or geological site or feature, but does not include improvements.

“*Non-buildable area*” means a site that has any portion thereof within a geologic special study area where a geologic hazards investigation has not been conducted, a site where known or readily apparent geologic hazards exist in an area subject to a development application, which area is not depicted on the geologic hazards study area where a geologic hazards investigation has not been conducted, or that portion of a site which a geologic hazards report has concluded may be impacted by geologic hazards that cannot be reasonably mitigated to an acceptable level, and where the siting of habitable structures, structures requiring a building permit, or critical facilities, is not permitted.

“*Open space*” means those areas of a subdivision, planned unit development, condominium or other type of land use project that are not occupied by structures, paved parking areas, paved roadways, or similar improvements. Open space is contiguous land set aside for environmental protection and/or passive or active recreation purposes, or to preserve environmentally sensitive or riparian areas. Open space may include parkland, play areas, walkways, trails, informational and interpretive centers or similar facilities for active or passive use, and may be private, communal, or a combination thereof. Open space may be formally landscaped or retained with natural vegetation.

“*Retention area*” means an area that is designed to catch runoff water.

“*Rockfall*” means a rock or mass of rock, newly detached from a cliff or other steep slope which moves down-slope by falling, rolling, toppling, or bouncing; includes rockslides, ~~rock fall and~~ rockfall avalanches, and talus.

“*Sensitive development*” means any land use that maintains the character of the native landscape and natural or cultural resources that define the area.

“*Sensitive lands*” or “*sensitive area*” means retention areas, conservation areas, and any other land within a sensitive lands district or which qualifies for inclusion in a sensitive lands district as provided in this chapter.

“*Sensitive lands district*” or “*sensitive lands overlay*” means any designated overlay area published on an official map by the city which describes a sensitive area or special study zones. The sensitive lands district or overlay identifies properties that require additional study to determine the existence of geologic conditions that may be hazardous to public health, safety or welfare. An official sensitive lands overlay map, as shown in Appendix A, shall be approved by the city council and shall be on record with the city. Sensitive lands overlay maps may also be available on the web at the city’s official website.

“*Setback*” means an area subject to risk from a geologic hazard within which foundation elements that support habitable structures or critical facilities is not permitted.

“*Slope stability*” means the resistance of a natural or artificial-constructed slope or other inclined surface to failure by landsliding, ~~usually~~-assessed under both static and dynamic (earthquake-induced) conditions.

~~“*Snow avalanche*” means a mass of predominantly snow and ice, but also including a mixture of soil or rock and organic debris, falling, sliding, and/or flowing rapidly down a hillside or mountainside under the force of gravity.~~

“*Special study zone*” refers to an area within the vicinity of a potential or known fault zone(s) that warrant study to determine the feasibility of development in compliance with the regulations as outlined in Appendix B.

“*Standard of care*” means that a professional such as an architect, a landscape architect, an engineer, a geologist, or a land surveyor is required to use the same degree of learning, care and skill ordinarily used by other professionals of the same type, under like circumstances, in the same or similar locality and time as where the subject professional services were provided.

“*Structure designed for human occupancy*” means any residential dwelling or any other structure used or intended for supporting or sheltering any use or occupancy by humans or businesses, including all Risk Category II structures as defined in the currently adopted International Building Code, but does not include an accessory building which houses no accessory dwelling unit or business. which is expected to have an occupancy rate of at least 2,000 person hours per year.—

“*SWPPP*” means a storm-water pollution prevention plan, conducted in accordance with appropriate standards, as determined by the city and the Utah Pollutant Discharge Elimination System (UPDES).

“*Talus*” means rock fragments lying at the base of a cliff or a very steep rocky slope.

“*Terrain adaptive architecture*” means a system of architectural design where buildings step down steeply sloping sites and hillsides to create the least amount of disturbance to the slope and the least amount of visual impact from lower lying vantage points.

~~“*Talus*” means rock fragments lying at the base of a cliff or a very steep rocky slope.~~

“*Trail*” means a system of public recreational pathways located within the city for use by the public.

“*UGS*” means the Utah Geological Survey.

“*Unpublished sources*” means maps, documents, consultant’s reports, or other data produced by credible scientific or professionally licensed individuals or entities that have not been published in publicly or generally available formats.

“*USGS*” means the United States Geological Survey.

“*Wet stamp*” or “*seal*” means the official hallmark of an engineer, surveyor or other licensed professional that is reproduced, via ink or embossing, on plans, plats, ~~studies~~studies, or the like prepared by such professional or under his direction, to prove its authenticity and/or to confirm its accuracy, or electronic equivalent.

19.72.030 Conflict Regulations

Unless otherwise specifically provided, the regulations contained in this chapter are in addition to the standards applicable to the underlying zones, or overlay zones, provided elsewhere in this title, code, ordinance, or law. In cases of conflict between the standards, guidelines and criteria of this chapter and the requirements of the underlying zoning district, the city’s subdivision

ordinance, or any other ordinance of Cottonwood Heights City, the more restrictive provision shall apply.

19.72.040 Applicability

The provisions of this chapter shall apply to all lands located in Cottonwood Heights City. Every legal lot of record and lot in a proposed land subdivision within a geologic hazard study area as defined by this chapter, must have a buildable area safe for the intended use. Each buildable area must also have access from the nearest existing public or private street which is free of unreasonable and unacceptable geologic hazards. Any geologic hazards which must be mitigated in order to provide a buildable area with acceptable and reasonable access must be mitigated prior to issuance of the final plat recordation.

Detached accessory buildings that are not designed for human occupancy are not required to comply with the provisions of this chapter. In addition, the remodeling of existing structures designed for human occupancy may occur without compliance with this chapter, if no expansion of the existing structure footprint, foundation, and no structure use change is proposed. Complete or substantial demolition and replacement of structures shall comply with this chapter.

As defined in the currently statewide adopted 2018 International Building Code (IBC), Table 1604.5, the city considers IBC Risk Category III buildings and other structures to represent a substantial hazard to human life in the event of failure, except that any structure with an occupancy greater than 1000 shall also be considered IBC Risk Category III when not meeting the criteria for IBC Risk Category IV; and IBC Risk Category IV buildings and other structures are designated as essential (critical) facilities.

19.72.040-050 Development Standards And Controls

Compliance with the development standards and controls of this chapter shall be required in connection with all structures and construction on sensitive lands; provided, however, that the development standards and controls contained in this chapter shall not circumvent or diminish the zoning controls of underlying zoning designations. Instead, the development standards and controls in this chapter are intended to, and shall, enhance the city's regulatory control regarding building and development surrounding and within sensitive lands.

A. Slopes.

1. No development, including structures and retaining walls, is permitted on Sslope areas in excess of 30% ~~may not be developed~~, with the following exception:

a. Slope areas in excess of 30% may be developed upon finding that:

i. The slope area is smaller than one (1.00) acre in size;

ii. The slope is not part of a larger, contiguous slope that exceeds 30 percent;

iii. Their disturbance or removal will not create unstable geologic or drainage conditions that result in damage to public or private property; and

iv. The city engineer has approved a site-specific slope stability study performed by qualified engineering geologists and geotechnical engineers which meets all the requirements of this chapter.

b. This exception (1a) shall not apply to natural slope areas in excess of 30% east of Wasatch Blvd., as determined by the director.

2. and nNo more than 30% of a development's slope areas in excess of 30% may be included in the area calculation to determine residential density.

A.a. The planning commission, upon analyzing a conditional use application or other land use proposal following a recommendation of the DRC, may modify this requirement to include no more than 50% of the slope in excess of 30% toward density calculations upon finding that:

1.i. No significant or moderate harm will result;

2.ii. The proposed modification will result in a materially more functional and improved plan;

iii. Conditions or requirements are reasonably imposed by the planning commission to mitigate any adverse effects which may result from the proposed modification;

iv. The development shall be considered to lie within a moderate or greater slope stability hazard area and a site-specific slope stability study shall be performed by qualified engineering geologists and geotechnical engineers which meets all the requirements of this chapter;

3.v. The development shall meet the requirements of all other sections of this title, the city's building code and all other applicable ordinances; and

4.vi. If reasonably requested by the city in compliance with applicable legal standards for, inter alia, development exactions, the applicant developer agrees to dedicate as open space any portion of the project that is not developable under this title.

B. Single Family Lots. For developments containing single family lots, the minimum lot size and yard requirements of the underlying zone shall apply, with the following exceptionsadditional requirements:

1. Every lot shall have at least 3,500 square feet of buildable area, consisting of the area of the lot where the slope is 30% or less, which is completely contiguous and which has a minimum dimension of 50 feet in both length and width. Setback area cannot be counted toward buildable area requirements.

2. Lots shall be designed to allow dwelling units to be located within 250 feet from a public or private street. All main and accessory buildings shall be built entirely within the buildable area.

C. Density Limitations.

1. The density limitations of the underlying zoning district shall control residential density.

2. The planning commission shall not adjust other zoning controls related to bulk and massing, including increased maximum structure height.

D. Maximum Impervious Surface. The total maximum allowable coverage by impervious material within the sensitive lands portion of a project shall not exceed 30% of the area of those sensitive lands. Areas of roofs and private driveways will be estimated and included in the total impervious surface area. In areas where geologic hazards can be mitigated through a reduction in surface water infiltration, the maximum allowable coverage by

impervious material shall follow the recommendations of an approved geotechnical report.

- E. Grading, ~~d~~Drainage, and ~~E~~rosion ~~C~~ontrol. The area of the watershed shall be used to determine the amount of storm water runoff generated before and after construction.
1. A grading and drainage report shall be prepared in which the developer-applicant shall describe the methods intended to be employed to control the erosion increase while in construction.
 2. The developer-applicant is responsible for interim stabilization of all disturbed areas during periods of construction to prevent erosion offsite effects, and for final stabilization once construction is completed.
 3. The SCS, Curve Number Method, or Rational Method, or other storm-water computation method as approved by the city engineer, shall be used in computing runoff.
 4. Lots shall be arranged so as to ensure adequate setbacks from drainage channels. The 100-year storm event shall be that basis for determining the minimum flood elevation.
 5. Existing natural drainage channels shall remain as historically located except that roads and utilities may be installed across such channels as approved by the city engineer. Where these channel modifications are planned, the developer-applicant shall obtain applicable state Division of Water Rights and U.S. Army Corps of Engineers permits. The developer-applicant shall provide evidence of such permits to the city.
 6. Facilities for the collection of storm-water runoff shall be constructed on the development sites and according to the following requirements:
 - a. Such facilities shall be the first improvements or facilities constructed on the development site.
 - b. Such facilities shall be designed so as to detain safely and adequately the maximum expected storm-water runoff for a 100-year storm event while allowing an offsite discharge not to exceed one tenth (0.1) cubic foot per second per acre.
 - c. Such facilities shall be so designed so as to divert surface water away from cut faces or sloping surfaces of a fill.
 - d. The existing drainage system, including natural drainage channels, shall be utilized to the greatest extent practicable, as directed-approved by the city engineer.
 - e. Where drainage channels are required, wide shallow swales lined with appropriate vegetation, rock, or other ~~approved~~-material approved by the city engineer shall be used instead of cutting narrow, deep drainage ditches. Flow retarding devices, such as detention ponds, check dams, and recharge berms, shall be used where practical to minimize increases in runoff volume and peak flow rate due to development.
 7. Construction on a development site shall be of a nature that will minimize the disturbance of vegetative cover.
 8. Erosion control measures on a development site shall minimize increased suspended solids loading in runoff from such areas. A drainage system design to

control storm-water erosion during and after construction shall be contained in a detailed grading and drainage report submitted by the ~~developer~~applicant.

9. No grading or stripping shall be permitted except as part of a development plan approved in advance by the DRC pursuant to this chapter.
- F. Cut and Fill Slopes. Cut and fill slopes shall comply with the following unless otherwise recommended in an approved soils and geology report:
1. Cut and fill slopes shall not exceed 12 feet.
 2. Cut and fill slopes shall not exceed a slope ratio of 2H:1V ~~except and shall be further restricted~~ as follows:
 - a. No slopes shall be cut steeper than the bedding plane, fracture, fault or joint in any formation where the cut slope will lie on the dip of the strike line of the fracture, bedding plane, fault or joint.
 - b. No slopes shall be cut in an existing landslide, mud flow or other form of naturally unstable slope.
 - c. If the material of a slope is of such composition and character as to be unstable under the anticipated maximum moisture conditions, the slope angle shall be reduced to a stable value or increased through retention using a method recommended in a soils and geology report approved by the city engineer ~~and certified as to its stability by a professional soils engineer~~.
 3. Fill slopes shall not be constructed on natural slopes steeper than 2H:1V.
 4. Roadway cut and fill slopes located outside the dedicated public right-of-way shall be within recorded easements providing for slope protection and preservation. The easements shall be in a form acceptable to the city.
- G. Earthwork. Earthwork shall comply with the following unless otherwise recommended in an approved geotechnical report.
1. All surface areas to receive fill shall be stripped of any surface vegetation, topsoil, and organics and cleared of any trash and debris that may be present at the time of construction.
 2. After the site has been cleared and stripped, the exposed subgrade soils in those areas to receive fill shall be scarified to a depth of eight inches.
 3. Unless otherwise recommended in an approved geotechnical report, Aall fill material shall be earth materials that are free from organic material, (less than 30% by volume) and other deleterious materials as well as free of metal, concrete, asphalt and other construction debris, or engineered recycled or engineered fill materials approved by a qualified geotechnical engineer. Imported fill material should be a non-expansive (less than 2% swell) granular materials and should not contain rocks or lumps over 6-inches in greatest dimension and not more than 15% of the material larger than 2½ inches.
 4. Surface areas disturbed by trench excavations shall be contained within the limits of the development or within approved rights-of-way, except as may be necessary in order to comply with Occupational Safety and Health Administration requirements and as approved by the city engineer. Trench boxes shall be used whenever required to ensure compliance with this requirement.

5. Unless otherwise recommended in an approved geotechnical report, the following compaction criteria shall be met for filling operations based on ASTM test designation 698-78D1557:

<i>Description</i>	<i>Compaction Effort</i>
Subgrade <u>Structural fill beneath footings</u>	95%
Structural fill <u>beneath concrete flatwork</u>	97% <u>90%</u>
Trench backfill	95%
Trench backfill (top 12 inches beneath pavement or concrete)	97%
Basement wall backfill	90%

Fill material shall be spread and compacted in uniform horizontal lifts not exceeding eight inches in uncompacted thickness. Before compaction begins, the fill shall be brought to within $\pm 2\%$ ~~+~~ of the optimum moisture content. Each lift should be thoroughly mixed before compaction to ensure a uniform distribution of moisture.

6. All structures shall bear on well compacted documented structural fill material or firm, undisturbed natural soil. No organic material, mud, muck, frozen material, or ponded water shall be allowed in the footing foundation.
 7. A written summary report of the completed compaction, showing location and depth of tests, materials used, moisture-density curves, moisture contents and relative density (if appropriate), prepared, signed and stamped by a civil engineer, geotechnical engineer, or soils engineer shall be submitted to the city engineer for review.
 8. The city engineer may require additional tests or information if the results of his review indicate that the conditions or materials are such that additional information is necessary.
- H. Setbacks. The setbacks and other restrictions specified by this subsection are a minimum, and may be increased by the city if necessary for safety and stability, to prevent damage of adjacent properties from deposition or erosion, or to provide access for slope maintenance and drainage. Setbacks dealing with distances from property lines, structures or faults, and must satisfy the requirements of the following paragraphs. Retaining walls may be used to reduce the required setbacks when approved by the city.
1. Setbacks from property lines shall comply with most restrictive requirements that are applicable under this title, ~~and~~ the city's building code, and all other applicable ordinances.
 2. Setbacks between graded slopes (cut or fill) and structures shall comply with this title, the city's building code and all other applicable ordinances.
 3. No habitable structure, essential facility, or critical facility shall be located over a fault. Determinations of the appropriate setback distance from ~~the a hazardous~~ fault shall be made using data obtained in the geological report by the person or firm who prepared the geological report, but in no case shall this distance be less than 20-15 feet.
- I. Vegetation and Re-vegetation.

- ~~1. All areas on development sites cleared of natural vegetation in the course of construction of offsite improvements shall be replanted with drought tolerant vegetation which has good erosion control characteristics.~~
- ~~2. The use of persons or firms having expertise in the practice of re-vegetation (i.e., licensed landscape architects, erosion control specialists or nurserymen) shall approve the planning and installation of vegetative cover.~~
- ~~3.1.~~ Vegetation shall be removed only when absolutely necessary, e.g., for the construction of buildings, roads and filled areas.
- ~~4.2.~~ No vegetation shall be removed on a continuous hillside, crest (upslope or downslope) or a slope 30% or greater unless otherwise determined by the planning commission upon recommendation of the DRC.
- ~~3.~~ Any re-vegetation method of a trail, open space or hillside shall be subject to the approval of the city engineer.
4. A vegetation plan shall be submitted for any development activity which involves the removal of existing vegetation. The vegetation plan shall be stamped by a licensed landscape architect. This plan shall include the following for both vegetation which is to be removed and vegetation which is to be added:
 - i. Species
 - ii. Location
 - iii. Quantity
 - iv. Irrigation
- ~~5.~~ Irrigation systems shall be designed and maintained so as not to spray excess water onto sidewalks, right-of-way, or other extraneous areas.
- ~~5.6.~~ Species which are drought tolerant and aid in erosion control are encouraged wherever possible, but are required in areas of development that have been cleared of natural vegetation.
- ~~6.7.~~ Topsoil removed during construction shall be conserved whenever practicable for later use on areas requiring vegetation or landscaping (i.e., cut and fill slopes).
- ~~7.8.~~ All disturbed soil surfaces shall be stabilized or covered prior to November 1st. If the planned impervious surfaces (i.e., road, driveways, etc.) cannot be established prior to November 1st, a temporary treatment adequate to prevent erosion shall be installed on those surfaces.
- ~~8.9.~~ The property owner and/or developer shall be fully responsible for any destruction of native or applied vegetation identified as necessary for retention and shall be responsible for such destroyed vegetation. They shall carry the responsibility both for employees and subcontractors from the first day of construction until the final acceptance of improvements. The property owner and developer shall replace all destroyed vegetation with varieties of vegetation approved by the DRC. The property owner shall assume co-responsibility with the developer upon purchase of the property.

J. Geology.

1. No habitable structure or critical or essential infrastructure shall be built on or within ~~20-15~~ feet of any identified hazardous fault. Actual setbacks shall be determined through the process outlined in Appendix B.
2. No structures or off-site improvements shall be allowed on any active landslide area as determined by the ~~C~~city ~~E~~ngineer.

3. Problems associated with development on or near perched ~~ground water~~ and/or shallow ground-water must be mitigated in a manner as approved by the ~~planning commission~~ city engineer.
- K. Fire Protection. Development shall comply with the following unless otherwise recommended by the fire department.
1. A full building permit shall be issued only when the water system is completed and operational to provide fire protection.
 2. Each development site proposal and building permit application shall be reviewed by the fire department to assure compliance with the city's fire code. Non-compliant developments shall not be approved.
 3. Spark arresters shall be installed in every fireplace, whether constructed indoor or outdoor. The diameter of screen openings in such arresters shall not exceed ¼ inch.
 4. Development adjacent to public lands shall provide access for fire protection vehicles and equipment.
 5. A development in a sensitive lands district shall not ~~require~~ allow the use of wood shake shingles or wood exterior siding, regardless of whether or not such materials have been treated with fire retardant.
- L. Streets and Ways. Streets, roadways, and private access ways shall follow as nearly as possible the natural terrain. The following additional standards shall apply:
1. At least one ingress and one egress route shall be provided for each subdivision or PUD project, unless there is a crash gate or the extension of a future stub street that will provide additional access.
 2. Points of access shall be provided to all developed and undeveloped areas for emergency and fire-fighting equipment. Driveways located upon each lot extending from a public or private street shall have sufficient width and design to admit and accommodate fire-fighting equipment and must comply with all applicable city standards.
 3. Cul-de-sacs shall not exceed 600 feet in length and shall have a fire-department-approved turnaround with a back of curb line radius of at least 55 feet. Stub-streets that are longer than the width or length of any adjacent single lot or 200 feet, whichever is less, shall have a temporary turnaround at the end thereof.
 4. Centerline curvatures shall not be less than a 100-foot radius on any curved street pattern.
 5. Variations of the street design standards developed to solve special hillside visual and functional problems may be presented to the planning commission for consideration and approval. Examples of such variations may be the use of split roadways to avoid deep cuts, one-way streets, modifications of surface drainage treatments, sidewalk design, or the extension of a cul-de-sac.
 6. Development sites which are located near canyon trails ~~will~~ shall provide public access to those trails. Public parking areas may be required by the planning commission at trail heads.
 7. Developments adjacent to public lands shall provide for access to those public lands by fire protection equipment.
 8. ~~The maximum amount of impervious surface for streets and roadways shall be 20% of the entire development site, or shall follow more stringent~~

~~recommendations of the city engineer and/or city geologist, reviewed on a case-by-case basis.~~

8. Developments shall provide ample pedestrian and vehicle connectivity.

9. All streets or rights-of-way for vehicular traffic shall be subject to the following limitations:

~~a. The maximum grade of such streets or rights-of-way shall be 12% except as hereafter provided.~~

~~b.a.~~ The provisions of this subsection shall not apply to streets or rights-of-way already constructed or which have heretofore been granted preliminary approval by the planning commission.

~~e.b.~~ Roads shall be designed to meet the city's road base, asphalt, and compaction standards.

M. Trails ~~u~~Upon ~~h~~Hillsides.

1. The subdivider or other developer shall dedicate and improve to city standards trails necessary to provide public access to public lands and other trails shown on city or county master plans or required by the planning commission. Trails shall be located so that the route is feasible for both construction and long-term maintenance; side slopes shall not exceed 70% and rock cliffs and other insurmountable physical obstructions shall be avoided. The specific location of the trail right-of-way shall be verified on the ground before approving the subdivision.

2. A trail may be constructed to access upper/lower portions of residential property subject to the following conditions:

a. No ~~unn~~non-engineered cut or fill of the hillside shall be in excess of four feet. All cuts or fills shall be properly retained.

~~b. The trail shall follow a meandering course, and not use a direct line pathway to the desired location.~~ Where possible, the trail should follow the natural contours of the hillside.

c. Where topographic conditions allow, the grade of trails generally shall not exceed 12%. Trails, and retainage of adjacent slopes, shall be designed as directed-approved by the city engineer.

d. New trails shall be planned to harmonize with nature, including minimizing the destruction of existing stands of vegetation.

e. New trails shall include the installation of bridges across natural drainages with permanent or temporary flow that cannot be crossed without entering the drainage.

f. The trail shall be appropriately landscaped with native materials.

g. Prior to construction and/or hillside cuts, the trail plan shall be submitted to the director and city engineer for review and approval.

N. Architectural Design. Architectural controls are primarily regulated by underlying zoning districts; however, the architectural requirements of this chapter include the following as determined by the city's architectural review commission ("ARC") ~~and planning commission~~:

1. The design of buildings and structures proposed for construction shall be visually compatible with the natural beauty of the foothills and canyon areas and other surrounding sensitive lands.

2. The materials used for buildings, structures and fences shall blend harmoniously with the natural setting.
 - ~~3. The planning commission may review the design and comment on the specified exterior materials and colors for all structures.~~
 - 4.3. Exposed foundation walls shall not exceed four feet above finished grade at any point, unless otherwise recommended in an approved geotechnical report.
 - 5.4. The design and construction of structures within the urban interface area shall be consistent with the 2006-most current edition of the Utah Wildland-Urban Interface Code, as amended.
- O. On-Site Development. The property owner and developer shall be fully responsible for making all improvements in accordance with the development site approval, e.g., drainage, erosion, and vegetation requirements.
- P. Bond. In addition to the requirements of this code requiring the posting of a completion bond for a development, the developer or owner shall be required to guarantee (via a cash bond, cash escrow or bank letter of credit, all in such form as city may require) the completion of re-vegetation projects, the stabilization of grading sites, cuts and fills, construction of storm-water runoff facilities, and the construction of recreation space as required in this code. Such bond shall be in an amount equal to 110% of the city's estimate of the cost of construction of such work, and shall continue for 12 months after the completion date of all such project, improvements or facilities.
- Q. Flooding and FEMA. All habitable living space for new construction shall be at least one foot above the 100-year flood plain elevation. Any addition to an existing structure that includes any additional square feet shall meet this requirement.
- R. Protection of Subsurface Infrastructure. All new utilities or existing facilities located within a proposed subdivision and that cross a major-hazardous fault or located in areas that are prone to ground shifting shall be equipped with a flexible expansion joint that is capable of withstanding the maximum anticipated offset as a result of settling or seismic displacement as required by the city. The flexible expansion joint for liquid carrying utilities shall be an integrated cast ball and socket type joist-joint with expansion sleeves and have a minimum 2:1 safety factor with a 350-psi pressure rating and meet USA factory certifications, as per the city engineer, unless otherwise recommended in an approved geotechnical report.
- R.S. Subdivision Plats. All approved subdivision plats that lie wholly or partially in a sensitive lands district shall be recorded with such designation shown on the official plat.

19.72.050-060 Responsibility For Geologic Hazard And Other Studies

- ~~A. All applicants wishing to develop and/or build on sensitive lands shall provide, at their own expense, all applicable geologic, geotechnical or other studies outlined in this chapter and as directed by the DRC pursuant to Section 19.72.020.~~
- B.A. Geologic hazard studies of surface fault rupture, slope stability and landslide, liquefaction, debris flow, and rock fall hazards often require both engineering geology and geotechnical engineering expertise. Engineering geologic studies shall be performed under the direct supervision of a qualified licensed engineering geologist, qualified as provided in Section 19.72.060, and gGeotechnical engineering studies shall be performed under the direct supervision of a qualified licensed geotechnical engineer, qualified as provided in Section 19.72.060. All plans submitted to the city shall be stamped by a

~~licensed geotechnical engineer and/or engineering geologist, as the case and standard of care may warrant, appropriately licensed and in good standing with the state of Utah.~~

~~C.B.~~ When analyzing a conditional use application or other land use proposal, ~~the DRC, the city or the planning commission upon recommendation of the DRC,~~ may, based on an initial geologic and/or geotechnical study, ~~from time to time~~ require that additional studies related to the sensitive lands being developed be completed to address additional geologic hazards ~~issues~~ that may include, without limitation, hydrology, snow avalanche, wildlife habitat, ecology, etc. All additional studies shall be completed by a city-approved expert in the particular field of study.

19.72.060-070 Minimum Acceptable Qualifications Of ~~Professionals~~ The Engineering Geologist

~~A. Minimum acceptable qualifications of the engineering geologist.~~ Engineering geology and the evaluation of geologic hazards is a specialized discipline within the practice of geology requiring technical expertise and knowledge of techniques not commonly used in other geologic disciplines. Therefore, geologic hazard investigations involving engineering geology ~~ie studies~~ shall only be accepted by ~~the city~~ the city when conducted, signed, and stamped by a qualified engineering geologist. The minimum qualifications of the engineering geologist who performs geologic hazard investigations of sensitive lands in the city are:

A. An undergraduate or graduate degree in geology, engineering geology, or geological engineering, or closely related field, from an accredited college or university.

B. Five (5) full years of experience in a responsible position in the field of engineering geology in Utah, or in a state with similar geologic hazards and regulatory environment. This experience must demonstrate the engineering geologist's knowledge and application of appropriate techniques in performing geologic hazard studies.

~~1.C.~~ An active, current Utah State Professional Geologist's license.

~~2.D.~~ In good standing with the Division of Professional and Occupational Licensing of the Utah Department of Commerce.

~~3. Demonstrated competence in the specified field as evidenced by a current CV provided to the city for review and approval.~~

B. 19.72.080 Minimum Acceptable Qualifications Of a The gGeotechnical eEngineer.

Evaluation and mitigation of geologic hazards often require contributions from a qualified geotechnical engineer, particularly in the design of mitigation measures. Geotechnical engineering is a specialized discipline within the practice of civil engineering requiring technical expertise and knowledge of technique not commonly used in civil engineering. ~~in geotechnical engineering.~~ Therefore, geologic hazard investigations requiring contributions from a qualified geotechnical engineer will only be accepted by ~~the city~~ the city when also ~~conducted,~~ signed and stamped by a qualified geotechnical engineer. Minimum qualifications of a geotechnical engineer who participates in geologic hazard investigations of sensitive lands in the city are:

A. A Graduate degree in geological or civil engineering, with an emphasis in geotechnical engineering; or a B.S. degree in civil engineering with twelve (12) semester hours of post-B.S. credit in geotechnical engineering, or course content related to evaluation of geologic hazards, from an accredited college or university.

B. Five (5) full years of experience in a responsible position in the field of geotechnical engineering in Utah, or in a state with similar geologic hazards and regulatory environment, and experience demonstrating the engineer's knowledge and application of appropriate techniques in participating in geologic hazard studies.

~~1.C.~~ An active, current Utah State Professional Engineer's license.

~~2.D.~~ In good standing with the Division of Professional and Occupational Licensing of the Utah Department of Commerce.

~~3. Demonstrated competence in the specified field as evidenced by a current CV provided to the city for review and approval.~~

C. 19.72.090 Minimum acceptable qualifications of other professionals.

~~From time to time the DRC, or the planning commission upon recommendation of the DRC, The city may require additional studies of additional geologic hazards to evaluate issues that may include, but are not limited to without limitation, hydrology, wildlife habitat, ecology, vegetation, snow avalanche, etc. The DRC city shall determine the adequacy of the qualifications of professionals performing additional studies based upon the following minimum standards:~~

~~1.A.~~ An active, current Utah State professional license in the specified field and in good standing with the Division of Professional and Occupational Licensing of the Utah Department of Commerce; or,

B. Where a license from the Utah Division of Professional & Occupational Licensing is not available:

2.1. Demonstrated competence in the specified field as evidenced by a current CV provided to the city for review and approval, showing extensive study in the specified field, experience performing the specified studies and professional competence; and

3.2. Professional certification obtained through a reputable national organization such as LEED, AIA, AICP, ASLA or other applicable equivalent acceptable to the city.

19.72.070-100 Procedure Preliminary Activities

~~Proposals for building or development on sensitive lands shall follow the procedure set forth in this section, which shall consist of four distinct parts: (1) scoping study; (2) conceptual proposal/ disturbance permit request; (3) preliminary proposal; and (4) final approval. Applications for review by the city shall be filed and processed in the following order:~~

~~A. Development Improvements. This section shall apply to any geologic hazard investigation for the purpose of determining the feasibility of development or for the purpose of exploring, evaluating, or establishing locations for permanent improvements.~~

~~A.~~

~~B. Scoping Pre-application Meeting. The developer applicant or consultant shall schedule a scoping pre-application meeting with the DRC city to evaluate the investigative approach of the engineering geologist/geotechnical engineer. At this meeting, the consultant shall present a work plan that includes locations of anticipated geologic hazards and locations of proposed exploratory excavations, such as test pits, trenches, borings, and cone penetrometer test (CPT) soundings, which, at a minimum, meet the minimum standards of practice. The investigation approach should allow for flexibility due to unexpected site conditions. Field findings may require modifications to the work~~

plan. Upon ~~successful completion of the~~ completion of a successful scoping meeting, an application for a disturbance permit may be submitted to the city.

B.

C. Land Disturbance Permit. No person shall commence or perform any land disturbance, grading, relocation of earth, or any other land disturbance activity on sites greater than or equal to one acre in size or on sites smaller than an acre that are part of a larger development, without first obtaining a land disturbance permit. Application for a land disturbance permit shall be filed with the city engineer on forms furnished by the city for such purposes only after a scoping meeting has taken place.

A. ~~Conceptual proposal/disturbance permit applications.~~

1. Proposals for surveying, testing or other design-related activities requiring physical entry into areas located within a sensitive lands district shall be submitted to the DRC for review and modification, approval or denial. Prior to review by the DRC, the areas of proposed disturbance shall be staked at the applicant's expense. Following staking, the city engineer or city geologist shall have at least two business days to observe the staking.
2. Thereafter, the DRC, upon receiving a favorable recommendation from the city engineer and geologist, may authorize issuance of a grading permit to allow access to, and permit testing of, the approved areas.
3. The permit shall be limited to the staked area of proposed disturbance and may include conditions deemed appropriate by the DRC to protect sensitive areas. As dictated by the DRC, such conditions may include requirements for the following:
 - a. Photo documentation to identify pre-existing types and general locations of vegetation which may need to be protected or replaced.
 - b. The submission of a SWPPP for the implementation of adequate erosion control measures to protect affected areas. Supplemental erosion control measures may also be required between initial disturbances and either construction of permanent improvements or restoration and re-vegetation of the disturbed area.
 - c. Limitations on cuts and fills to ensure that they are made only where necessary to obtain access for required testing.
 - d. Requirements for restoration and re-vegetation of disturbed areas where permanent improvements are not constructed within one year following the disturbance.
 - e. A land disturbance bond (cash bond, cash escrow or bank letter of credit, all in such form as city may require) to cover the expense of re-vegetating disturbed areas and returning graded areas to their natural state.
 - f. Any other reasonable requirement to mitigate the effect of potential interruption caused by the disturbance of the area for conceptual or preliminary activities.
4. The conceptual plan shall include the following information; provided, however, that the DRC may reasonably modify the following requirements:
 - a. A conceptual development map, drawn at a minimum scale of 1"=100', which shows:
 - 1) One or two foot contours;

- 2) Natural slopes of 30% or greater color shaded;
 - 3) Proposed development layout of lots, roads, schools, churches, parks, open space, fire stations, commercial, cut or fill slopes or areas of disturbance, and any other proposed land use;
 - 4) Labeling of any roads with grades in excess of eight percent; and
 - 5) Native vegetation, by type and location.
- b. A report which indicates:
- 1) Total development area;
 - 2) Total area with over 30% slope
 - 3) Number of lots or units proposed;
 - 4) Proposed density calculation;
 - 5) Evidence of compliance with city stormwater requirements;
 - 6) Percentage of each use, such as residential, commercial, recreational, transportation, etc.; and
 - 7) Statement of compliance with the design requirements of this chapter.
- c. A re-vegetation plan addressing restoration plans for areas disturbed by preliminary activities.

~~B.D.~~ Preliminary assessment and mitigation. Following conceptual approval, preliminary approval of a hazard assessment plan shall be sought from the planning commission or the community development department, as applicable. The information and reports required in this subsection are outlined in the appendices to this chapter; shall be submitted as part of an application for preliminary approval; and may be in addition to information otherwise required for preliminary approval for a subdivision or PUD, or a permit for a conditional or permitted use.

~~C.E.~~ Final approval of assessment and mitigation measures. Final approval of hazard assessment and mitigation measures shall be issued by the community development department if the applicant demonstrates satisfactory compliance with all of the requirements of this chapter and compliance with all city requirements for final plat approval, PUD approval and/or conditional use approval, as applicable. All bonding requirements of this code also shall be satisfied prior to the issuance of the final approval by the community development department.

~~D.F.~~ Reclamation plan procedure. Any land disturbance in sensitive areas, including test pits, re-grading or alteration of vegetation shall require a reclamation plan. The reclamation plan shall include information about the existing site, the scope of the disturbance, compaction requirements, drainage, impact to native vegetation, slope stabilization, site security, erosion control measures, revegetation, long term measures to mitigate the proposed impact and any other measures that impact the ability to restore the property to a stable, long term condition. If failure to follow the reclamation plan jeopardizes the safety of the property or results in impact to another property, the city may require a bond, as determined by the DRC.

19.72.080-110 Geologic Hazards Study Area Maps

A. Geologic hazard study areas in Cottonwood Heights City are defined as, but are not necessarily limited to:

1. Cottonwood Heights City geologic hazards study area maps;

2. Designated Special Study areas by the Utah Department of Natural Resources, Utah Geological Survey (UGS), including those areas around hazardous faults in the *Utah Geologic Hazards Portal*, *Earthquake Hazards*, *Hazardous Faults layer*, and *Utah Quaternary Fault and Fold Database*;
3. Geologic units designated as Qm, Qms, Qms1, Qmsy, Qmso, Qmc, Qmg, Qac, Qay, Qg, Qga, Qgy, Qgmy, Qgo, Qgao Qgm, Qgmo, Qmdf, Qaf, Qafy, Qafo, Qaf1, Qaf2, Qaf3, Qaf4, Qaf5, Qafb, Qafp, Qafoe, Qgr, Qmtr, Qmy, Qct, and Tn on the most recent geologic maps published by the UGS;
4. Landslide hazard areas defined as:
 - a. Low, moderate, and high landslide susceptibility areas as identified in UGS Map M-228: *Landslide Susceptibility Map of Utah*;
 - b. Landslide areas identified in the UGS *Utah Landslide Database*; and
 - c. Areas where slopes are in excess of 30 percent and those requiring slope stability analyses as defined in this chapter;
5. All properties located on alluvial fans and those with drainage channels subject to flash flooding and/or debris flows;
6. Other areas where the topography; geology, including soils and bedrock conditions, either on the subject property or adjacent indicate the presence of geologic hazards; and other previously identified geologic hazards that the city finds to be of significance to the health, safety, and welfare of the citizens of Cottonwood Heights City; and
7. Site-specific surface-fault-rupture investigations are required for all critical facilities and structures for human occupancy (International Building Code [IBC] Risk Category II, III, and IV) along latest Pleistocene-Holocene faults and for critical facilities (IBC Risk Category IV) along late Quaternary and Quaternary faults. For noncritical facilities for human occupancy (IBC Risk Category II and III) along late Quaternary and Quaternary faults, investigations are recommended, but not required. See the UGS *Utah Geologic Hazards Portal*, *Earthquake Hazards*, *Hazardous Faults layer* and *Utah Quaternary Fault and Fold Database* to locate Quaternary age faults within Cottonwood Heights City and to determine their activity class.

A.B. ~~Geologic hazards study area maps. Appendix A of this chapter contains the geologic hazards study area maps and other supplemental maps (the “Appendix A maps”) applicable to identified sensitive lands in the city. The Appendix A maps are prepared using the best available scientific information, but are necessarily generalized and designed only to indicate areas where hazards may exist and where geologic hazards studies are required. Because such maps are prepared at a non-site-specific scale, geologic hazards may exist that are not shown on the maps. The fact that a site is not shown in a geologic hazards study area for a particular hazard does not exempt the applicant from considering the hazard if evidence is found that it may exist. It is the responsibility of the applicant to consider and identify all geologic hazards on the subject site. If it is subsequently determined that the site has geologic hazards or other features that are not shown on the Appendix A geologic hazards study area maps, the review process will be pursuant to this chapter.~~

B.C. ~~Geologic hazards study area boundaries: Boundaries shown on the Appendix A geologic hazards study area maps will not be systematically adjusted as each individual~~

site-specific study indicates whether or not an actual hazard exists at the site. Geologic hazards study area maps ~~and other supplemental maps~~ are meant only to define areas within the city where scientific evidence indicates a hazard may exist. However, ~~the Exhibit A geologic hazards study area~~ maps may be updated and amended by the city if found to be inaccurate or ~~erroneous in error~~, or as new methods or data are developed to better define areas of potential hazards.

~~C.D. Modification of geologic hazards study area and supplemental maps.~~ Where geologic hazards study area maps are thought by an applicant to be inaccurate or ~~erroneous in error~~ and require revision, the applicant shall submit to the city technical evidence by a qualified professional supporting the claim and showing the proposed revision. The ~~DRC-city~~ will review the information and render a decision. The applicant may appeal that decision ~~to the city's appeals hearing officer as provided in Chapter 19.92 of this title by following the appeals process contained in this chapter.~~

19.72.090-120 Geologic Hazard Studies And Reports Required

A. Any applicant requesting development approval on a parcel of land within a geologic hazard study area or where there are known or readily apparent geologic hazards and the area is not depicted on the geologic hazards study area maps, sensitive lands shall submit to the city ~~five paper copies and one electronic copy~~ of a site specific geologic hazard study report that specifically relates to the geologic hazards present on and adjacent to the site that may affect the site, for such land meeting the requirements of Appendices B-G of this chapter.

~~B. Applicants who are required to complete site-specific geological hazards tests shall be directed by the city regarding the scope of the required studies and tests through the conceptual proposal/disturbance permit process outlined in this chapter.~~

~~C.B.~~ A foundation excavation report or observation report must be submitted to the city's building department for all new construction on sensitive lands. This report shall show that the developer or applicant has complied with all requirements and recommendations (included those in previous geotechnical reports that have been conducted for the subject property); shall show any geologic hazards found after excavation but prior to footing and foundation construction; and shall be certified by a licensed geotechnical engineer or engineering geologist as required by this chapter.

19.72.130 Building Permits on Lots Recorded Prior to the Effective Date of These Ordinances

A. The following submittals and processes are required prior to the issuance of a building permit for a new or replacement structure designed for human occupancy and additions to structures designed for human occupancy for all legal lots of record recorded prior to the effective date hereof which are on property noted as restricted for geologic hazard reasons on a recorded plat or within designated geologic hazard study areas:

1. A statement from an engineering geologist identifying the presence or absence of any geologic hazards and describing the buildable area on the lot for the proposed structure;
2. A statement from a geotechnical engineer verifying that the slope stability of the proposed structure location will have a ≥ 1.1 dynamic (pseudostatic) and ≥ 1.5 static factor of safety. The statement shall clearly identify the anticipated

conditions, such as the seismic ground acceleration and pseudostatic coefficients used, and any required mitigation methods to achieve the required factors of safety;

3. A statement from a Utah-licensed professional structural engineer stating that they have reviewed the geologic and geotechnical reports, which may be combined into one report, and that they have designed the structure in accordance with the report recommendations, accounting for any identified geologic and geotechnical hazards in accordance with the currently statewide adopted International Building Code and related standards;
 4. Written verification from the consultant's issuer of professional errors and omissions liability insurance, in the amount of \$2,000,000.00 per consultant, which covers the licensed professional engineering geologist, geotechnical engineer, and structural engineer, and which are in effect on the date of issuance of the building permit by the city;
 5. A hold harmless agreement, on a city approved form, which is executed and recorded on the subject property;
 6. A geologic hazards disclosure, on a city approved form, which is executed and recorded on the subject property; and
 7. All conditions of the currently adopted statewide building and fire codes must be adhered to.
- B. Prior to the issuance of a certificate of occupancy for a new or replacement structure designed for human occupancy, and additions to structures designed for human occupancy for all parcels recorded prior to the effective date hereof, and which are within a Geologic Hazards Study Area:
1. An excavation inspection report shall be submitted by a geotechnical engineer to the city prior to footing placement, which verifies that the proposed building was in accordance with the recommendations of the geologic and geotechnical reports, which may be combined into one report;
 2. The city may require, at any time, written verification from a geotechnical engineer or a Utah-licensed professional structural engineer, that the structure conforms to the recommendations of the original reports and designs, and if not, provides appropriate as-built drawings documenting the changes; and
 3. All requirements of the currently statewide adopted Utah State Construction and Fire Codes Act must be met.

19.72.100-140 Geologic Hazard Reports

- A. Upon a determination by the DRC of the scope of geologic or other hazard studies required by an applicant, the applicant, at its expense, shall provide the city with a site-specific report consistent with the requirements of this chapter that identifies~~Each geologic hazards report shall be site-specific consistent with the requirements of this chapter and shall identify~~ all known or suspected geologic hazards, on the site, whether originating on-site or off-site, ~~and~~ whether previously identified or previously unrecognized, that may affect the subject property. All geologic hazard reports shall include the original signature and ~~wet stamp~~professional seal of the qualified professional ~~geotechnical engineer or engineering geologist~~. A geologic hazard report may be combined with a geotechnical report and/or contain information on multiple hazards.

Geologic hazards reports co-prepared by professional geologists and engineers must include the original signature and wet stamp of both professionals.

B. A field review by the city is required during subsurface exploration activities (test pits, trenches, drilling, etc.) to allow the city to evaluate the subsurface conditions, such as the age and type of deposits encountered, the presence or absence of landslides and faults, etc. with the applicant's consultant. Discussions about questionable features or appropriate setback distances are appropriate, but the city will not assist with field logging, explaining stratigraphy, or give approval of the proposed development during the field review. Exploratory trenches when excavated, shall be open, safe, and in compliance with applicable federal Occupational Safety and Health Administration, State of Utah, and other excavation safety regulations, have the walls appropriately cleaned, and a field log completed by the time of the review. The applicant must provide a minimum notice of 2 days to the city for scheduling the field review.

~~A.~~

~~B. The scope of the development and the potential for hazards to exist on a sensitive lands property, as determined by the DRC in consultation with the city engineer and city geologist, shall govern which of the following studies must be completed in connection with a development application (the specific requirements for the performance of such studies are found in the appendices to this chapter):~~

~~1.C. Surface fault rupture hazard report (Appendix B). Surface fault rupture hazard reports shall contain all requirements described in “Appendix B, Minimum Standards for Surface Fault Rupture Hazard Studies” of this chapter, ~~Minimum Standards for Surface Fault Rupture Hazard Studies~~. Surface fault rupture studies shall be conducted by a qualified engineering geologist.~~

~~2.D. Slope stability and landslide hazard reports (Appendix C). Slope stability and landslide hazard reports shall contain all requirements described in “Appendix C, Minimum Standards for Slope Stability Hazard Analysis”, of this chapter, ~~Minimum Standards for Slope Stability Hazard Studies~~. Slope stability and landslide studies shall be conducted by a qualified engineering geologist, a qualified geotechnical engineer.~~

~~3.E. Liquefaction hazard reports (Appendix D). Liquefaction hazard reports shall contain all requirements described in “Appendix D, Minimum Standards for Liquefaction Hazard Investigations and Evaluations”, of this chapter, ~~Minimum Standards for Liquefaction Hazard Studies~~. Liquefaction analyses shall be conducted by a qualified geotechnical engineer. Liquefaction investigations are not required for residential construction classified in the International Residential Code as R-3.~~

~~4.F. Debris flow hazard reports (Appendix E). Debris flow hazard reports shall contain all requirements described in “Appendix E, Minimum Standards for Debris Flow Hazard Analyses”, of this chapter, ~~of this chapter, Minimum Standards for Debris Flow Hazard Studies~~. Debris flow hazard investigations shall be conducted by a qualified engineering geologist. Mitigation measures will generally require contributions from geotechnical engineers, hydrologists, or civil engineers.~~

~~5. Rockfall hazard reports (Appendix F). Rockfall hazard reports shall contain all requirements described in “Appendix F, Minimum Standards for Rock-Fall Hazard Analyses”, of this chapter, ~~of this chapter, Minimum Standards for Rock-Fall Hazard Studies~~. Rockfall studies shall be conducted by a qualified engineering geologist.~~

Mitigation measures will generally require contributions from geotechnical and/or civil engineers.

- ~~6. Foundation excavation observation reports (Appendix H). Foundation excavation observation reports shall contain all requirements described in Appendix H of this chapter, Minimum Standards for Foundation Excavation Observation Reports. Foundation observation reports shall be conducted by a qualified geotechnical engineer or engineering geologist. A foundation excavation observation report is required as a condition to issuance of all building permits in sensitive lands areas.~~
- C.G. In addition to the requirements of the aforementioned reports, all geologic hazards reports shall meet the submittal and preparation requirements of this chapter, UGS Circular 122: Guidelines for Investigating Geologic Hazards and Preparing Engineering-Geology Reports, With a Suggested Approach to Geologic-Hazard Ordinances in Utah, Chapter 2, and shall include, at a minimum the following:
1. A one to twenty-four thousand (1:24,000)-scale geologic map, with references, showing the general surface geology (landslides, rockfall, alluvial fans, etc.), bedrock geology where exposed, bedding attitudes, faults, ~~and~~ other geologic structural features, and the location of any other known geologic hazards;
 2. A detailed site geologic map and geologic cross section(s) of the subject area, at a scale equal to or more detailed than one inch equals ~~200~~ 100 feet (1":100'), showing the locations of subsurface investigations and site-specific geologic mapping performed as part of the geologic hazard investigation, including boundaries and features related to any geologic hazards, topography, and drainage. The site geologic map must show the location and boundaries of the property, geologic hazards, delineation of any recommended setback distances from hazards, and recommended locations for structures. Buildable and non-buildable areas shall be clearly identified;
 3. Trench and test pit logs, when applicable, prepared in the field and presented in the geologic hazard report with standard geologic nomenclature at a scale equal to or more detailed than one inch equals five feet (1":5'). Field logs shall be kept by the consultant and may be requested by the city for further review during the project;
 4. Boring logs, when applicable, prepared with standard geologic and engineering nomenclature and format;
 5. Listing of aerial photographs used and other supporting information, as applicable;
 6. Conclusions and recommendations, clearly supported by adequate data included in the report, that summarize the characteristics of the geologic hazards, and that address the potential effects of the geologic conditions and geologic hazards on the proposed development and its occupants, particularly in terms of risk and potential damage;
 7. Specific recommendations for additional or more detailed studies, as may be required to understand or quantify a geologic hazard;
 8. An evaluation of whether ~~or not~~ mitigation measures are required, including an evaluation of multiple, viable mitigation options that include specific recommendations for avoidance or mitigation of the effects of the hazards, consistent with the purposes set forth in this chapter, including design or

performance criteria for engineered mitigation measures and all supporting calculations, analyses, modeling or other methods, and assumptions. Final design plans and specifications for engineered mitigation must be signed and stamped by a qualified, Utah-licensed engineer (specializing in geotechnical or civil) and/or structural engineer, as appropriate;

9. Specific recommendations for avoidance or mitigation of the effects of the hazards, consistent with the purposes set forth in this chapter, including design or performance criteria for engineered mitigation measures and all supporting calculations, analyses, modeling or other methods, and assumptions. Final design plans and specifications for engineered mitigation must be signed and stamped by a qualified geotechnical, civil and/or structural engineer, as appropriate;
10. All data upon which recommendations and conclusions are based shall be clearly stated in the report;

11. A statement shall be provided by the engineering geologist regarding the suitability of the proposed development from a geologic hazard perspective; and

~~11.12.~~ All geologic hazard reports shall be signed and stamped by the Utah-licensed professional(s) that prepared the reports in accordance with Utah Code 58-76-603 (Professional Geologists) and 58-22-603 (Professional Engineers).

~~12. Identification of all utilities that serve the proposed development, including design and specifications of flexible expansion joints for utility lines that cross any fault line(s).~~

H. When a submitted report does not contain adequate data to support its findings, additional or more detailed studies shall be required to explain or quantify a particular geologic hazard or to describe how mitigation measures recommended in the report are appropriate and adequate.

~~D.I.~~ When a final geologic hazard report indicates that a geologic hazard does not exist within an adopted geologic hazard study area indicated by a map referenced by this article, the city will consider the new geologic information in potentially revising the adopted hazard maps to remove the specific area from the adopted geologic hazard study area.

19.72.150 Submittal of Geologic Hazard Reports

A. All applicants for land use approval within a geologic hazard study area shall prepare and submit a geologic hazard report (may be combined with geotechnical and/or other geologic reports) pursuant to the requirements of this article prior to any consideration for a concept plan; preliminary or final plat; commercial, institutional, or one-, two-, and multi-family dwelling; or any conditional use permit which requires site plan approval. The applicant is required to submit the following additional information with the report:

1. A written, stamped certification from a Utah-licensed professional geologist that the geologic hazard report has been prepared pursuant to the requirements of this chapter;
2. A written, stamped certification from a Utah-licensed professional geologist and a professional engineer that every proposed development lot, building pad, and parcel does not present an unreasonable or unacceptable risk to the health, safety, and welfare of persons or property, including buildings, storm drains, public streets, culinary water facilities, utilities, or critical facilities, whether off site, on adjacent properties, or on site, because of the presence of geologic hazards or because of modifications to the site due to the proposed land use;

3. A written, stamped certification from a Utah-licensed professional geologist and a professional engineer that every proposed development lot, building site, and parcel layout demonstrates that, consistent with regional standards of practice, the identified geologic hazards can be mitigated to a level where the risk to human life and damage to property are reduced to an acceptable and reasonable level in a manner which will not violate applicable federal, state, and local statutes, ordinances, and regulations. Mitigation measures shall consider in their design, the intended aesthetic functions of other governing ordinances of the city;
4. A written, stamped certification from a Utah-licensed professional geologist and a professional engineer along with a mitigation plan, if necessary, that demonstrates that the identified hazards or limitations will be addressed without impacting or adversely affecting off site areas, including adjacent properties. Mitigation measures must be reasonable and practical to implement and shall not require ongoing maintenance by property owners; and
5. Written verification from the issuer of professional errors and omissions liability insurance, in the amount of \$2,000,000.00 each, which covers the Utah-licensed professional geologist and professional engineer, and which are in effect on the date of preparation and submittal of all required reports and certifications.

19.72.110-160 Review Of Geologic Hazard Reports

- A. The city shall review any proposed land use which requires preparation of a geologic hazards report under this chapter to determine the possible risks to the safety of persons, property, and city infrastructure from geologic hazards.
- B. Prior to consideration of any request for ~~rezoning~~, preliminary plat approval, conditional use approval and/or site plan approval of property, the required geologic hazard reports shall be submitted to the city for review.
- C. The city will endeavor to complete each review in a reasonable time frame within forty-five (45) days.~~act diligently in reviewing each submitted geologic hazard report.~~
- D. All direct costs associated with the review of geologic hazard reports shall be paid by the applicant ~~through the application fee~~.
- E. The city shall retain a copy of each geologic hazard report in the community development department's project file.
- F. The city shall determine whether the report complies with all of the standards set forth in this chapter, including the following:
 1. ~~That s~~Suitable geologic hazard reports have been prepared by qualified, Utah-licensed professionals.
 2. ~~That t~~The proposed land use does not present an unreasonable risk to the health, safety, and welfare of persons or property, including buildings, storm drains, public streets, culinary water facilities, utilities or critical facilities, whether off-site or on-site, or to the aesthetics and natural functions of the landscape, such as slopes, streams, other waterways, drainage, or wildlife habitat, whether off-site or on-site, because of the presence of geologic hazards or because of modifications to the site due to the proposed land use.
 3. ~~That t~~The proposed land use demonstrates that, consistent with the state of the practice, the identified geologic hazards can be mitigated to a level where the risk to human life and damage to property are reduced to an acceptable and reasonable

level in a manner which will not violate applicable federal, state, or local statutes, ordinances, or regulations. Mitigation measures should consider, in their design, the intended aesthetic functions of other governing ordinances. The applicant must include with the geologic hazards reports a mitigation plan that defines how the identified hazards or limitations will be addressed without impacting or adversely affecting off-site areas. Implementation of mitigation measures must be reasonable and practical to implement, especially if such measures require on-going maintenance by property owners.

3.4. Should a geologic report be found deficient with respect to this chapter and/or the current, regional state of practice, a letter will be provided to the applicant summarizing the specific deficiencies. If a submitted report is found deficient three times or a report was excessively deficient, the city may notify the Utah Division of Occupational & Professional Licensing about the licensed professional(s) deficient reports that were submitted to a public entity that were not in compliance with Utah Rules R156-76-502 (Professional Geologists) and/or R156-22-502 (Professional Engineers).

- G. The city may set other requirements that it deems necessary to mitigate any geologic hazards and to ensure that the purposes of this chapter are met. These other requirements may include, without limitation, the following:
1. Additional or more detailed studies-investigations and professional certifications to understand or quantify the hazard and/or determine whether mitigation measures recommended in the report are adequate;
 2. Specific mitigation requirements, establishing buildable and non-buildable areas, limitations on slope grading, ~~and~~ controls on grading, and/or re-vegetation;
 3. Grading plans, when required, shall be prepared, signed, and sealed by a Utah-licensed professional engineer. As built grading plans, when required, shall be signed and sealed by the project geotechnical engineer as well as the professional engineer that prepared the grading plans. Grading plans, when required, shall include, at a minimum, the following: ~~which include the following, as required by the DRC:~~
 - a. Maps of existing and proposed contours and the source and accuracy of topographic data used;
 - b. Present and proposed slopes for each graded area;
 - c. Existing and proposed drainage patterns;
 - d. Location and depth of all proposed cuts and fills;
 - e. Description of methods to be employed to achieve soil and/or rock stabilization and compaction, as appropriate;
 - f. Location and capacities of proposed drainage, structures, and erosion control measures based on maximum runoff for a 100-year storm or greater;
 - g. Location of existing buildings ~~or~~, structures, roads, wells, retention and other basins, and on-site sewage disposal systems on or within 100 feet of the site, ~~or which that~~ may be affected by the proposed grading and construction; and
 - h. Plan for monitoring and documentation of testing, field inspections during grading, and reporting to the city.:-

4. Installation of monitoring equipment and seasonal monitoring of surface and subsurface geologic conditions, including ground-water levels; and
5. Other requirements such as time schedules for completion of the mitigation and phasing of development.

~~H. All information shall be submitted as an original signed, wet stamped document for the city's use, such as, making additional copies as deemed necessary, distribution to the public, review by other professionals or use by other parties that have an interest in the property. All information shall also be submitted in a digital format as directed by the city for use in the city's infrastructure database, GIS, CADD archives or other digital platform for city business, or for recordation at the Salt Lake County Recorder's office.~~

~~H.~~ As a condition of approval of any development of sensitive lands which requires a geologic hazards report, the city may also set additional requirements ~~as it deems~~ necessary to protect the health, safety, and welfare of its residents, protect the city's infrastructure and financial health, and minimize potential adverse effects of geologic hazards to public health, safety, and property.

~~J.I.~~ The city may require ~~a qualified professional~~ the engineering geologist and geotechnical engineer that prepared the geologic hazard and/or geotechnical report(s) to be on site, at the ~~developer's applicant's~~ cost, during certain phases of development and construction, particularly during grading phases ~~and,~~ the construction of retaining walls, and geologic hazard mitigation. For any real property being developed based on a geologic hazard and/or geotechnical report which has been accepted by the city, no final inspection shall be completed, certificate of occupancy issued, or performance bond released until the geotechnical engineer or engineering geologist who signed, stamped, and approved such report certifies in writing that the completed improvements and structures conform to the descriptions and requirements contained in such report, and that all the required inspections were made and approved by the engineering geologist and geotechnical engineer that prepared said report(s). If the preparing engineering geologist and geotechnical engineer are unavailable, an engineering geologist and geotechnical engineer, similarly qualified and licensed in Utah, shall provide the certifications.

~~K.J.~~ An applicant may appeal any decision made under the provisions of this chapter only after the city has issued a written review of a report. The city's appeals hearing officer shall serve as the appeal authority for any dispute under this chapter. Any such appeal shall set forth the specific grounds or issues upon which the appeal is based. The appeal shall be submitted in writing to the ~~city's appeals hearing officer~~ director -within 30 days after the city's issuance of the written review or other decision that is the subject of such appeal. The city may assemble a professional panel of three (3) qualified experts to assist the appeal authority for any technical dispute. The panel shall consist of an expert designated by the city, an expert designated by the applicant, and an expert chosen by the city's and the applicant's designated experts. If the city's and the applicant's designated experts cannot reach a consensus of the third expert within thirty (30) days, the city shall select the third expert. The costs of the appeal process shall be paid by the applicant.

19.72.120-170 Disclosure When A Geologic Hazard Report Is Required

- A. Whenever a geologic hazard report is required under this chapter, the owner of the affected site parcel shall record a signed, notarized disclosure notice, running with the

land, in a form satisfactory to the city prior to the city's approval of any development or subdivision of such ~~land~~parcel or commencement of construction activity. The recorded disclosure shall include the following:

1. Notice that the ~~land~~parcel is located within a geologic hazards study area as shown on the geologic hazards study area map or as otherwise defined in this chapter; and
 2. Notice that a geologic hazards report was prepared and is available for public inspection in the city's files.
- B. Where geologic hazards ~~and~~, related setbacks, and non-buildable areas are delineated in a subdivision, the owner shall also place additional notification on the plat stating the above information, prior to final approval and recording of the plat.

19.72.130-180 Warning And Disclaimer

~~The~~The city's geologic hazards study area maps represent only those potentially hazardous areas known to the city and should not be construed to include all possible potential hazard areas. This chapter and the geologic hazards study area maps referenced herein may be amended by the city as new information becomes available pursuant to procedures set forth in this chapter. The provisions of this chapter do not in any way assure or imply that areas outside the geologic hazards study area maps boundaries are free from the possible adverse effects or risk of geologic hazards. This chapter shall not create any liability on the part of ~~the~~the city or any of its officers, employees, reviewers, consultants, agents or contractors for any damages from geologic hazards that result from reliance on this chapter, or any administrative requirement or decision lawfully made hereunder.

19.72.140-190 Change Of Use

No change in use which results in the conversion of a building or structure from one that is not used for human occupancy to one that is so used ~~for human occupaney~~ shall be permitted unless the building or structure complies with the provisions of this chapter.

19.72.150 Conflicting Regulations

~~In cases of conflict between this chapter and the provisions of existing zoning classifications, building code, subdivision ordinance, or any other ordinance of the city or applicable law, the most restrictive provision shall apply.~~


19.72.160-200 Maps And Appendices


Click to view a PDF of the maps and appendices for Chapter 17.72.

APPENDIX A

Geologic Hazards Study Area Maps

(Final maps to be included in PDF format)





0 900 1,800 3,600 5,700 7,600 Feet
 1 inch = 3,000 feet
 Base map:
 2012 12.5cm HRO aerial imagery provided by the State of Utah
 AGRC. Hillshades derived from 2013-2014 0.5m LIDAR and 5 meter
 DEMs provided by the State of Utah AGRC.

**Alluvial Fan Flooding
 and Debris Flow**


Plate
 1



0 900 1,800 3,600 5,700 7,600 Feet
 1 inch = 3,000 feet
 Base map:
 2012 12.5cm HRO aerial imagery provided by the State of Utah
 AGRC. Hillshades derived from 2013-2014 0.5m LIDAR and 5 meter
 DEMs provided by the State of Utah AGRC.

Flooding Hazard


Plate
 1



0 900 1,800 3,600 5,700 7,600 Feet
 1 inch = 3,000 feet
 Basemap:
 2012 12.5cm HRO aerial imagery provided by the State of Utah
 AGRC. Hillshades derived from 2013-2014 0.5m LIDAR and 5 meter
 DEMs provided by the State of Utah AGRC.




Liquefaction Potential	Plate 1
------------------------	------------



0 900 1,800 3,600 5,700 7,600 Feet
 1 inch = 3,000 feet
 Basemap:
 2012 12.5cm HRO aerial imagery provided by the State of Utah
 AGRC. Hillshades derived from 2013-2014 0.5m LIDAR and 5 meter
 DEMs provided by the State of Utah AGRC.




Shallow Groundwater	Plate 1
---------------------	------------



0 900 1,800 3,600 5,700 7,600 Feet
 1 inch = 3,000 feet
 Basemap:
 2012 12.5cm HRO aerial imagery provided by the State of Utah
 AGRC. Hillshades derived from 2013-2014 0.5m LIDAR and 5 meter
 DEMs provided by the State of Utah AGRC.




Landslide and Slope Stability
 Plate 1



0 900 1,800 3,600 5,700 7,600 Feet
 1 inch = 3,000 feet
 Basemap:
 2012 12.5cm HRO aerial imagery provided by the State of Utah
 AGRC. Hillshades derived from 2013-2014 0.5m LIDAR and 5 meter
 DEMs provided by the State of Utah AGRC.




Surface Fault Rupture
 Special Study zone
 Plate 1



0 950 1,900 3,800 5,700 7,600 Feet
 1 inch = 3,000 feet
 Basemap:
 2012 12.5cm HRI aerial imagery provided by the State of Utah
 AGRC. Hillshades derived from 2013-2014 0.5m LIDAR and 5 meter
 DEMs provided by the State of Utah AGRC.

Topographic Map

Plate 1



0 950 1,900 3,800 5,700 7,600 Feet
 1 inch = 3,000 feet
 Basemap:
 2012 12.5cm HRI aerial imagery provided by the
 State of Utah AGRC. Hillshades derived from 2013-2014 0.5m
 LIDAR and 5 meter DEMs provided by the State of Utah AGRC.

2012 Aerial Imagery

Plate 1

APPENDIX B

Minimum Standards for Surface Fault Rupture Hazard Studies

1.0 INTRODUCTION

1.1 Purposes

1.2 Properties requiring a fault investigation

1.3 References and sources

2.0 MINIMUM STANDARDS FOR FAULT STUDIES

2.1 Scoping Meeting

2.2 Fault investigation method

- 2.2.1. Previous studies and aerial photograph review
- 2.2.2. Exploration methods
- 2.2.3. Trench siting
- 2.2.4. Location determination
- 2.2.5. Depth of excavation
- 2.2.6. Documenting trench exposures
- 2.2.7. Age dating

2.3 Field review

2.4 Recommendations for fault setbacks

2.5 Small displacement faults

2.6 Required outline for surface fault rupture hazard studies

- 2.6.1. Report
- 2.6.2. Report references
- 2.6.3. Support information

1.0 INTRODUCTION

The Wasatch Fault Zone is a major tectonic feature of the intermountain region in the western United States. It extends from Fayette, Utah at the south to Malad, Idaho at the north, comprising about 230 miles. Surface faulting has occurred along the Wasatch Fault Zone in northern Utah throughout late Pleistocene and Holocene time. “*Surface faulting*” is a fault-related offset or displacement of the ground surface that may occur in an earthquake.

The Wasatch Fault Zone consists of a series of normal-slip fault segments where the earth experiences relative downward movement on the west side and upward movement on the east side. Ten major fault segments are recognized along the Wasatch Fault Zone, which are believed to be independent in regard to their potential for surface faulting. These segments have distinct geomorphic expression and are clearly visible on aerial photographs.

In the Salt Lake Valley, the Wasatch Fault Zone is represented by the Salt Lake City segment, which extends about 23 miles along the eastern edge of the valley. A portion of the Salt Lake City segment of the Wasatch Fault Zone is present in the foothills of Cottonwood Heights (the “*city*”) on the eastern side of city. Documentation of repeated Holocene movements suggest that at least four major earthquake events have occurred in the last 6,000 years along Wasatch Boulevard near the mouth of Little Cottonwood Canyon.

In the event of an earthquake, a fault could break the ground surface below or near a structure and cause significant property damage, injuries and loss of life. In order to reduce risk from surface- fault-rupture hazards and to protect public health and safety, the city has defined a

boundary for the sensitive lands that may have a heightened potential for surface fault ruptures and is requiring study for all new development or re-development within this area. Quaternary faults located within the Surface Fault Rupture Hazard Study Area should be considered active until proven otherwise.

The city requires a site specific geologic study for all properties that may be impacted by the Wasatch Fault Zone. The study must address the surface fault rupture potential and assess the suitability of the proposed development. In the event that a fault is discovered and deemed active (i.e., Holocene-age), appropriate building setbacks are required to minimize the potential damage during an earthquake.

The site-specific surface fault rupture hazard study requires a field investigation. This includes geologic documentation of an excavated trench or other pre-approved method of exploration and accompanying report that addresses the findings. The following information in this appendix describes the minimum standards required by the city for the surface fault rupture hazard study. In addition to the minimum standards contained in this appendix, these investigations and reports shall conform with the *Guidelines for Evaluating Surface-Fault-Rupture Hazards in Utah* (UGS Circular 122), as appropriate.

1.1 Purposes.

(a) The purposes of establishing minimum standards for surface fault rupture hazard studies are to:

(i) Protect the health, safety, welfare, and property of the public by minimizing the potential adverse effects of surface fault ruptures and related hazards.

(ii) Provide guidance for property owners and land developers in performing reasonable and adequate studies of sensitive lands in the city.

(iii) Provide consulting engineering geologists with a common basis for preparing proposals, conducting investigations, and recommending setbacks.

(iv) Provide a consistent and objective framework for review of fault study reports.

(b) The procedures in this appendix are intended to provide the developer and consulting engineering geologist with an outline of appropriate exploration methods, standardized report information, and city expectations.

(c) These standards are the minimum level of effort required in conducting surface fault rupture hazard studies within the city. Considering the complexity of evaluating surface and near-surface faults, additional effort beyond the minimum standards may be required at some sites to adequately address the surface fault rupture hazard. The information presented in this appendix does not relieve the engineering geologist from his/her duty to perform additional geologic or engineering services he/she believes are necessary to assess the surface fault rupture potential at a site. In the interest of public safety, the city may, at any time, require additional information, studies, tests or other work that is not included in this appendix.

1.2 Properties requiring a fault investigation.

(a) Before approval of any land use, a fault study is required for properties within the surface fault rupture special study area that is located near the Wasatch Fault Zone, or any other property within the city that observes a fault trace during excavation. Appendix A of city code chapter 19.72 (“*chapter 19.72*”) contains the Surface Fault Rupture Hazard Study Area Map (Map 1) that identifies areas with known active faults in the city. Properties within this area must perform site-specific geologic investigations. Development of any parcel within the Surface

Fault Rupture Hazard Study Area requires submittal and review of a site-specific fault study prior to receiving a land use or building permit from the city. It is the responsibility of the applicant to retain a *qualified* (as provided in chapter 19.72) engineering geologist to perform the fault study.

(b) In addition, a fault study may be required if onsite or nearby fault-related features not shown on the Surface Fault Rupture Hazard Study Area Map are identified during the course of other geologic or geotechnical studies performed on or near the site or during construction.

Table 1. Table showing when a surface fault rupture hazard investigation is required, based on the structure’s IBC Risk Category and the age of the last movement on the designated Special Study Zone fault.

<u>IBC Risk Category</u>	<u>Surface Fault Rupture Hazard Investigation (Fault Movement Age)</u>		
	<u>Latest Pleistocene-Holocene</u>	<u>Late Quaternary</u>	<u>Quaternary</u>
<u>I</u>	<u>Optional</u>	<u>Optional</u>	<u>Optional</u>
<u>II(a)¹</u>	<u>Required</u>	<u>Optional</u>	<u>Optional</u>
<u>II(b)²</u>	<u>Required</u>	<u>Required</u>	<u>Required</u>
<u>III</u>	<u>Required</u>	<u>Required</u>	<u>Required</u>
<u>IV</u>	<u>Required</u>	<u>Required</u>	<u>Required</u>

¹ – Single family dwellings.

² – Buildings and other structures except those listed in IBC Risk Categories I, II(a), III, and IV.

(c) The requirement for site-specific investigation of surface faulting depends on fault activity level as defined by the most recent Western States Seismic Policy Council (WSSPC) Policy Recommendation (PR) for faults that cross properties with proposed structures. The current PR is 21-3: *Definitions of Recency of Surface Faulting for the Basin and Range Province* and defines latest Pleistocene-Holocene, late Quaternary, and Quaternary faults as:

(i) Latest Pleistocene-Holocene fault – A fault whose movement in the past 15 ka [15,000 years] has been large enough to break the ground surface.

(ii) Late Quaternary fault – A fault whose movement in the past 130 ka [130,000 years] has been large enough to break the ground surface.

(iii) Quaternary fault – A fault whose movement in the past 2.6 Ma [2.6 million years] has been large enough to break the ground surface.

The city requires site-specific investigation on parcels with latest Pleistocene-Holocene faults for all new critical facilities and structures for human occupancy (IBC Risk Category II, III, and IV structures), on parcels with latest Pleistocene-Holocene and late Quaternary faults for all new critical facilities (IBC Risk Category III and IV structures), and on parcels with the faults listed in item 2 below.

(d) The *UGS Utah Geologic Hazards Portal*, *Earthquake Hazards, Hazardous Faults* layer and *UGS Utah Quaternary Fault and Fold Database* provide the latest information on Quaternary faulting in Utah to determine fault activity levels as defined above and where surface fault rupture Geologic Hazard Study Areas have been defined. Where data are inadequate to determine the fault activity class, the fault shall be assumed to be latest Pleistocene-Holocene, pending detailed surface-fault-rupture and/or paleoseismic investigations. The database currently includes the following mapped Quaternary faults within the city:

- Wasatch fault zone, Salt Lake City section – Latest Pleistocene-Holocene fault

Cottonwood Heights City may require a site-specific investigation if on-site and/or nearby fault-related features not shown in the database are identified during other geologic or geotechnical investigations or during project construction.

Investigations are required for all critical facilities, whether near a mapped Quaternary fault or not, to ensure that previously unknown faults are not present. If evidence for a Quaternary fault is found, subsurface investigations are required and trenching to locate a suitable buildable area may be necessary (IBC Sections 1704.6.1 and 1803.5.11).

(e) When an alternative subsurface exploration plan is proposed in lieu of paleoseismic trenching, a map and written description and plan shall be submitted to Cottonwood Heights City for review, prior to the scoping meeting and exploration implementation. The plan must include at a minimum, a map of suitable scale showing the site limits, surface geologic conditions within 2000 feet of the site boundary, the location and type of the proposed exploration, the anticipated subsurface geologic conditions, and a through description of why the alternative exploration is being proposed.

1.3 References and sources.

- (a) Guidelines for Evaluating Surface Fault Rupture Hazards in Utah (AEG, 1987).
- (b) Guidelines to geologic and seismic reports, (CDMG, 1986a).
- (c) Guidelines for preparing engineering geologic reports (CDMG, 1986b).
- (d) Guidelines for Evaluating Potential Surface Fault Rupture/Land Subsidence Hazards in Nevada (Nevada Earthquake Safety Council, 1998)
- (e) Fault Setback Requirements to Reduce Fault Rupture Hazards in Salt Lake County (Batatian and Nelson, 1999).
- (f) Salt Lake County Geologic Hazards Ordinance (2002).
- (g) Draper City Geologic Hazard Ordinance (2003).
- (h) Guidelines for evaluating surface-fault-rupture hazards in Utah (Christenson and others, 2003).

(i) Guidelines for Investigating Geologic Hazards and Preparing Engineering-Geology Reports, with Suggested Approach to Geologic-Hazard Ordinances in Utah (Bowman and Lund, 2016).

2.0 MINIMUM STANDARDS FOR FAULT STUDIES

The following are the minimum standards for a comprehensive surface fault rupture study investigation.

2.1 Scoping meeting.

A scoping meeting with the DRC shall be scheduled by the consultant geologist. At this meeting, the developer, the city and the consultant will evaluate the fault investigation approach. The consultant should bring a site plan to the meeting that shows the following information:

- (a) Proposed building locations (if known);
- (b) Expected fault location(s) and orientation;
- (c) Proposed trench locations, orientation, length, and depth (see Section 2.2, Fault Investigation Method);
- (d) Extent of impact to vegetation and trees; and
- (e) Method of controlling erosion and managing storm water.

The investigative approach should allow for flexibility due to unexpected site conditions. The field findings may require modifications to the work plan.

2.2 Fault investigation method.

Inherent in fault study methods is the assumption that future faulting will recur along pre-existing faults and in a manner consistent with past displacement. The focus of fault studies is therefore to accurately locate existing faults. If faults are documented, the investigation shall also include (a) evaluation of the age of movement along the fault trace(s), and (b) estimation of amounts of past displacement, which is required in order to derive fault setbacks.

2.2.1 Previous studies and aerial photograph review. A fault study shall include review of available literature pertinent to the site and vicinity, including previous published and unpublished geologic/soils reports, and interpretation of available stereo-paired aerial photographs. The photographs reviewed should include more than one set and should include pre-urbanization aerial photographs, if available. Efforts must be made to accurately plot the locations of mapped or inferred fault traces on the property as shown by previous studies in the area.

2.2.2 Exploration methods. Sub- surface trenching exploration is required. The engineering geologist shall clean and document (“log”) trench exposures as described in Section 2.3.5. Existing faults may also be identified and mapped in the field by direct observation of young, fault-related geomorphic features, and by examination of aerial photographs. If trenching is not feasible due to the presence of shallow ground water or excessive fill, supplemental methods such as closely spaced Cone Penetration Test (CPT) soundings may be employed. Such supplemental methods must be discussed with the city prior to implementation and should be clearly described in the report.

(i) In lieu of conventional trenching or the CPT method, an alternative subsurface exploration program may be acceptable, depending upon site conditions. Such a program may consist of geophysical exploration techniques or a combination of other techniques.

(ii) When an alternative exploration program is proposed, a written description of the proposed exploration program along with an exploration plan should be submitted to the city for review and approval, prior to the exploration. The plan must include, at a minimum, a map of suitable scale showing the site limits, surface geologic conditions within several thousand feet of the site boundary, the location and type of the proposed alternative subsurface exploration, and the anticipated earth materials present at depth on the site.

(iii) The actual subsurface exploration program to be used on any specific parcel will be determined on an individual basis, considering the current state of technical knowledge about the fault zone and information gained from previous exploration on adjacent or nearby parcels. At all times, consideration must be given to safety, and trenching should comply with all applicable safety regulations.

2.2.3 Trench siting.

(i) Exploratory trenches must be oriented approximately perpendicular to the anticipated trend of known fault traces. The trenches shall provide the minimum footage of trenching necessary to explore the portion of the property situated in the surface fault rupture study area, such that the potential for surface fault rupture may be adequately assessed. When trenching to determine if faults might affect a proposed building site, the trench should extend beyond the building footprint at least the minimum setback distance for the building type (see Table A-1).

(ii) Test pits or potholes alone are neither adequate nor acceptable. In some instances more than one trench may be required to cover the entire building area, particularly if the proposed development involves more than one building. Where feasible, trenches shall be located outside the proposed building footprint, as the trench is generally backfilled without compaction, which could lead to differential settlement beneath the footings. Supplemental trenching may be required in order to:

- A. Further refine fault locations (or the absence thereof);
- B. Accurately define building restriction areas, and/or;
- C. Provide additional exposures for evaluating the age of movement along fault traces.

2.2.4 Location determination. All trenches and fault locations must be surveyed by a registered professional land surveyor. The extrapolation of subsurface conditions should not exceed 300 feet. Fault locations should be surveyed with an accuracy of 0.1 foot or better, so that structural setbacks can be developed. The fault locations (and all other features shown in the site plans) must be tied to a minimum of two Salt Lake County section corner monuments and the coordinate data shall be in US State Plane NAD83 (US Survey Feet). Other features in the site plan shall include property lines, building footprint, geologic features, utilities, existing structures, roadway, fences, etc. The location of all features, including the fault lines, shall be wet stamped and certified by the land surveyor.

2.2.5 Depth of excavation.

(i) The depth of the trenches will ultimately depend on the trench location, occurrence of ground water, stability of subsurface deposits, and the geologic age of the subsurface geologic units. As a minimum, however, trenches shall extend substantially below the A and B soil horizons and well into distinctly bedded Pleistocene-age materials, if possible. Where possible, the trenches should extend below Holocene deposits and should expose contacts between Holocene materials and the underlying older materials.

(ii) Appropriate safety measures pertaining to trench safety for ingress, egress, and working in or in the vicinity of the trench must be implemented and maintained. It is the responsibility of the person in the field directing trench excavation to ensure that fault trenches are excavated in compliance with current Occupational Safety and Health Administration excavation safety regulations.

(iii) Trench backfilling methods and procedures should be documented in order to establish whether additional corrective excavation, backfilling, and compaction should be performed at the time of site grading.

(iv) In cases where Holocene (i.e., active) faults may be present, but pre- Holocene deposits are below the practical limit of excavation, the trenches must extend at least through sediments that are clearly older than several fault recurrence intervals. The practical limitations of the trenching must be acknowledged in the report and recommendations must reflect resulting uncertainties.

2.2.6 Documenting trench exposures. Trench walls shall be cleaned of debris and backhoe smear prior to documentation. Trench logs shall be carefully drawn in the field at a minimum scale of 1-inch equals 5-feet (1:60) following standard and accepted fault trench investigation practices. Vertical and horizontal control must be used and shown on trench logs. Trench logs must document all significant geologic information from the trench and should graphically represent the geologic units observed; see Section 2.6.3(E). The strike, dip, and net vertical displacement (or minimum displacement) of faults must be noted.

2.2.7 Age dating.

(i) The engineering geologist shall interpret the ages of geologic units exposed in the trench. When necessary, radiocarbon or other age determinations methods shall be used. If evidence of faulting is documented, efforts shall be made to date the time of latest movement to determine whether recent (Holocene) displacement has occurred by using appropriate geologic and/or soil stratigraphic dating techniques. When necessary, obtain radiocarbon or other age determinations.

(ii) Many of the surficial deposits within Salt Lake Valley were deposited during the last pluvial lake cycle, referred to as the Bonneville lake cycle. Although late-stage Bonneville lake cycle sediments do not correspond to the Pleistocene-Holocene boundary (i.e., Bonneville lake cycle deposits are older than 10,000 years old), for purposes of evaluating fault activity, these deposits provide a useful regional datum, particularly when the entire Holocene sequence of sediments is not present.

(iii) For practical purposes, and due to documented Holocene displacement along the Salt Lake segment of the Wasatch fault, any fault which displaces late-stage Bonneville Lake Cycle deposits should be considered active unless the Bonneville deposits are overlain by clearly unfaulted early Holocene-age deposits. Conversely, the presence of demonstrably unbroken, undeformed, and stratigraphically continuous Bonneville sediments constitutes reasonable geologic evidence for the absence of active faulting.

2.3 Field review.

A field review by the city's geologist is required during exploratory trenching. The applicant must provide a minimum of two business days notice to schedule the field review with the city. The trenches should be open, safe, cleaned, and a preliminary log completed at the time of the review. The field review allows the city to observe the subsurface data such as the age, type of sediments, and presence or absence of faulting with the consultant. Discussions about questionable features or an appropriate setback distance are encouraged, but the city will not help log the trench, explain the stratigraphy, or give verbal approval of the proposed development during the field review.

2.4 Recommendations for fault setbacks.

(a) Determination of the appropriate setback distance from a hazardous fault shall be made in conformance with the Guidelines for Evaluating Surface-Fault-Rupture Hazards in Utah (Lund and others, 2020; UGS Circular 128, Chapter 3). To address wide discrepancies in fault setback recommendations, the city has also adopted the fault setback calculation methodology for normal faults of Batatian and Nelson (1999) and Christenson and others (2003). The consultant should use this method to establish the recommended fault setback for critical facilities and structures designed for human occupancy. If another fault setback method is used, the consultant must provide justification in the report for the method used. Faults and fault setbacks must be clearly identified on site plans and maps.

(b) The minimum setbacks are based on the type and occupancy of the proposed structure as shown in Table A-1. The setbacks should be calculated using the following formulas presented below, and then compared to the minimum setback established in Table A-1. The greater of the two shall be used as the setback. Minimum setbacks apply to both the hanging wall and footwall blocks.

(c) Top of slope and/or toe of slope setbacks required by the local Building Code must also be considered; again, the greater setback must be used.

Downthrown Fault Block (Hanging Wall)

The fault setback for the downthrown block will be calculated using the following formula:

$$S = U (2D + F/\tan\Theta) \text{ where:}$$

S = Setback within which structures for human occupancy are not permitted;

U = Criticality Factor, based on the proposed occupancy of the structure (see Table A-1)

D = Expected fault displacement per event (assumed to be equal to the net vertical displacement measured for each past event)

F = Maximum depth of footing or subgrade portion of the building

Θ = Dip of the fault (degrees)

Upthrown Fault Block (Footwall)

The dip of the fault and depth of the subgrade portion of the structure are irrelevant in calculating the setback on the upthrown fault block. Therefore, the setback for the upthrown side of the fault will be calculated as:

$$S = U \times 2D$$

The setback is measured from the portion of the building closest to the fault, whether subgrade or above grade. Minimum setbacks apply as discussed above.

2.5 Small displacement faults.

~~(a)~~—Small-displacement faults are not categorically exempt from structure setback requirements. However, if structural risk-reduction measures are proposed for these faults, the following criteria must be met:

(a) Reasonable geologic data indicating that future surface displacement along the faults will not exceed~~Some faults having less than~~ 4 inches (100 mm) of displacement (“*small displacement faults*”) may be exempt from setback requirements following the UGS Circular 122 guidelines; and

(b) Specific structural risk-reduction options such as foundation reinforcement may be acceptable for some small-displacement faults in lieu of setbacks. Structural options must minimize structural damage.

(c) Fault studies must still identify faults and fault displacements (both net vertical displacements and horizontal extension across the fault or fault zone), and consider the possibility that future displacement amounts may exceed past amounts. If structural risk-reduction measures are proposed for small displacement faults, the following criteria must be addressed:

(i) Reasonable geologic data indicating that future surface displacement along the particular fault will not exceed 4 inches.

(ii) Specific structural mitigation to minimize structural damage and ensure safe occupant egress.

(iii) A Utah-licensed structural engineer must provide appropriate designs and the city shall review the designs.

2.6 Required outline for surface fault rupture hazard studies.

(a) The information described herein may be presented as a separate surface fault rupture hazard report or it may be incorporated within other geology or engineering reports that may be required for the property.

(b) The report shall contain a conclusion regarding the potential risk of surface fault rupture on the subject property and a statement addressing the suitability of the proposed development from a surface fault rupture hazard perspective. If exploration determines that there is a potential for surface rupture due to faulting, or if gradational contacts or other uncertainties associated with the exploration methods preclude the determination of absence of small fault offsets, the report should provide estimates of the amplitude of fault offsets that might affect habitable structures.

(c) Surface fault rupture hazard reports submitted to the city are expected to follow the outline and address the subjects presented below. However, variations in site conditions may require that additional items be addressed, or permit some of the subjects to be omitted (except as noted).

2.6.1 Report.

(i) *Statement of the purpose and scope of work.* The report shall contain a clear and concise statement of the purpose of the study and the scope of work performed for the study.

(ii) *Site description and conditions.* The report shall include information on geologic units, graded and filled areas, vegetation, geomorphic features, existing structures, and other factors that may affect site development, choice of investigative methods, and the interpretation of data.

(iii) *Geologic and tectonic setting.* The report shall contain a clear and concise statement of the general geologic and tectonic setting of the site and surrounding vicinity. This section should include a discussion of active faults in the area, paleoseismicity of the relevant fault system(s), and should reference relevant published and unpublished geologic literature.

(iv) *Methods of investigation.*

A. Review of published and unpublished maps, literature and records concerning geologic units, faults, surface and ground water, and other factors.

B. Stereoscopic interpretation of aerial photographs to detect fault-related topography, vegetation or soil contrasts, and other lineaments of possible fault origin. Reference the photograph source, date, flightline numbers, and scale. Salt Lake County has an excellent collection of stereoscopic aerial photographs dating back to 1937 (including 1937, 1940, 1958, 1964, and 1985).

C. Observations of surface features, both on-site and offsite, including mapping of geologic and soil units; geomorphic features such as scarps, springs, and seeps (aligned or not); faceted spurs, offset ridges or drainages; and geologic structures. Locations and relative ages of other possible earthquake-induced features such as sand blows, lateral spreads, liquefaction, and ground settlement should be mapped and described. Slope failures, although they may not be conclusively tied to earthquake causes, should also be noted.

D. The report shall include a description of the program of subsurface exploration, including trench logs, purpose of trench locations, and a summary of trenching or other detailed, direct observation of continuously exposed geologic units, soils, and geologic structures. All trench logs shall be at a scale of at least 1-inch is equal to five-feet.

E. The report must describe the criteria used to evaluate the ages of the deposits encountered in the trench, and clearly evaluate the presence or absence of active (Holocene) faulting.

(v) *Conclusions.*

A. Conclusions must be supported by adequate data and shall contain, at a minimum a summary of data upon which conclusions are based.

B. Location of active faults, including orientation and geometry of faults, amount of net slip along faults, anticipated future offset, and delineation of setback areas.

C. Degree of confidence in and limitations of data and conclusions.

(vi) *Recommendations.* Recommendations must be supported by adequate geologic data and appropriate reasoning behind each statement. Minimum recommendations shall include:

A. Recommended setback distances per Section 2.4. Supporting calculations must be included. Faults and setbacks must be shown on site maps and final recorded plat maps.

B. Other recommended building restrictions or use limitations (i.e., placement of detached garages, swimming pools, or other non-habitable structures).

C. Need for additional or future studies to confirm buildings are not sited across active faults, such as inspection of building footing or foundation excavations by the consultant.

2.6.2 Report references. Reports must include citations of literature and records used in the study, referenced aerial photographs or images interpreted (air-photo source, date and flight number, scale), and any other sources of data and information, including well logs, personal communications, etc.

2.6.3 Support information. At a *minimum*, each geologic report must include the following support information:

(i) *Location map.* A site location map depicting topographic and geographic features and other pertinent data. Generally a 1:24,000-scale USGS topographic base map will suffice.

(ii) *Geologic map.* A regional-scale map (1:24,000 to 1:50,000 scale) is generally adequate. Depending on site complexity, a site-scale geologic map (minimum 1 inch= 200 ft or more detailed) may also be necessary. The map should show Quaternary and bedrock geologic units, faults, seeps or springs, soil or bedrock slumps, and other geologic and soil features existing on and adjacent to the project site. Geologic cross-sections may be included as needed to illustrate 3-dimensional relationships.

(iii) *Site plan and fault map.* A detailed survey-grade site plan is required. The site plan shall be prepared and certified by a licensed surveyor. The site plan should be at a minimum scale of at least 1 inch = 200 feet and should clearly show site boundaries, proposed building footprints, existing structures, streets, slopes, drainages, exploratory trenches, boreholes, test pits, geophysical traverses, utilities, property lines, fences, slopes, trees, retaining walls, adjacent structures and any other appurtenant features. The site plan shall include the locations of subsurface investigations and site-specific geologic mapping performed as part of the geologic investigation, including boundaries and features related to any geologic hazards, topography, and drainage. The site map must also show the surface fault rupture hazard study area within the subject site the locations of all faults identified during the investigation conducted for the subject site including inferred location of the faults between trenches and must show all recommended setbacks from identified faults and from the ends of trenches located within the surface fault rupture hazard study area. The site map must show the location of all proposed flexible expansion joints for utilities. Both buildable and non-buildable areas shall be clearly identified. All features on the map shall be tied to a minimum of two public survey monuments tied with

bearings and distances. The datum shall be submitted in US State Plane NAD83 (US Survey Feet) and wet-stamped by a licensed surveyor. The site map should include a legend describing pertinent items shown on the map.

(iv) *Exploratory trench logs.* Trench logs are required for each trench excavated as part of the study, whether faults are encountered or not. Trench logs shall accurately depict all observed geologic features and conditions. Trench logs are hand- or computer-generated maps of excavation walls that show details of geologic units and structures. Logs must be submitted with a scale and not be generalized or diagrammatic. The minimum scale is 1 inch = 5 feet (1:60) with no vertical exaggeration. Trench logs must accurately reflect the features observed in the trench (see Section 2.3.6). Photographs shall not be used as a substitute for trench logs. However, it is recommended that a photographic log of the trench also be created.

(v) *Contents of trench logs.* Trench logs shall include orientation and indication of which trench wall was logged; trench top and bottom; stratigraphic contacts; stratigraphic unit descriptions including lithology, USCS soil classification, genesis (geologic origin), age, and contact descriptions; soil (pedogenic) horizons; marker beds; and deformation or offset of sediments, faults, and fissures. Other features of tectonic significance such as buried scarp free-faces, colluvial wedges, in-filled soil cracks, drag folds, rotated clasts, lineations, and liquefaction features including dikes, sand blows, etc. should also be shown. Interpretations of the age and origin of the deposits and any faulting or deformation must be included, based on depositional sequence. Fault orientation and geometry (strike and dip), and amount of net displacement must be measured and noted. Provide evidence for the age determination of geologic units. For suspected Holocene faults where unfaulted Holocene deposits are deeper than practical excavation depths, clearly state the study limitations

(vi) *Exploratory boreholes and CPT soundings.* If boreholes or CPT soundings are utilized as part of the investigation, reports shall include the logs of the borings/soundings. Borehole logs must include lithology descriptions, interpretations of geologic origin, USCS soil classification or other standardized engineering soil classification (include an explanation of the classification scheme), sample intervals, penetrative resistance values, static ground-water depths and dates measured, total depth of borehole, and identity of the person logging the borehole. Electronic copies of CPT data files should be provided to the city's reviewer, upon request. Since boreholes are typically multipurpose, borehole logs should contain standard geotechnical and geologic data such as lithology descriptions, soil class, sampled intervals, sample recovery, blow-count results, static ground-water depths with dates measured, total depth of boreholes, drilling and sampling methods, and identity of the person logging the borehole. In addition, borehole, geoprobe hole, and cone-penetrometer logs for fault studies should include the geologic interpretation of deposit genesis for all layers. Also include boring logs or logs from other exploration techniques, when applicable, prepared with standard geologic nomenclature.

(vii) *Geophysical data.* All geophysical data, showing stratigraphic interpretations and fault locations, must be included in the report, along with correlations to trench or borehole logs to confirm interpretations.

(viii) *Photographs.* Photographs of scarps, trench walls, or other features that enhance understanding of site conditions and fault-related conditions are not required but should be included when deemed appropriate. Composite, rectified digital photographs of trench walls may be used as background for trench logs, but features as outlined above must still be delineated.

(ix) *Type and number of buildings.* A description of the location and size of site and proposed type and number of buildings (if known) planned for the site.

(x) *Specific recommendations.* Specific recommendations consistent with the purposes set forth in chapter 19.72, including a discussion of the evidence establishing the presence or absence of faulting including ages and geologic origin of faulted and unfaulted stratigraphic units and surfaces. The discussion shall include the location of faults, including orientation and geometry of faults, maximum amounts of vertical displacement on faults, anticipated future offsets, calculation of setbacks, and delineation of setback (non-buildable) areas if applicable. Recommendations must be supported with geologic evidence and appropriate reasoning that is supported by industry standards. Other recommended building restrictions, use limitations, or risk- reduction measures such as placement of detached garages, swimming pools, or other non-habitable structures in fault zones, or use of reinforced foundations for small-displacement faults.

(xi) *Support data.* All data upon which recommendations and conclusions are based shall be clearly stated in the report. This includes a complete citations of literature and records used in the study including personal communications, published and unpublished geologic literature with emphasis on current sources that discuss Quaternary faults in the area, historical seismicity (particularly earthquakes attributed to area faults), and geodetic measurements where pertinent. A listing of aerial photographs used and other supporting information, as applicable.

(xii) *Suitability of the development.* A statement shall be provided regarding

the suitability of the proposed development from a geologic hazard perspective.

(xiii) *Flexible expansion joints.* All sewer and water lines that cross any fault on the subject site shall be equipped with flexible expansion joints to prevent rupture and consequential damage in the event of an earthquake.

(xiv) *Foundation excavation inspection.* Recommended inspection of building foundation excavations during construction to confirm surface and subsurface investigations.

(xv) *Current signature and seal.* A current signature and seal of the investigating, Utah-licensed professional geologist(s). Qualifications giving education and experience in engineering geology and fault studies can be presented through a CV or resume format in the appendix of the report.

(xvi) *Conclusions.* Conclusions that are clearly supported by adequate data included in the report, that summarize the characteristics of observed surface fault rupture hazards, and that address the potential effects of all identified faults on the proposed development, particularly in terms of risk and potential damage. All other geologic hazards identified during the investigation should be discussed. A discussion regarding the degree of confidence and/or limitations of the data should also be included. Supporting data relevant to the investigation not given in the text such as cross-sections, conceptual models, fence diagrams, survey data, water-well data, and qualifications statements. Specific recommendations for additional or more detailed studies, as may be required to understand or quantify all geologic hazards identified at the subject site.

Table A-1. Setback recommendations and criticality factors (U) for IBC occupancy classes
(International Code Council, 2003).

Class (IBC)	Occupancy group	Criticality	U	Minimum setback
A	Assembly	2	2.0	25 feet
B	Business	2	2.0	20 feet
E	Educational	1	3.0	50 feet
F	Factory/Industrial	2	2.0	20 feet
H	High hazard	1	3.0	50 feet
I	Institutional	1	3.0	50 feet
M	Mercantile	2	2.0	20 feet
R	Residential (R-1, R-2, R-4)	2	2.0	20 feet
R-3	Residential (R-3, includes Single Family Homes)	3	1.5	15 feet
S	Storage	-	1	0
U	Utility and misc.	-	1	0
	Table A- 2	1	3.0	50 feet

Table A-2

Additional Structures Requiring Geologic Investigation

- A. Buildings and other structures that represent a substantial hazard to human life in the event of failure, but not limited to:
1. Buildings and other structures where more than 300 people congregate in one area.
 2. Buildings and other structures with elementary school, secondary school or day care facilities with occupancy greater than 250.
 3. Buildings and other structures with occupancy greater than 500 for colleges or adult education facilities.
 4. Health care facilities with occupancy greater than 50 or more resident patients but not having surgery or emergency treatment facilities.
 5. Jails and detention facilities.
 6. Any other occupancy with occupancy greater than 1000.
 7. Power generating stations, water treatment or storage for potable water, wastewater treatment facilities and other public utility facilities.
 8. Buildings and other structures containing sufficient quantities of toxic or explosive substances to be dangerous to the public if released.
- B. Buildings and other structures designed as essential facilities including, but not limited to:
1. Hospitals and other care facilities having surgery or emergency treatment facilities.
 2. Fire, rescue and police stations and emergency vehicle garages and fueling facilities.
 3. Designated emergency shelters.
 4. Designated emergency preparedness, communications, and operation centers and other facilities required for emergency response.
 5. Power-generating stations and other public utility facilities required as emergency backup facilities for facilities and structures included in this table.
 6. Structures containing highly toxic materials as defined by the most recently adopted version of the IBC where the quantity of the material exceeds the maximum allowable quantities defined by the most recently adopted version of the IBC.
 7. Aviation control towers, air traffic centers and emergency aircraft hangars.
 8. Buildings and other structures having critical national defense functions.
 9. Water treatment and storage facilities required to maintain water pressure for fire suppression.

APPENDIX C

Minimum Standards for Slope Stability Analyses

1.0 INTRODUCTION

1.1 Purposes

1.2 References and Sources

1.3 Areas Requiring Slope Stability Analysis

1.4 Roles of Engineering Geologist and Engineering

2.0 GENERAL REQUIREMENTS

3.0 SUBMITTALS

4.0 FACTORS OF SAFETY

5.0 LANDSLIDES

6.0 SITE INVESTIGATION AND GEOLOGIC STUDIES

7.0 SUBSURFACE EXPLORATION

7.1 Trenching

7.2 Methods for Bedded Formations

7.3 Other Geologic Units

8.0 SOIL PARAMETERS

8.1 Residual Shear Strength Parameters

8.2 Interpretation

9.0 SOIL CREEP

10.0 GROSS STATIC STABILITY

11.0 SURFICIAL STABILITY OF SLOPES

12.0 SEISMIC SLOPE STABILITY

12.1 Ground Motion for Pseudostatic and Seismic Deformation Analyses

12.2 Pseudo-Static Evaluations

12.3 Permanent Seismic Slope Deformation

13.0 WATER RETENTION BASINS AND FLOOD CONTROL CHANNELS

14.0 MITIGATION

14.1 Full Mitigation

14.2 Partial Mitigation for Seismic Slope Deformation

1.0 INTRODUCTION

The procedures outlined in this appendix are intended to provide consultants with a general outline for performing quantitative slope stability analyses and to clarify the expectations of the city of Cottonwood Heights (the “city”). These standards constitute the minimum level of effort required in conducting quantitative slope stability analyses in the city. Considering the complexity inherent in performing slope stability analyses, additional effort beyond the minimum standards presented herein may be required at some sites to adequately address slope stability. The information presented herein does not relieve consultants of their duty to perform additional geologic or engineering analyses they believe are necessary to assess the stability of slopes at a site.

The evaluation of landslides generally requires quantitative slope stability analyses. Therefore, the standards presented herein are directly applicable to landslide investigation, and

also constitute the *minimum* level of effort when performing landslide investigations. This appendix does not address debris flows (see Appendix E) or rock falls (see Appendix F).

1.1 Purposes. The purposes for establishing minimum standards for slope stability analyses are to:

- (a) Protect the health, safety, welfare, and property of the public by minimizing the potentially adverse effects of unstable slopes and related hazards;
- (b) Assist property owners and land developers in conducting reasonable and adequate slope stability studies;
- (c) Provide consulting engineering geologists and geotechnical engineers with a common basis for preparing proposals, conducting investigations, and designing and implementing mitigation; and
- (d) Provide an objective framework for regulatory review of slope stability reports.

1.2 References and Sources. The minimum standards presented in this appendix were developed, in part, from the following sources:

- (a) Guidelines for Evaluating Landslide Hazards in Utah (Hylland, 1996).
- (b) Recommended Procedures for Implementation of DMG Special Publication 117, Guidelines for Analyzing and Mitigating Landslide Hazards in California (Blake et al., 2002).
- (c) CDMG Special Publication 117, Guidelines for Analyzing and Mitigating Landslide Hazards in California.
- (d) Salt Lake County Geologic Hazards Ordinance (2002).
- (e) Cottonwood Heights, Utah Code of Ordinances (2005).
- (f) City of Draper, Utah, Title 9, Land Use and Development Code for Draper City, Chapter 9-19, Geologic Hazards Ordinance, December 11, 2007.

1.3 Areas Requiring Slope Stability Analyses.

- (a) Slope stability analyses shall be performed for all sites located within the Slope Stability Study Area Map and for all slopes that may be affected by the proposed development which meet the following criteria:
 - (i) Cut and/or fill slopes steeper than about 2 horizontal (h) to 1 vertical (v).
 - (ii) Natural slopes steeper than or equal to 3 horizontal (h) to 1 vertical (v).
 - (iii) Natural and cut slopes with potentially adverse geologic conditions (e.g. bedding, foliation, or other structural features that are potentially adverse to the stability of the slope).
 - (iv) Natural and cut slopes which include a geologic hazard such as a landslide, irrespective of the slope height or slope gradient.
 - (v) Buttresses and stability fills.
 - (vi) Cut, fill, or natural slopes of water-retention basins or flood-control channels.
 - (vii) Units Qm, Qms, Qms1, Qmsy, Qmso, Qmc, Qmg, Qac, Qg, Qga, Qgy, Qgmy, Qgay, Qgo, Qgao Qgm, Qgmo, and Tn on the most recent geologic maps published by the UGS. Most maps are available in the UGS Interactive Geologic Map Portal, but contact the UGS for interim, progress update, and other non-final maps that may be available, but not online.
 - (viii) Low, moderate, and high landslide susceptibility areas identified in UGS Map M-228: Landslide Susceptibility Map of Utah.
 - (ix) Mapped landslide areas in the UGS Utah Landslide Database.

(b) In hillside areas, investigations shall address the potential for surficial instability, rock slope instability, debris/mudflows (see Appendix E), rock falls (see Appendix F), and soil creep on all slopes that may affect the proposed development, ~~or~~ be affected by the proposed development, and along access roads. Intermediate Geomaterials (IGM), those earth materials with properties between soil and rock, if present, shall be appropriately investigated, sampled, and tested.

(c) When evaluating site conditions to determine the need for slope stability analyses, off-property conditions shall be considered (both up-slope to the top(s) of adjacent ascending slopes and down-slope to and beyond the toe(s) of adjacent descending slopes). Also, the consultant shall demonstrate that the proposed hillside development will not affect adjacent sites or limit adjacent property owners' ability to develop their sites.

1.4 Roles of Engineering Geologist and Engineering.

The investigation of the static and seismic stability of slopes is an interdisciplinary practice. To provide greater assurance that the hazards are properly identified, assessed, and mitigated, involvement of both an engineering geologist and geotechnical engineer is required. Analyses shall be performed only by or under the direct supervision of licensed professionals, qualified and competent in their respective area of practice. An engineering geologist shall provide appropriate input to the geotechnical engineer with respect to the potential impact of the geology, stratigraphy, and hydrologic conditions on the stability of the slope. The shear strength and other geotechnical earth material properties shall be evaluated by the geotechnical engineer. All slope stability should be performed by a qualified and licensed engineer or under the purview of a licensed engineer. Ground motion parameters for use in seismic stability analysis may be provided by either the engineering geologist or geotechnical engineer.

2.0 GENERAL REQUIREMENTS

Except for the derivation of the input ground motion for pseudostatic and seismic deformation analyses (see Section 12), slope stability analyses and evaluations should be performed in general accordance with the latest version of Recommended Procedures for Implementation of DMG Special Publication 117, Guidelines for Analyzing and Mitigating Landslide Hazards in California (Blake et al., 2002). Procedures for developing input ground motions to be used in the city are described in Section 12.1. If on-site sewage and/or stormwater disposal exists or is proposed, the slope stability analyses shall also include the effects of the effluent plume on slope stability.

3.0 SUBMITTALS

(a) Submittals for review shall include boring logs; geologic cross sections; trench and test pit logs; laboratory data (particularly shear strength test results, including individual stress-deformation plots from direct shear tests); discussions pertaining to how idealized subsurface conditions and shear strength parameters used for analyses were developed; analytical results, and summaries of the slope stability analyses and conclusions regarding slope stability.

(b) Subsurface geologic and groundwater conditions must be illustrated on geologic cross sections and must be utilized by the geotechnical engineer for the slope stability analyses. If on-site sewage or storm water disposal exists or is proposed, the slope stability analyses shall include the effects of the effluent plume on slope stability.

(c) The results of any slope stability analyses must be submitted with pertinent backup documentation (i.e., calculations, computer output, etc.). Printouts of input data, output data (if requested), and graphical plots must be submitted for each computer-aided slope stability analysis.

4.0 FACTORS OF SAFETY

The minimum acceptable static factor of safety is 1.5 for both gross and surficial slope stability. The minimum acceptable factor of safety for a calibrated pseudostatic analysis is ~~1.0~~1.1 using the method of Stewart et al. (2003) (see Section 12.2) or other method pre-approved by the city engineer.

5.0 LANDSLIDES

Landslides are the downslope movement of earth (soil, rock, and/or debris) materials and can cause significant property damage, injury, and/or death. The evaluation of landslides generally requires quantitative slope stability analyses, involving engineering geologists and geotechnical engineers experienced in landslide investigation, analysis, and mitigation. Therefore, the standards presented herein are directly applicable to landslide investigation, and also constitute the minimum level of effort when performing landslide investigations. Evaluation of landslides shall be performed in the preliminary phase of hillside developments. Where landslides are present or suspected, sufficient subsurface exploration will be required to determine the basic geometry and stability of the landslide mass and the required stabilization measures. The depth of geologic exploration shall consider the regional geologic structure, the likely failure mode of the suspected failure, and past geomorphic conditions. Additional effort beyond the minimum standards presented herein may be required at some sites to adequately address slope stability. Slope stability and landslide hazard investigations and reports shall conform with the *Guidelines for Evaluating Landslide Hazards in Utah* (UGS Circular 122), as appropriate.

6.0 SITE INVESTIGATION AND GEOLOGIC STUDIES

(a) Adequate evaluation of slope stability for a given site requires thorough and comprehensive geologic and geotechnical engineering studies. These studies are a crucial component in the evaluation of slope stability. Geologic mapping and subsurface exploration are normal parts of field investigation. Samples of earth materials are routinely obtained during subsurface exploration for geotechnical testing in the laboratory to determine the shear strength parameters and other pertinent engineering properties.

(b) In general, geologic studies for slope stability consist of the following fundamental phases:

(i) Study and review of published and unpublished geologic information (both regional and site specific).

(ii) Review and interpretation of available stereoscopic and oblique aerial photographs, DEMs, and LiDAR data.

(iii) Geologic field mapping, including, but not necessarily limited to, measurement of bedding, foliation, fracture, and fault attitudes and other parameters.

(iv) Documentation and evaluation of subsurface groundwater conditions (including effects of seasonal and longer- term natural fluctuations as well as landscape irrigation), surface water, on-site sewage disposal, and/or storm water disposal.

- (v) Subsurface exploration.
- (vi) Analysis of the geologic failure mechanisms that could occur at the site (e.g., mode of failure and construction of the critical geologic cross sections).
- (vii) Presentation and analysis of the data, including an evaluation of the potential impact of geologic conditions on the project.
- (c) Geologic/geotechnical reports shall demonstrate that each of the phases described in subsection 6.0(b) has been adequately performed and that the information obtained has been considered and logically evaluated. Minimum criteria for the performance of each phase are described and discussed in Blake et al. (2002).

7.0 SUBSURFACE EXPLORATION

The purpose of subsurface exploration is to identify potentially significant geologic materials and structures at a site and to provide samples for detailed laboratory characterization of materials from potentially critical zones. Subsurface exploration is almost always required and may be performed by a number of widely known techniques such as bucket-auger borings, conventional small-diameter borings, cone penetration testing (CPT), test pits, trenches, and/or geophysical techniques (see section 4.2 of Blake et al., 2002). In general, subsurface explorations should extend to a minimum depth of the anticipated failure planes or 2/3 the maximum height of the slope, whichever is greater. A discussion of the applicability of some subsurface exploration techniques follows.

7.1 Trenching. Subsurface exploration consisting of trenching has proven, in some cases, to be necessary when uncertainty exists regarding whether or not a particular landform is a landslide. Care must be exercised with this exploration method because landslides characteristically contain relatively large blocks of intact geologic units, which in a trench exposure could give the false impression that the geologic unit is “in-place.” Although limited to a depth of about 15 feet below existing grades, trenching has also proven to be a useful technique for verifying margins of landslides, although the geometry of a landslide can generally be readily determined from evaluation of stereoscopic aerial photographs. Once a landslide is identified, conventional subsurface exploration drilling techniques will be required (see Section 7.2 and 7.3). Slope stability analyses based solely on data obtained from trenches will not be accepted.

7.2 Methods for Bedded Formations.

- (a) Conventional subsurface exploration techniques involving continuous core drilling with an oriented core barrel, test pits, and deep bucket-auger borings may be used to assess the subsurface soil and geologic conditions, particularly for geologic units with inclined bedding that includes weak layers.
- (b) Particular attention must be paid to the presence or absence of weak layers (e.g., clay, claystone, silt, shale, or siltstone units) during the exploration. Unless adequately demonstrated (through comprehensive and detailed subsurface exploration) that weak (clay, claystone, silt, shale, or siltstone) layers (even as thin as 1/16-inch or less) are not present, a weak layer shall be assumed to possibly occur anywhere in the stratigraphic profile (i.e., ubiquitous weak clay beds).
- (c) The depth of the subsurface exploration must be sufficient to assess the conditions at or below the level of the deepest potential failure surface possessing a factor of 1.5 or less. A

preliminary slope stability analysis may need to be performed to assist in the planning of the subsurface exploration program.

(d) Soil and/or rock sampling and testing shall be based on current ASTM International and/or American Association of Highway Officials (AASHTO) standards, as appropriate. Laboratory tests shall be performed using current ASTM International or AASHTO standards, as appropriate, in a laboratory accredited by the AASHTO Materials Reference Laboratory and/or the U.S. Army Corps of Engineers to ensure compliance with current laboratory testing standards and quality control procedures. The final report shall include complete laboratory test results reported in conformance with current ASTM International or AASHTO standards, as appropriate.

7.3 *Other Geologic Units.* For alluvium, fill materials, or other soil units that do not contain weak interbeds, other exploration methods such as small-diameter borings (e.g., rotary wash or hollow-stem-auger) or cone penetration testing may be suitable.

8.0 SOIL PARAMETERS

Soil and/or rock properties, including unit weight and shear strength parameters (cohesion and friction angle), may be based on conventional field and laboratory tests as well as on field performance. Where appropriate (i.e., for landslide slip surfaces, along bedding planes, for surficial stability analyses, etc.), laboratory tests for saturated, residual shear strengths must be performed. Estimation of the shear resistance along bedding (or landslide) planes normally requires an evaluation of saturated residual along-bedding-strength values of the weakest interbedded (or slide-plane) material encountered during the subsurface exploration, or in the absence of sufficient exploration, the weakest material that may be present, consistent with site geologic conditions. Strength parameters derived solely from CPT data may not be appropriate for slope-stability analysis in some cases, particularly for strengths along existing slip surfaces where residual strengths have developed. Additional guidance on the selection of strength parameters for slope stability analyses is contained in Blake et al. (2002).

8.1 *Residual Shear Strength Parameters.* Residual strength parameters may be determined using the direct shear or ring shear testing apparatus; however, ring shear tests are preferred. If performed properly, direct shear test results may approach ring-shear test results. The soil specimen must be subjected to a sufficient amount of deformation (e.g., a significant number of shearing cycles in the direct shear test or a significant amount of rotation in the ring shear test) to assure that residual strength has been developed. In the direct-shear and ring-shear tests, stress-deformation curves can be used to determine when a sufficient number of cycles of shearing have been performed by showing that no further significant drop in shear strength results with the addition of more cycles or more rotation. The stress-deformation curves obtained during the shear tests must be submitted with the other laboratory test results. It shall be recognized that for most clayey soils, the residual shear strength envelope is curved and passes through the origin (i.e., at zero normal stress there is zero shear strength). Any “apparent shear strength” increases resulting from a non-horizontal shear surface (i.e., ramping) or “bulldozing” in residual direct shear tests shall be discounted in the interpretation of the strength parameters.

8.2 *Interpretation.*

(a) The engineer will need to use considerable judgment in the selection of appropriate shear test methods and in the interpretation of the results to develop shear strength parameters commensurate with slope stability conditions to be evaluated. Scatter plots of shear strength data may need to be presented to allow for assessment of idealized parameters. The report shall summarize shear strength parameters used for slope stability analyses and describe the methodology used to interpret test results and estimate those parameters.

(b) Peak shear strengths may be used to represent across-bedding failure surfaces or compacted fill, in situations where strength degradations are not expected to occur (see guidelines in Blake et al., 2002). Where peak strengths cannot be relied upon, fully softened (or lower) strengths shall be used.

(c) Ultimate shear strength parameters shall be used in static slope stability analyses when there has not been past deformation. Residual shear strength parameters shall be used in static slope stability analyses when there has been past deformation.

(d) Averaged strength parameters may be appropriate for some across-bedding conditions, if sufficient representative samples have been carefully tested. Analyses for along-bedding or along-existing-landslide slip surfaces shall be based on lower-bound interpretations of residual shear strength parameters and comparison of those results to correlations, such as those of Stark et al. (2005).

9.0 SOIL CREEP

(a) The potential effects of soil creep shall be addressed where any proposed structure is planned in close proximity to an existing fill slope or natural slope. The potential effects on the proposed development shall be evaluated and mitigation measures proposed, including appropriate setback recommendations. Setback recommendations shall consider the potential effects of creep forces.

(b) All reports in hillside areas shall address the potential for surficial instability, debris/mudflow (Appendix E), rock falls (Appendix F), and soil creep on all slopes that may affect the proposed development or be affected by the proposed development. Stability of slopes along access roads shall be addressed.

10.0 GROSS STATIC STABILITY

Gross stability includes rotational and translational deep-seated failures of slopes or portions of slopes existing within or outside of but potentially affecting the proposed development. The following guidelines, in addition to those in Blake et al. (2002), shall be followed when evaluating slope stability:

(a) Stability shall be analyzed along cross sections depicting the most adverse conditions (e.g., highest slope, most adverse bedding planes, shallowest likely ground water table, and steepest slope). Often analyses are required for different conditions and for more than one cross section to demonstrate which condition is most adverse. When evaluating the stability of an existing landslide, analyses must also address the potential for partial reactivation. Inclinometers may be used to help determine critical failure surfaces and, along with high-resolution GPS/GNSS, the state of activity of existing landslides. The critical failure surfaces on each cross-section shall be identified, evaluated, and plotted on the large-scale cross section.

(b) Rock slope stability shall be based on current rock mechanics practice, using the methods of [Yyllie and Mah \(2004\)](#), based on [Hoek and Bray \(1981\)](#); [Practical Rock](#)

Engineering; Federal Highway Administration (1989); and similar references, such as <https://www.rocsience.com/learning/hoeks-corner/publications>.

(bc) If the long-term, static factor of safety is less than 1.5, mitigation measures will be required to bring the factor of safety up to the required level or the project may be redesigned to achieve a minimum factor of safety of 1.5.

(ed) The temporary stability of excavations shall be evaluated and mitigation measures shall be recommended as necessary to obtain a minimum factor of safety of 1.3.

(de) Long-term stability shall be analyzed using the highest known or anticipated groundwater level based upon a groundwater assessment performed under the requirements of ~~Section 6.0~~ this chapter or as described in UGS Circular 122: *Guidelines for Investigating Geologic Hazards and Preparing Engineering-Geology Reports, With a Suggested Approach to Geologic-Hazard Ordinances in Utah*, Chapter 2, along with groundwater sensitivity analyses.

(f) Slope stability cannot be contingent on uncontrollable factors, such as limiting landscape irrigation, etc.

(eg) Where back-calculation is appropriate, shear strengths utilized for design shall be no higher than the lowest strength computed using back calculation. If a consultant proposes to use shear strengths higher than the lowest back-calculated value, justification shall be required. Assumptions used in back-calculations regarding pre-sliding topography and groundwater conditions at failure must be discussed and justified.

(fh) Reports shall describe how the shear strength testing methods used are appropriate in modeling field conditions and long-term performance of the subject slope. The utilized design shear strength values shall be justified with laboratory test data and geologic descriptions and history, along with past performance history, if known, of similar materials.

(gi) Reports shall include shear strength test plots consisting of normal stress versus shear resistance (failure envelope). Plots of shear resistance versus displacement shall be provided for all residual and fully softened (ultimate) shear tests.

(hj) The degree of saturation for all test specimens shall be reported. Direct shear tests on partially saturated samples may grossly overestimate the cohesion that can be mobilized when the material becomes saturated in the field. This potential shall be considered when selecting shear strength parameters. If the rate of shear displacement exceeds 0.005 inches per minute, the consultant shall provide data to demonstrate that the rate is sufficiently slow for drained conditions.

(ik) Shear strength values higher than those obtained through site-specific laboratory tests generally will not be accepted.

(jl) If direct shear or triaxial shear testing is not appropriate to model the strength of highly jointed and fractured rock masses, the design strengths shall be evaluated in a manner that considers overall rock mass quality and be consistent with rock mechanics practice.

(km) Shear strengths used in slope stability analyses shall be evaluated considering the natural variability of engineering characteristics inherent in earth materials. Multiple shear tests on each site material will typically to be required.

(hn) Direct shear tests do not always provide realistic strength values (Watry and Lade, 2000). Correlations between liquid limit, percent clay fraction, and strength (fully softened and residual) with published data (e.g., Stark and McCone, 2002) shall be performed to verify tested shear strength parameters. Strength values used in analyses that exceed those obtained by the correlation must be appropriately justified.

(~~mo~~) Shear strengths for proposed fill slopes shall be evaluated using samples mixed and remolded to represent anticipated field conditions. Confirming strength testing may be required during grading.

(~~mp~~) Where bedding planes are laterally unsupported on slopes, potential failures along the unsupported bedding planes shall be analyzed. Similarly, stability analyses shall be performed where bedding planes form a dip-slope or near-dip-slope using composite potential failure surfaces that consist of potential slip surfaces along bedding planes in the upper portions of the slope in combination with slip surfaces across bedding planes in the lower portions of the slope.

(~~eq~~) The stability analysis shall include the effect of expected maximum moisture conditions on soil unit weight.

(~~pr~~) For effective stress analyses, measured groundwater conditions adjusted to consider likely unfavorable conditions with respect to anticipated future groundwater levels, seepage, or pore pressure shall be included in the slope stability analyses.

(~~qs~~) Tension crack development shall be considered in the analyses of potential failure surfaces. The height and location of the tension crack shall be determined by ~~searching~~ modeling.

(~~rt~~) Anticipated surcharge loads as well as external boundary pressures from water shall be included in the slope stability evaluations, as deemed appropriate.

(~~su~~) Analytical chart solutions may be used provided they were developed for conditions similar to those being analyzed. Generally though, computer-aided searching techniques shall be used, so that the potential failure surface with the lowest factor of safety can be located. Examples of typical searching techniques are illustrated on figures 9.1(a) through 9.1(f) in Blake et al. (2002). However, verification of the reasonableness of the analytical results is the responsibility of the geotechnical engineer and/or engineering geologist.

(~~tv~~) The critical potential failure surface used in the analysis may be composed of circles, wedges, planes, or other shapes considered designed to yield the minimum factor of safety most appropriate for the geologic site conditions. The critical potential failure surface having the lowest factor of safety with respect to shearing resistance must be sought. Both the lowest factor of safety and the critical failure surface shall be documented.

11.0 SURFICIAL STABILITY OF SLOPES

Surficial slope stability refers to slumping and sliding of near-surface sediments and is most critical during the snowmelt and rainy season or when excessive landscape water is applied. The assessment of surficial slope stability shall be based on analysis procedures for stability of an infinite slope with seepage parallel to the slope surface or an alternate failure mode that would produce the minimum factor of safety. The minimum acceptable depth of saturation for surficial stability evaluation shall be four feet.

11.1 Applicability and Procedures.

(a) Conclusions shall be substantiated with appropriate data and analyses. Residual shear strengths comparable to actual field conditions shall be used in completing surficial stability analyses. Surficial stability analyses shall be performed under rapid draw-down conditions where appropriate (e.g., for debris and detention basins).

(b) Where ~~2H:1V~~ or steeper slopes have soil conditions that can result in the development of an infinite slope with parallel seepage, calculations shall be performed to demonstrate that the slope has a minimum static factor of safety of 1.5, assuming a fully

saturated 4-foot thickness. If conditions will not allow the development of a slope with parallel seepage, surficial slope stability analyses may not be required (provided the geologic/geotechnical reviewer concurs).

(c) Surficial slope stability analyses shall be performed for fill, cut, and natural slopes assuming an infinite slope with seepage parallel to the slope surface or other failure mode that would yield the minimum factor of safety against failure. A suggested procedure for evaluating surficial slope stability is presented in Blake et al. (2002).

11.2 Soil Properties. Soil properties used in surficial stability analyses shall be determined as noted in ~~Section 8.1~~ this chapter. Residual shear strength parameters for surficial slope stability analyses shall be developed for a stress range that is consistent with the near-surface conditions being modeled. It shall be recognized that for most clayey soils, the residual shear strength envelope is curved and passes through the origin (for example, at zero normal stress, there is zero shear strength). For sites with deep slip surfaces, the guidelines given by Blake et al. (2002) should be followed.

11.3 Seepage Conditions. The minimum acceptable vertical depth for which seepage is parallel to the slope shall be applied is four feet for cut or fill slopes. Greater depths may be necessary when analyzing natural slopes that have significant thicknesses of loose surficial material.

12.0 SEISMIC SLOPE STABILITY

In addition to static slope stability analyses, slopes shall be evaluated for seismic slope stability as well. Acceptable methods for evaluating seismic slope stability using calibrated pseudo-static limit-equilibrium procedures and simplified methods (e.g., those based on Newmark, 1965) to estimate permanent seismic slope movements are summarized in Blake et al. (2002). Nonlinear, dynamic finite element/finite difference numerical methods also may be used to evaluate slope movements resulting from seismic events as long as the procedures, input data, and results are thoroughly documented, and deemed acceptable by the city.

12.1 Ground Motion for Pseudostatic and Seismic Deformation Analyses.

(a) The controlling fault that would most affect the city is the Salt Lake City segment of the Wasatch fault zone (WFZ). Repeated Holocene movement has been well documented along this segment (Black et al., 2003). Studies along the Salt Lake City segment of the WFZ indicate a recurrence interval of about 1,300 years and the most recent event being about 1,300 years ago (Lund, 2005). Based on the paleoseismic record of the Salt Lake City segment and assuming a time-dependent model, McCalpin (2002) estimates a conditional probability (using a log-normal renewal model) of 16.5% in the next 100 years (8.25% in the next 50 years) for a $M > 7$ surface-faulting earthquake. Therefore, using a time-dependent rather than Poisson or random model for earthquake recurrence, the likelihood of a large surface-faulting earthquake on the Salt Lake City segment of the WFZ is relatively high and therefore the Salt Lake City segment is considered the primary controlling fault for deterministic analyses.

(b) Regarding design ground accelerations for seismic slope-stability analyses, the city prefers a probabilistic approach to determining the likelihood that different levels of ground motion will be exceeded at a particular site within a given time period. In order to more closely represent the seismic characteristics of the WFZ and better capture this possible high likelihood

of a surface-faulting earthquake on the Salt Lake City segment, design ground motion parameters for seismic slope stability analyses shall be based on the peak accelerations with a 2.05 percent probability in 50 years (2,500-year return period). Peak bedrock ground motions can be readily obtained via the internet from the United States Geological Survey (USGS) National Seismic Hazard Maps, Data and Documentation web page (USGS, 2002), which is based on Frankel et al., 2002. PGAs obtained from the USGS (2002) web page should be adjusted for effects of soil/rock (site-class) conditions in accordance with Seed et al. (2001) or other appropriate methods that consider the site-specific soil conditions and their potential for amplification or de-amplification of the high-frequency strong motion. Site specific response analysis may also be used to develop PGA values as long as the procedures, input data, and results are thoroughly documented, and deemed acceptable by the city.

12.2 Pseudo-Static Evaluations.

(a) Pseudo-static methods for evaluating seismic slope stability are acceptable as long as minimum factors of safety are satisfied, and appropriate consideration is given in the selection of the seismic coefficient, k_h , reduction in material shear strengths, and the factor of safety for pseudo-static conditions.

(b) Pseudo-static seismic slope stability analyses can be performed using the “screening analysis” procedure described in Blake et al. (2002). For that procedure a k_h - value is selected from seismic source characteristics (modal magnitude, modal distance, and firm rock peak ground acceleration) and less than or equal to 2 inches (5 cm) an acceptable level of deformation is specified. For this procedure, a factor of safety of 1.0 or greater is considered acceptable; otherwise, an analysis of permanent seismic slope deformation shall be performed.

12.3 Permanent Seismic Slope Deformation.

(a) For seismic slope stability analyses, estimates of permanent seismic displacement are preferred and may be performed using the procedures outlined in Blake et al. (2002). It should be noted that Bray and Rathje (1998), referenced in Blake et al. (2002), has been updated and superseded by Bray and Travararou (2007), which is the city’s currently preferred method. For these analyses, calculated seismic displacements shall be 15 cm or less, or mitigation measures shall be proposed to limit calculated displacements to 15 cm or less.

(b) For specific projects, different levels of tolerable displacement may be possible, but site-specific conditions, which shall include the following, must be considered:

(i) The extent to which the displacements are localized or broadly distributed – broadly distributed shear deformations would generally be less damaging and more displacement could be allowed.

(ii) The displacement tolerance of the foundation system – stiff, well-reinforced foundations with lateral continuity of vertical support elements would be more resistant to damage (and hence could potentially tolerate larger displacements) than typical slabs-on-grade or foundation systems with individual spread footings.

(iii) The potential of the foundation soils to experience strain softening – slopes composed of soils likely to experience strain softening should be designed for relatively low displacements if peak strengths are used in the evaluation of k_v due to the potential for progressive failure, which could involve very large displacements following strain softening.

(c) In order to consider a threshold larger than 15 cm, the project consultant shall provide prior, acceptable justification to the city and obtain the city’s approval. Such justification

shall demonstrate, to the city's satisfaction, that the proposed project will achieve acceptable performance.

13.0 WATER RETENTION BASINS AND FLOOD CONTROL CHANNELS

For cut, fill, or natural slopes of water- retention basins or flood-control channels, slope stability analyses shall be performed. In addition to analyzing typical static and seismic slope stability, those analyses shall consider the effects of rapid drawdown, if such a condition could develop. All proposed structures should be permitted under Utah Dam Safety rules, as applicable.

14.0 MITIGATION

(a) When slope stability hazards are determined to exist on a project, measures to mitigate impacts from those hazards shall be implemented. Some guidance regarding mitigation measures is provided in Blake et al. (2002). Slope stability mitigation methods include:

- (i) hazard avoidance,
- (ii) grading to improve slope stability,
- (iii) reinforcement of the slope or improvement of the soil within the slope, and
- (iv) reinforcement of the structure built on the slope to tolerate anticipated slope displacements.

(b) Where mitigation measures that are intended to add stabilizing forces to the slope are to be implemented, consideration should be given to strain compatibility. For example, if a compacted fill buttress is proposed to stabilize laterally unsupported bedding or a landslide, the amount of deformation needed to mobilize the recommended shear strength in the buttress shall be considered to confirm that it will not result in adverse movements of the upslope bedding or landslide deposits. Similarly, if a series of drilled piers is to be used to support a potentially unstable slope and a structure will be built on the piers, pier deformations resulting from movements needed to mobilize the soil's shear strength shall be compared to tolerable deflections in the supported structure.

14.1 *Full Mitigation.* Full mitigation of slope stability hazards shall be performed for developments in the city. Remedial measures that produce static factors of safety in excess of 1.5 and acceptable seismic displacement estimates shall be implemented as needed.

14.2 *Partial Mitigation for Seismic Displacement Hazards.* On some projects, or portions thereof (such as small structural additions, residential "infill projects", non- habitable structures, and non-structural natural-slope areas), full mitigation of seismic slope displacements may not be possible, due to physical or economic constraints. In those cases, partial mitigation, to the extent that it prevents structural collapse, injury, and loss of life, may be possible if it can be provided consistent with IBC philosophies, and if it is approved by the city. The applicability of partial mitigations to specific projects will be evaluated on a case-by-case basis.

15.0 NOTICE OF GEOLOGIC HAZARD AND WAIVER OF LIABILITY

For developments where full mitigation of seismic slope displacements is not implemented, a Notice of Geologic Hazard shall be recorded with the proposed development describing the displacement hazard at issue and the partial mitigation employed. The notice shall

clearly state that the seismic displacement hazard at the site has been reduced by the partial mitigation, but not totally eliminated. The notice also shall provide that the owner assumes all risks, waives all claims against the city and its consultants, and indemnifies and holds the city and its consultants harmless from any and all claims arising from the partial mitigation of the seismic displacement hazard.

APPENDIX C - REFERENCES

Bartlett, S.F. and Youd, T. L., 1995, Empirical prediction of liquefaction-induced lateral spread: Journal of Geotechnical Engineering, v. 121, n. 4 -April, American Society of Civil Engineers, pp. 316-329.

Beukelman, G.S. and Hylland, M.D., 2016, Guidelines for evaluating landslide hazards in Utah in Guidelines for investigating geologic hazards and preparing engineering-geology reports, with a suggested approach to geologic-hazard ordinances in Utah: Utah Geological Survey Circular 122, p. 59-73, online: <https://ugspub.nr.utah.gov/publications/circular/c-122.pdf>.

Black, B.D., Hecker, Suanne, Hylland, M.D., Christenson, G.E., and McDonald, G.N. (2003), Quaternary fault and fold database and map of Utah, Utah Geological Survey Map 193DM, CD.

Blake, T.F., Hollingsworth, R.A. and Stewart, J.P., Editors (2002), Recommended Procedures for Implementation of DMG Special Publication 117, Guidelines for analyzing and mitigating landslide hazards in California: organized by the Southern California Earthquake Center, available for download at:
http://www.scec.org/resources/catalog/hazar_dmitigation.html#land.

Boulanger, R.W., and Idriss I.M., 2004, Evaluating the potential for liquefaction resistance or cyclic failures of silts and clays: University of California, Davis Center for Geotechnical Modeling Report UCD/CGM-04/01, [https://faculty.engineering.ucdavis.edu/boulanger/wp-content/uploads/sites/71/2014/09/Boulanger Idriss CGM04-01 2004.pdf](https://faculty.engineering.ucdavis.edu/boulanger/wp-content/uploads/sites/71/2014/09/Boulanger%20Idriss%20CGM04-01%202004.pdf).

Bowman, S.D., and Lund, W.R., editors, 2016, Guidelines for investigating geologic hazards and preparing engineering-geology reports, with a suggested approach to geologic-hazard ordinances in Utah: Utah Geological Survey Circular 122, 203 p., online: <https://ugspub.nr.utah.gov/publications/circular/c-122.pdf>.

Bowman, S.D., and Lund, W.R., 2016, Guidelines for conducting engineering-geology investigations and preparing engineering-geology reports in Utah in Guidelines for investigating geologic hazards and preparing engineering-geology reports, with a suggested approach to geologic-hazard ordinances in Utah: Utah Geological Survey Circular 122, p. 15-30, online: <https://ugspub.nr.utah.gov/publications/circular/c-122.pdf>.

Bray, J.D., and Rathje, E.M., 1998, Earthquake-induced displacements of solid-waste landfills: Journal of Geotechnical and Geoenvironmental Engineering, v. 124, no. 3, pp. 242-253.

Bray J. D. and Sancio R. B., 2006, Assessment of liquefaction susceptibility of fine-grained soils: ASCE Journal of Geotechnical and Geoenvironmental Engineering, September 2006.

Bray, J.D., and Travasarou, T, 2007, Simplified procedure for estimating earthquake-induced deviatoric slope displacements: Journal of Geotechnical and Geoenvironmental Engineering, v. 133, no. 4, April 1, 2007, pp. 381–392.

California Division of Mines and Geology (CDMG) (1997), Guidelines for evaluating and mitigating seismic hazards in California, CDMG Special Publication (SP) 117.

Federal Highway Administration, 1989, Rock slopes-design, excavation, stabilization: Federal Highway Administration Publication FHWA-TS-89-045, variously paginated, online: <https://geodata.geology.utah.gov/pages/view.php?ref=58219>.

FEMA (1997), NEHRP guidelines for the seismic rehabilitation of buildings: FEMA-273/October,

Frankel, A.D., Petersen, M.D., Mueller, C.S., Haller, K.M., Wheeler, R.L., Leyendecker, E.V., Wesson, R.L., Harmsen, S.C., Cramer, C.H., Perkins, D.M., and Rukstales, K.S. (2002), Documentation for the 2002 update of the National Seismic Hazard Maps, USGS Open-File Report 02- 420.

Giraud, R.E., 2016, Guidelines for the geologic investigation of debris-flow hazards on alluvial fans in Utah in Guidelines for investigating geologic hazards and preparing engineering-geology reports, with a suggested approach to geologic-hazard ordinances in Utah: Utah Geological Survey Circular 122, p. 75-91, online: <https://ugspub.nr.utah.gov/publications/circular/c-122.pdf>.

Giraud, R.E., and Shaw, L.M., 2007, Landslide susceptibility map of Utah: Utah Geological Survey Map M-228, 11 p., 1 plate, scale 1:500,000, online: <http://ugspub.nr.utah.gov/publications/maps/m-228/m-228.pdf>.

Hoek, E., Bray, J.W., 1981, Rock slope engineering, revised third edition: E & FN Spon, London, 358 p.

IBC (2006), International Building Code, International Code Council, Inc., 658 p
Idriss, I.M., and Boulanger, R.W., 2010, SPT-based liquefaction triggering procedures: University of California, Davis Center for Geotechnical Modeling Report No. UCD/CGM 10/02, 259 p., https://faculty.engineering.ucdavis.edu/boulanger/wp-content/uploads/sites/71/2014/09/Idriss_Boulanger_SPT_Liquefaction_CGM-10-02.pdf.

International Code Council, Inc., 2006, 2017, 2018 International building code: International Code Council, Country Club Hills, Illinois, 728 p., <https://codes.iccsafe.org/content/IBC2018>.

Lund, W.R. (2005), Consensus preferred recurrence-interval and vertical slip-rate estimates- Review of Utah paleoseismic- trenching data by the Utah Quaternary Fault Parameters Working Group, Utah Geological Survey Bulletin 134, CD.

Lund, W.R., Christenson, G.E., Batatian, L.D., and Nelson, C.V., 2016, Guidelines for evaluating surface-fault-rupture hazards in Utah in Guidelines for investigating geologic hazards and preparing engineering-geology reports, with a suggested approach to geologic-hazard ordinances in Utah: Utah Geological Survey Circular 122, p. 31-58, online: <https://ugspub.nr.utah.gov/publications/circular/c-122.pdf>.

Lund, W.R., and Knudsen, T.R., 2016, Guidelines for evaluating rockfall hazards in Utah in Guidelines for investigating geologic hazards and preparing engineering-geology reports, with a suggested approach to geologic-hazard ordinances in Utah: Utah Geological Survey Circular 122, p. 111-123, online: <https://ugspub.nr.utah.gov/publications/circular/c-122.pdf>.

Martin, G.R., and Lew, M., editors., 1999, Recommended procedures for implementation of DMG Special Publication 117, Guidelines for analyzing and mitigating liquefaction potential in California: Southern California Earthquake Center, University of Southern California, 63 p., <http://sceinfo.usc.edu/resources/catalog/LiquefactionproceduresJun99.pdf>.

McCalpin, J.P. (2002), Post-Bonneville paleoearthquake chronology of the Salt Lake City segment, Wasatch fault zone, from the 1999 “megatrench” site, Utah Geological Survey Miscellaneous Publication 02-7, 38 p.

Mears, A.I., 1992, Snow-avalanche hazard analysis for land use planning and engineering: Colorado Geological Survey Bulletin B-49, 55 p., <https://store.coloradogeologicalsurvey.org/product/snow-avalanche-hazard-analysis-land-use-planning-engineering-2/>.

National Academies of Sciences, Engineering, and Medicine, 2016, State of the art and practice in the assessment of earthquake-induced soil liquefaction and its consequences The National Academies Press, <https://doi.org/10.17226/23474>.

Newmark, N.M. (1965), Effects of earthquakes on dams and embankments, *Geotechnique*, v. 25, no. 4.

Seed, H.B., and Idriss, I.M., 1982, Ground motion and soil liquefaction during earthquakes: Earthquake Engineering Research Institute, Oakland, California, 135 p.

Seed, R.B., Cetin, K.O., Moss, R.E.S., Kammerer, A.M., Wu, J., Pestana, J.M., and Riemer, M.F. (2001), Recent advances in soil liquefaction engineering and seismic site response evaluation, Fourth International Conference on Recent Advances in Geotechnical Earthquake Engineering and Soil Dynamics, University of Missouri-Rolla, Rolla, Missouri, 2001, Paper No. SPL-2, 45 p.

Seed, R.B., Cetin, K.O., Moss, R.E.S., Kammerer, A.M., Wu, J., Pestana, J.M., and Riemer, M.F., Sancio, R.B., Bray, J.D., Kayen, R.E., and Faris, A., 2003, Recent advances in soil liquefaction engineering: A unified and consistent framework: Earthquake Engineering Research Institute Report No. EERC 2003-06, 71 p., https://digitalcommons.calpoly.edu/cgi/viewcontent.cgi?article=1007&context=cenv_fac.

Stark, T.D., Choi, H., and McCone, S. (2005), “Drained shear strength parameters for analysis of landslides,” *Journal of Geotechnical and Geoenvironmental Engineering*, v. 131, no. 5, pp. 575-588.

Stewart, J.P., Blake, T.M., and Hollingsworth, R.A. (2003), Development of a screen analysis procedure for seismic slope stability: *Earthquake Spectra*, 19 (3), pp. 697–712.

USGS (2002), National Seismic Hazard Maps, Data and Documentation web page: <http://eqhazmap.usgs.gov>. For obtaining a pga for a specific probability or return period see <http://earthquake.usgs.gov/research/hazmaps/design/>.

[Youd, T.L., and Idriss, I.M., editors., 1997, Proceedings of the NCEER workshop on evaluation of liquefaction resistance of soils: National Center for Earthquake Engineering Research Technical Report NCEER 97-0022, also Youd, T.L., and Idriss, I.M., 2001, Liquefaction resistance of soils: Summary Report from the 1996 NCEER and 1998 NCEER/NSF workshops on evaluation of liquefaction resistance of soils: Journal of Geotechnical and Geoenvironmental Engineering, v. 127, no. 4, April 2001, <http://www.ce.memphis.edu/7137/PDFs/Reference2/Youd%20ad%20Idriss.pdf>.](#)

[Youd, T.L., and Gilstrap, S.D., \(1999\), Liquefaction and deformation of silty and fine-grained soils: Proceedings of the Second International Conference on Earthquake Geotechnical Engineering, Lisboa, Portugal, 21-25 June 1999, Seco e Pinto, pp. 1013-1020.](#)

[Youd, T.C., Hansen, C.M., and Bartlett, S.F., \(2002\), Revised MLR equations for predicting lateral spread displacement, ASCE Journal of Geotechnical and Geoenvironmental Engineering, December 2002.](#)

Watry, S.M. and Lade, P.V. (2000), “Residual shear strengths of bentonites on Palos Verdes Peninsula, California,”

[Wyllie, D.C., and Mah, C.W., 2004, Rock slope engineering, civil and mining, 4th edition: Spon Press, New York, 431 p.](#)

Proceedings of the session of Geo-Denver 2000, American Society of Civil Engineers, pp. 323-342.

APPENDIX D

Minimum Standards for Liquefaction Investigations and Evaluations

1.0 INTRODUCTION

1.1 Purposes

1.2 References and Sources

1.3 Properties Requiring Liquefaction Analyses

1.4 Roles of Engineering Geology and Geotechnical Engineering

1.5 Minimum Qualifications of the Licensed Professional

2.0 GENERAL REQUIREMENTS

3.0 PRELIMINARY SCREENING FOR LIQUEFACTION

4.0 FIELD INVESTIGATIONS

4.1. Geologic Reconnaissance

4.2. Subsurface Explorations

5.0 GROUND MOTION FOR LIQUEFACTION SUSCEPTIBILITY AND GROUND DEFORMATION ANALYSES

6.0 REMEDIAL DESIGN

7.0 SUBMITTALS

1.0 INTRODUCTION

D. Liquefaction is a process by which strong shaking during an earthquake causes the ground to temporarily lose its strength and to behave like a viscous liquid rather than a solid material. Liquefaction can cause buildings to tip and settle; roads to crack, deform and flood; buried storage tanks to rise towards the surface; and other types of damage to buildings and infrastructure. Liquefaction hazard investigation reports shall conform with the requirements described below and be prepared by a qualified geotechnical engineer as defined above. The procedures outlined in this Appendix D are intended to provide consultants with a general outline for performing liquefaction studies and to specify the city's expectations concerning such studies. These standards constitute the *minimum* level of effort required in conducting liquefaction studies in the city. Considering the complexity inherent in performing liquefaction studies, additional effort beyond the minimum standards presented herein may be required at some sites to adequately address the liquefaction potential at the site. The information presented in this Appendix D does not relieve consultants of their duty to perform additional geologic or geotechnical engineering analyses that is required by the city or otherwise reasonably necessary to adequately assess the liquefaction potential at a site.

1.1 Purposes. The purposes of establishing minimum standards for liquefaction investigations in the city are to:

- (a) Protect the health, safety, welfare, and property of the public by minimizing the potentially adverse effects of liquefaction and related hazards;
- (b) Assist property owners and land developers in conducting reasonable and adequate studies;
- (c) Provide consulting engineering geologists and geotechnical engineers with a common basis for preparing proposals, conducting studies, and mitigation; and

(d) Provide an objective framework for regulatory review of liquefaction study reports.

1.2 References and Sources. The minimum standards presented herein were developed, in part, from the following sources:

(a) CDMG Special Publication 117, Guidelines for evaluating and mitigating seismic hazards in California (1997).

(b) Recommended procedures for implementation of DMG special publication 117, guidelines for analyzing and mitigating liquefaction hazards in California (Martin and Lew, 1999).

(c) Proceedings of the NCEER Workshop on Evaluation of Liquefaction Resistance of Soils, Technical Report NCEER-97-0022 (Youd and Idriss, 1997).

(d) Liquefaction Resistance of Soils: Summary Report from the 1996 and 1998 NCEER/NSF Workshops on Evaluation of Liquefaction Resistance of Soils, Journal of Geotechnical and Environmental Engineering, (Youd et al., 2001).

(e) Salt Lake County geologic hazards ordinance (2002).

(f) Southern California Earthquake Center (1999), Recommended Procedures for Implementation of DMG Special Publication 117, Guidelines for analyzing and mitigating liquefaction in California.

1.3 Properties Requiring Liquefaction Analyses. The Liquefaction Hazard Study Area Map (Map 3 in Appendix A of Chapter 19.72 of this code) depicts generalized liquefaction susceptibility for the city, and shall be used to determine whether or not a site-specific liquefaction assessment is required for a particular project.

(a) The Liquefaction Hazard Study Area Map is based on a regional-scale investigation of Salt Lake County; therefore, the liquefaction potential at a specific site may be different (higher or lower) than the liquefaction potential suggested by the map. Such map may not identify all areas that have potential for liquefaction; a site located outside of an area of required study is not necessarily free from liquefaction hazard, and the study areas do not always include lateral spread run-out areas. The Liquefaction Hazard Study Area Map is available from the city's planning department.

(b) Chapter 19.72 requires a site-specific liquefaction study to be performed prior to approval of a project based on the liquefaction potential. The liquefaction potential for each individual soil layer in a CPT sounding or at the sampling frequency interval in a boring should be assessed. If the factor of safety for liquefaction is less than 1, then an estimate of the settlement for each layer should be completed. The total anticipated settlement should be defined in the analysis and report. All liquefaction analyses should be completed in accordance with DMG Special Publication 117 (1999), as amended or superseded.

(c) A liquefaction-hazard investigation shall be performed in conjunction with any geotechnical and/or geologic hazards investigation prepared within Cottonwood Heights City.

1.4 Roles of Engineering Geology and Geotechnical Engineering.

(a) The study of liquefaction hazard is an interdisciplinary practice. The site investigation report must be prepared by a qualified engineering geologist or geotechnical engineer, who must have competence in the field of seismic hazard evaluation and mitigation,

and be reviewed by a qualified geotechnical engineer, also competent in the field of seismic hazard evaluation and mitigation.

(b) Because of the differing expertise and abilities of qualified engineering geologists and geotechnical engineers, the scope of the site investigation report for the project may require that both types of professionals prepare and review the report, each practicing in the area of their expertise. Involvement of both a qualified engineering geologist and geotechnical engineer will generally provide greater assurance that the hazard is properly identified, assessed, and mitigated.

(c) Liquefaction analyses are the responsibility of the geotechnical engineer, although the engineering geologist should be involved in the application of screening criteria (section 3.0, steps 1 and 2) and general geologic site evaluation (section 4.1) to map the likely extent of liquefiable deposits and shallow groundwater. Engineering properties of earth material shall be evaluated by the geotechnical engineer. The performance of the quantitative liquefaction analysis resulting in a numerical factor of safety and quantitative assessment of settlement and liquefaction-induced permanent ground displacement shall be performed by geotechnical engineers. The geotechnical and civil engineers shall develop all mitigation and design recommendations. Ground motion parameters for use in quantitative liquefaction analyses may be provided by either the engineering geologist or the geotechnical engineer.

1.5 Minimum Qualifications of the Licensed Professional. Liquefaction analyses must be performed by engineering geologists and geotechnical engineers, qualified as provided in Chapter 19.72.

2.0 GENERAL REQUIREMENTS

Except for the derivation of input ground motion (see Section 5.0, below), liquefaction studies should be performed in general accordance with the latest version of Recommended Procedures for Implementation of DMG Special Publication 117, Guidelines for Analyzing and Mitigating Liquefaction in California (Martin and Lew, 1999). Additional protocol for liquefaction studies is provided in Youd and Idriss (1997, 2001), [Assessment of the Liquefaction Susceptibility of Fine-Grained Soils \(Bray and Sancio, 2006\)](#), and [SPT-Based Liquefaction Triggering Procedures \(Idriss and Boulanger, 2010\)](#). cited above. [Acceptable factors of safety are shown in the following table:](#)

<u>Type of Facility</u>	<u>Minimum Factor of Safety (FS)</u>
Critical Facilities, including essential or hazardous facilities and special occupancy structures	1.3
IBC Category III and IV Structures	
Industrial and Commercial Structures	
IBC Category II(b) Structures	1.25

3.0 PRELIMINARY SCREENING FOR LIQUEFACTION

(a) The Liquefaction Hazard Study Area Map is based on broad regional studies and does not replace site-specific studies. The fact that a site is located within a Liquefaction Hazard Study Area does not mean that there is a significant liquefaction potential at the site, only that a study shall be performed to determine if such potential is present.

(b) Soil liquefaction is caused by strong seismic ground shaking where saturated, cohesionless, granular soil undergoes a significant loss in shear strength that can result in settlement and permanent ground displacement. Surface effects of liquefaction include settlement, bearing capacity failure, ground oscillations, lateral spread and flow failure. It has been well documented that soil liquefaction may occur in clean sands, silty sands, sandy silt, non-plastic silts and gravelly soils. Research shows that the following conditions must be present for liquefaction to occur:

- (i) Soils must be submerged below the water table;
- (ii) Soils must be loose to moderately dense;
- (iii) Ground shaking must be relatively intense; and
- (iv) The duration of ground shaking must be sufficient for the soils to generate seismically-induced excess pore water pressure and lose their shearing resistance.

(c) The following screening criteria may be applied to determine if further quantitative evaluation of liquefaction hazard is required:

(i) If the estimated maximum past, current, and future groundwater levels (i.e., the highest groundwater level applicable for liquefaction analyses) are determined to be deeper than 50 feet below the existing ground surface or proposed finished grade (whichever is deeper), liquefaction studies are not required. For soil materials that are located above the level of the groundwater, a quantitative assessment of seismically induced settlement is required.

(ii) If “bedrock” or similar lithified formational material underlies the site, those materials need not be considered liquefiable and no analysis of their liquefaction potential is necessary.

(iii) If the corrected standard penetration blow count, $(N_1)_{60}$, is greater than or equal to 33 in all samples with a sufficient number of tests, liquefaction assessments are not required. If cone penetration test soundings are made, the corrected cone penetration test tip resistance, q_{c1N} , should be greater than or equal to 180 tsf in all soundings in sand materials, otherwise liquefaction assessments are needed.

(d) If plastic soil ($PI \geq 2018$) materials are encountered during site exploration, those materials may be considered non-liquefiable. Additional acceptable screening criteria regarding the effects of plasticity on liquefaction susceptibility are presented in Boulanger and Idriss (2004), Bray and Sancio (2006), and Seed and others (2003). [Youd and others \(2002\) provide additional guidance on analyzing lateral spreads.](#)

(e) If the screening investigation clearly demonstrates the absence of liquefaction hazards at a project site and the City concurs, the screening investigation will satisfy the site study report requirement for liquefaction hazards. If not, a quantitative evaluation is required to assess the liquefaction hazards.

(f) An important part of a liquefaction analysis is the potential for lateral spreading. Any open face and/or sloped sites should be assessed for the potential for lateral spreading. Mitigation measures should be provided in the analysis and report with respect to this hazard.

4.0 FIELD INVESTIGATIONS

Geotechnical field investigations are routinely performed for new projects as part of the normal development and design process. Geologic reconnaissance and subsurface explorations are normally performed as part of the field exploration program even when liquefaction does not need to be investigated.

4.1 Geologic Reconnaissance.

(a) Geologic research and reconnaissance are important to provide information to define the extent of unconsolidated deposits that may be prone to liquefaction. Such information should be presented on geologic maps and cross sections and provide a description of the formations present at the site that includes the nature, thickness, and origin of Quaternary deposits with liquefaction potential. There also should be an analysis of groundwater conditions at the site that includes the highest recorded water level and the highest water level likely to occur under the most adverse foreseeable conditions in the future, including seasonal changes.

(b) During the field investigation, the engineering geologist should map the limits of unconsolidated deposits with liquefaction potential. Liquefaction typically occurs in cohesionless silt, sand, and fine-grained gravel deposits of Holocene to late Pleistocene age in areas where the groundwater is shallower than about 50 feet, but other soil types may also be liquefiable.

(c) Shallow groundwater may exist for a variety of reasons, some of which are of natural and or manmade origin. Landscape irrigation, on-site sewage disposal, and unlined manmade lakes, reservoirs, and storm-water detention basins may create a shallow groundwater table in sediments that were previously unsaturated.

4.2 Subsurface Explorations.

(a) Subsurface explorations shall consist of drilled-borings and/or cone penetration tests (CPTs). The exploration program shall be planned to determine the soil stratigraphy, groundwater level, and indices that could be used to evaluate the potential for liquefaction by either in situ testing or by laboratory testing of soil samples. If borings are utilized, the use of mud-rotary drilling methods is highly recommended to achieve minimal disturbance of the in-situ soils. If mud-rotary drilling is not used, a through explanation is required in the submitted report. Borings and CPT soundings must penetrate a minimum of 50-45 feet below final ground surface. If during the investigation, the liquefaction evaluation indices the liquefaction potential may extend below 45 feet, the exploration shall be continued for a minimum of 10 feet, to the extent possible, until non-liquefiable soils are encountered.

(b) For saturated cohesionless soils where the SPT (N_1)₆₀ values are less than 15, or where CPT tip resistances are below 60 tsf, grain-size analyses, hydrometers tests, and Atterberg Limits tests shall be performed on these soils to further evaluate their potential for permanent ground displacement (Youd et al., 2002) and other forms of liquefaction-induced ground failure and settlement. In addition, it is also recommended that these same tests be performed on saturated cohesionless soils with SPT (N_1)₆₀ values between 15 and 30 to further evaluate the potential for liquefaction-induced settlement.

(c) Where a structure may have subterranean construction or deep foundations (e.g., caissons or piles), the depth of investigation should extend to a depth that is a minimum of 20 feet (6 m) below the lowest expected foundation level (e.g., caisson bottom or pile tip) or 50-45 feet (15 m) below the existing ground surface or lowest proposed finished grade, whichever is deeper. If, during the study, the indices to evaluate liquefaction indicate that the liquefaction potential may extend below that depth, the exploration should be continued until a significant thickness (at least 10 feet or 3 m, to the extent possible) of nonliquefiable soils are encountered.

5.0 GROUND MOTION FOR LIQUEFACTION SUSCEPTIBILITY AND GROUND DEFORMATION ANALYSES

(a) The two controlling faults that would most affect the city are the Salt Lake City and Provo segments of the Wasatch Fault Zone (WFZ). Repeated Holocene movement has been well documented along both segments (Black and others, 2003). Studies along the Provo segment of the WFZ indicate a recurrence interval of about 1150 years (Olig, and others, 2006; later revised, Olig, 2007) and the most recent event being about 500 to 650 years ago (Black and others, 2003; Olig, and others, 2006). Studies along the Salt Lake City segment of the WFZ indicate a recurrence interval of about 1300 years and the most recent event being about 1300 years ago (Lund, 2005). Based on the paleoseismic record of the Salt Lake City segment and assuming a time- dependent model, McCalpin (2002) estimates a conditional probability (using a log-normal renewal model) of 16.5% in the next 100 years (8.25% in the next 50 years) for a $M > 7$ surface-faulting earthquake. Therefore, using a time-dependent rather than Poisson or random model for earthquake recurrence, the likelihood of a large surface-faulting earthquake on the Salt Lake City segment of the WFZ is relatively high and therefore the Salt Lake City segment is considered the primary controlling fault for deterministic analyses.

(b) Concerning design ground accelerations for liquefaction analyses, the city prefers a probabilistic approach to determining the likelihood that different levels of ground motion will be exceeded at a particular site within a given time period. In order to more closely represent the seismic characteristics of the WFZ and to better capture this possible high likelihood of a surface-faulting earthquake on the Salt Lake City segment, design ground motion parameters for liquefaction analyses shall be based on the peak accelerations with a 2.0 percent probability in 50 years (2,500-year return period). Peak bedrock ground motions can be readily obtained via the internet from the United States Geological Survey (USGS) National Seismic Hazard Maps, Data and Documentation web page (USGS, 2002), which is based on Frankel and others (2002). PGAs obtained from the USGS (2002) web page should be adjusted for effects of soil/rock (site-class) conditions in accordance with Seed and others (2001) or other appropriate methods that consider the site-specific soil conditions and their potential for amplification/ deamplification of the high frequency strong motion. Site specific response analysis may also be used to develop PGA values if the procedures, input data, and results are thoroughly documented and deemed acceptable by the city.

6.0 REMEDIAL DESIGN

Sites, facilities, buildings, structures and utilities that are founded on or traverse liquefiable soils may require further remedial design and/or relocation to avoid liquefaction-induced damage. These should be investigated and evaluated on a site- specific basis with sufficient geologic and geotechnical evaluations to support the remedial design and/or mitigative plan. This design or plan may include changes/modifications to the soil, foundation system, structural frame or support of the building, etc. and should be reviewed and approved by the city.

For all structures where liquefaction-hazard analyses indicates that ground settlement and/or lateral spread may be anticipated, the project structural engineer must provide documentation that the building is designed to accommodate the predicted ground settlements and displacements in such a manner as to be protective of life (collapse prevention) during and after the design seismic event.

7.0 SUBMITTALS

(a) Submittals for review shall include boring logs; geologic cross-sections; laboratory data; discussions pertaining to how idealized subsurface conditions and parameters

used for analyses were developed; analytical results, including computer output files (on request); and summaries of the liquefaction analyses and conclusions regarding liquefaction potential and likely types and amounts of ground failure in addition to the other report requirements detailed in this chapter.

(b) Subsurface geologic and groundwater conditions developed by the engineering geologist must be illustrated on geologic cross-sections and must be utilized by the geotechnical engineer for the liquefaction analyses. If on-site sewage or storm-water disposal exists or is proposed, the liquefaction analyses shall include the effects of the effluent plume on liquefaction potential.

(c) The results of any liquefaction analyses must be submitted with pertinent backup documentation (i.e., calculations, computer output, etc.). Printouts of input data, output data (on request), and graphical plots must be submitted for each computer- aided liquefaction analysis. In addition, input data files, recorded on diskettes, CDs, or other electronic media, may be requested to facilitate the city's review.

APPENDIX E

Minimum Standards for Debris Flow Hazard Studies

Debris flows are fast-moving, flow-type landslides composed of a slurry of rock, mud, organic matter, and water that move down drainage basin channels onto alluvial fans. In addition to threatening lives, debris flows can damage structures and infrastructure by sediment burial, erosion, direct impact, and associated water flooding. Debris flow hazard investigations and reports shall conform with the Guidelines for the Geologic Investigation of Debris-Flow Hazards on Alluvial Fans in Utah (UGS Circular 122) and:

Debris flow hazard maps show the locations of previous debris flows, areas of potential debris flows, and recommended special study areas. These maps are published by the UGS but are currently not available for Cottonwood Heights City. Once these maps are available, at that time they will be adopted to become part of this ordinance. For areas where maps are not available, Geologic Hazard Study Areas are defined by:

1. Units Qmdf, Qaf, Qafy, Qafo, Qaf1, Qaf2, Qaf3, Qaf4, Qaf5, Qafb, Qafp, and Qafoe on the most recent geologic maps published by the UGS. Most maps are available in the UGS Interactive Geologic Map Portal, but contact the UGS for interim, progress update, and other non-final maps that may be available, but not online;

2. Other environmentally sensitive areas that Cottonwood Heights City find to be of significance to the health, safety, and welfare of the citizens of Cottonwood Heights City; and

3. All properties located on alluvial fans and drainage channels subject to flash flooding and debris flows. ~~Debris flow reports shall follow general guidance contained in "Guidelines for the geologic evaluation of debris flow hazards on alluvial fans in Utah," Utah Geological Survey Miscellaneous Publication 05-6. Debris flow hazard analyses and mitigation measures may require contributions from hydrologists as well as qualified engineering geologists and geotechnical engineers.~~

APPENDIX F

Minimum Standards for Rock Fall Hazard Studies

Rockfall is a type of landslide and a natural mass-wasting process that involves the dislodging and rapid downslope movement of individual rocks and rock masses. Rockfall hazard investigations and reports shall conform with the Guidelines for Evaluating Rockfall Hazards in Utah (UGS Circular 122) and:

1. Rockfall hazard maps show the locations of known rockfall, areas of potential rockfall, and recommended special study areas. These maps are published by the UGS but are currently not available for Cottonwood Heights City. Once these maps are available, at that time they will be adopted to become part of this ordinance. For areas where maps are not available, Geologic Hazard Study Areas are defined by:

a. Units Qmrf, Qmt, Qmtr, Qm, and Qmr on the most recent geologic maps published by the UGS. Most maps are available in the UGS Interactive Geologic Map Portal, but contact the UGS for interim, progress update, and other non-final maps that may be available, but not online;

Useful methods to evaluate rock-fall hazards are outlined in: Evans, S.G., and Hungr, O., 1993, The assessment of rockfall hazard at the base of talus slopes: Canadian Geotechnical Journal, v. 30, p. 620-636; Jones, C.L., Higgins, J.D., and Andrew, R.D., 2000, Colorado rockfall simulation program, version 4.0: Report prepared for the Colorado Department of Transportation, 127 p.; and Wieczorek, G.F., Morrissey, M.M., Iovine, G., and Godt, J., 1998, Rock-fall hazards in the Yosemite Valley: U.S. Geological Survey Open-File Report 98- 467, 7 p., 1 pl., scale 1:12,000. Rock-fall studies shall be prepared by a qualified engineering geologist and may require contributions from a qualified geotechnical engineer, particularly in the design of mitigation measures.

APPENDIX G

Groundwater Source Protection

Groundwater source protection requirements in the city are contained in Chapter 17.30, COTTONWOOD HEIGHTS CODE OF ORDINANCES. The provisions of said Chapter 17.30 are hereby incorporated by reference into this Chapter 19.72 to the same extent, and as fully, as if the provisions of said Chapter 17.30 were set forth in this Appendix G.

APPENDIX H

Foundation Excavation Observation Standards

1.0 INTRODUCTION

2.0 GENERAL REQUIREMENTS

3.0 SUBMITTALS

4.0 SITE INVESTIGATION AND SOIL INVESTIGATION STUDIES

5.0 MITIGATION

6.0 NOTICE OF GEOLOGIC HAZARD AND WAIVER OF LIABILITY

1.0 INTRODUCTION

1.1 Introduction. The procedures contained in this appendix are intended to provide consultants with a general outline for performing quantitative foundation excavation observation studies and reports for the development of structures within Cottonwood Heights (the “city”). These standards constitute the minimum level of effort required in conducting these studies. The information presented herein does not relieve consultants of their duty to identify and perform additional geologic or engineering analyses they believe are necessary to assess the suitability of development at a site.

1.2 Purposes. The purposes for establishing minimum standards for foundation excavation observation studies are to:

- (a) Protect the health, safety, welfare, and property of the public by minimizing the potentially adverse effects of development on unsuitable soils and/or high groundwater;
- (b) Assist property owners, contractors and land developers in conducting reasonable and adequate foundation excavation observation studies; and
- (c) Ensure that the recommendations from the subdivision’s geotechnical soils investigation are followed. If no report exists, ensure that a licensed engineer observes the foundation excavation and performs any necessary analyses to determine the suitability of the soils for the proposed building. The engineer shall report that the site is suitable for the proposed structure and that all recommended mitigation has been performed to render the site buildable.

1.3 Areas requiring foundation excavation observation reports. A foundation excavation observation report shall be performed for all proposed development or redevelopment within the city.

1.4 Roles of professionals. Analyses of soils that shall support a structure shall be performed only by or under the direct supervision of licensed professionals, qualified and competent in their respective area of practice.

2.0 GENERAL REQUIREMENTS

The expertise of qualified professional engineers, retained at the developer’s cost, is required to verify the suitability of the soil for the construction of a proposed structure and ensure that the actual in-situ soil material is consistent with previous reports and ensure that the recommendations from those reports have been followed. If no previous reports have been

prepared, an engineer shall make appropriate analyses of the *in-situ* material to determine the suitability of the site for construction and report that all necessary mitigation measures have been performed.

3.0 SUBMITTALS

3.1 Explanatory letter. A letter that states that the site is suitable for development shall be accompanied by an appendix with all pertinent data that was used to determine the suitability of the site for development, include boring logs; geologic cross sections; trench and test pit logs; laboratory data (Atterberg limits, plasticity, soil classification, soil bearing capacity, shear strength test results, density test results etc.); and a discussion regarding the suitability of the site for development. The appendix will contain recommendations for the footings and foundation of the structure such as backfill requirements, additional compaction, drainage, elevation, pilings, bedrock, or any other mitigation measure to meet current building codes, ensure adequate soil bearing capacity, prevent flooding or other adverse factors.

3.2 Subsurface conditions. Subsurface groundwater conditions must be considered and must include an estimate of the maximum anticipated groundwater elevation. If the site contains sewage or storm water infrastructure or is proposed, the recommendations shall reflect the potential impact from a 10-year and 100- year storm event.

3.3 Background documentation. The results of any foundation excavation observation study must be submitted with pertinent backup documentation such as soil logs, laboratory test data, calculations, photographs, measurements and other pertinent data.

4.0 SITE INVESTIGATION AND SOIL INVESTIGATION STUDIES

Adequate evaluation and comprehensive geotechnical engineering studies shall be used to evaluate the suitability of the soil to support the proposed building structure. As directed by the engineer, adequate soil sampling of the subsurface material may be necessary to perform geotechnical testing to determine the soil bearing capacity and other strength parameters to determine the suitability of the soil. In general, the foundation observation evaluation shall follow the following phases:

4.1 Review. Review the soils report or geotechnical investigation that has been performed for the subject site. Understand all relevant geotechnical features related to the property, including groundwater, soil bearing capacity, soil type, drainage, proximity to a flood zone, and all other pertinent geologic factors.

4.2 Excavation. Conduct a foundation excavation inspection prior to the placement of footings. Assess the potential for groundwater below the proposed footings as necessary.

4.3 Observation and assessment. Observe that all of the recommendations from the previous reports have been implemented. Observe that the soil properties are consistent with the findings and assumptions in the report. Assess the groundwater potential and observe that the elevation and drainage is suitable for the proposed structure.

4.4 *Documentation and evaluation.* Documentation and evaluation of subsurface groundwater conditions (including effects of seasonal and longer-term natural fluctuations as well as landscape irrigation), surface water, on-site sewage disposal, and/or storm water disposal.

4.5 *Additional suitability analysis.* If no previous geotechnical report has been performed, the licensed engineer shall perform whatever work is deemed necessary to evaluate the suitability of the site for development.

4.6 *Report.* Prepare a signed and wet stamped letter to the city that the site has been observed and has been deemed suitable for the proposed development. Once this letter has been received and accepted by the city, the placement of footings may commence.

5.0 MITIGATION

If in-situ soil conditions are inconsistent with previous reports and recommendations, a qualified engineer shall perform whatever tests are necessary to assess if the site is suitable for development. If the site is not suitable for development, an engineer may develop mitigation measures and shall report that these measures have been met in a signed and wet stamped letter to the city prior to the construction of footings.

6.0 NOTICE OF GEOLOGIC HAZARD AND WAIVER OF LIABILITY

For developments where full mitigation of recommended measures is not implemented, a notice of geotechnical hazard acceptable to the city shall be recorded with the proposed development describing the hazard at issue and the partial mitigation employed. The notice shall clearly state that the hazard at the site has been reduced by the partial mitigation, but not totally eliminated. In addition, the owner shall (a) be deemed to have assumed all risks and waived all claims against the city and its officers, employees, agents, contractors, consultants and other related parties consultants, and (b) indemnify and hold the city and such related parties harmless from any and all claims arising from the partial mitigation of the seismic displacement hazard.

APPENDIX I

Riparian Corridor and Watershed Protection

Riparian corridor and watershed protection requirements in the city are contained in Chapter 17.31, COTTONWOOD HEIGHTS CODE OF ORDINANCES. The provisions of said Chapter 17.31 are hereby incorporated by reference into this Chapter 19.72 to the same extent, and as fully, as if the provisions of said Chapter 17.31 were set forth in this Appendix I.



PLANNING COMMISSION MEMO

ZTA-19-001 – SLEDS Ordinance Revision (Riparian Protection Area)

Meeting Date: May 4, 2022

Staff Contact: Samantha DeSeelhorst, Associate Planner & Sustainability Analyst

Request

This application represents a city-initiated request to amend the Sensitive Lands Evaluation and Development Standards (SLEDS) Ordinance, including the introduction of a Riparian Protection Area as a component of the overall ordinance update.

Background

The existing SLEDS ordinance references riparian standards as existing within *Appendix I*, which subsequently directs readers to *Chapter 17.31*, a chapter that does not exist within Cottonwood Heights City Code. It is unclear whether these standards were eliminated via administrative error, or if they simply never existed as part of this ordinance. This discrepancy is being addressed as part of the overall SLEDS update.

Utilizing model ordinances from fellow western communities, (e.g. Salt Lake City, Lehi, Boise, Oro Valley, Santa Barbara, Phoenix, etc.), best practices from managing agencies, and University of Utah student work, staff developed a Riparian Protection Area concept which was introduced to the Planning Commission in early 2022, with subsequent updates throughout Spring 2022.

Update



Following feedback from the April 6, 2022 Planning Commission meeting, staff has contacted the Federal Emergency Management Agency (FEMA), the United States Army Corps of Engineers (USACE), and the United States Forest Service (USFS) to request input from these agencies on the draft riparian ordinance. This feedback will be provided to the Planning Commission at a future meeting, after the entities have finished their reviews.

The Planning Commission also requested clarification from staff regarding how the provisions of this riparian ordinance would affect various levels of development and redevelopment. A visual explanation of this concept has been included with this memo for Planning Commission review.

Attachments



1. Development Overview Flowchart

Maintenance or Interior Remodel of Existing Structure




Within Structure that Meets Riparian Protection Area

Within Structure that Does Not Meet Riparian Protection Area



Allowed

Allowed




Addition to Existing Structure

Addition Meets Riparian Protection Area Standards

Addition Does Not Meet Riparian Protection Area Standards

Allowed

Not Allowed



Construction of a New Structure

New Structure Meets Riparian Protection Area Standards

Allowed

New Structure Does Not Meet Riparian Protection Area Standards

Not Allowed
(Unless Reconstruction following Disaster)

1 **MINUTES OF THE COTTONWOOD HEIGHTS CITY**
2 **PLANNING COMMISSION WORK MEETING**

3
4 **Wednesday, April 6, 2022**
5 **5:00 p.m.**
6 **2277 East Bengal Boulevard**
7 **Council Workroom**
8

9 ***ATTENDANCE***

10
11 **Members Present:** Vice-Chair Dan Mills, Commissioner Chris Coutts, Commissioner Bob
12 Wilde, Commissioner Craig Bevan, Commissioner Jonathan Ebbeler
13

14 **Staff Present:** Community and Economic Development Director Michael Johnson,
15 Senior City Planner Andrew Hulka, Assistant City Planner and
16 Sustainability Analyst Samantha DeSeelhorst, Deputy City Recorder
17 Heather Sundquist, City Attorney Shane Topham
18

19 **Others:** Tim Thompson, Geostrata Engineering
20

21 **WORK MEETING**

22
23 In the absence of Chair Jesse Allen, Vice-Chair Dan Mills assumed the Chair and called the
24 Work Meeting to order at 5:00 p.m.
25

26 Chair Mills stated project ZTA-19-00 Sensitive Lands Evaluation and Development Standards
27 (“SLEDS”) Ordinance will be discussed. It was confirmed a full quorum is present although this
28 item is not up for a decision.
29

30 **1.0 Review Business Meeting Agenda.**

31
32 The Business Meeting Agenda was reviewed and discussed.
33

34 **1.1 Additional Discussion Items.**

35
36 Chair Mills introduced Project ADU-22-002, a public hearing to receive comments on a request
37 from Brian Allen for a Conditional Use Permit for a Detached Accessory Dwelling Unit
38 (“ADU”) located at 2217 East Cottonwood Cove Lane in the Rural Residential (RR-1-43) Zone.
39

40 Senior City Planner, Andy Hulka, reported that Project ADU-22-002 is the first Accessory
41 Dwelling Unit (“ADU”) application for review by the Planning Commission. ADUs became
42 legal in Cottonwood Heights with the passage of Ordinance Number 368, an ordinance enacting
43 and codifying Chapter 19.75 (“Accessory Dwelling Units”) of the Cottonwood Heights Code of
44 Ordinances. The ordinance was approved by the City Council in September 2021 in compliance
45 with House Bill 82 (HB 82 – Single-family Housing Modifications) during the 2021 General
46 Session of the Utah State Legislature. It required municipalities to allow internal ADUs in

1 single-family residential zones. The City Council decided to also allow detached ADUs as a
2 conditional use when adopting the City’s ADU ordinance. Before the adoption of
3 Ordinance 368, ADUs were prohibited in Cottonwood Heights. However, guesthouses have been
4 allowed if compliant with the bulk and massing requirements for accessory buildings and with
5 the condition that rental of the guesthouse was prohibited (19.76.030.A). He confirmed that a
6 permit to expand the existing guesthouse on the subject property was approved by the City in
7 2019.

8
9 A map of the subject property was displayed. Mr. Hulka defined an ADU as a permanent
10 residential dwelling unit intended for one additional family located in a separate dwelling unit on
11 the same lot as a single-family dwelling unit. The difference between an ADU and a guesthouse
12 is that the rental, lease, or use of a guesthouse as a permanent residence for a second family on
13 the premises is prohibited. The conversion of a guesthouse to an ADU would allow for rental of
14 30 days or longer. Detached ADUs shall be subject to the following additional development
15 standards:

- 16
17 • Any detached ADU shall be a permanent structure. Trailers, mobile homes, and other
18 portable structures shall not be permitted as detached ADUs. The City’s Building
19 Official shall determine whether a structure is permanent.
- 20 • Any detached ADU shall be subject to all primary structure setback standards for the
21 zone in which it is located.
- 22 • Any detached ADU shall meet all accessory building standards for height, lot coverage,
23 rear yard coverage, size, and any other applicable standards for the zone in which it is
24 located.
- 25 • Any detached ADU on a flag lot shall meet primary structure flag lot setback standards
26 for the zone in which it is located.
- 27 • Conversion of existing accessory buildings to detached ADUs is only permitted if the
28 structure meets or is modified to meet all current City standards and all applicable
29 provisions of this chapter.

30
31 Mr. Hulka stated that a more in-depth presentation would be provided during the Business
32 Meeting.

33
34 **1.2 (Project ZTA-19-001) Sensitive Lands Evaluation and Development**
35 **Standards (“SLEDS”) Ordinance.**

36
37 Assistant City Planner/Sustainability Analyst, Samantha DeSeelhorst, presented Project ZTA-19-
38 001 Sensitive Lands Evaluation and Development Standards (“SLEDS”) Ordinance. The
39 riparian standards were reviewed. She stated that within the existing SLEDS Ordinance, riparian
40 protection guidelines are referenced but the chapter that is supposed to contain them does not
41 exist. Most guidelines implement a buffered area system dividing areas adjacent to a waterway
42 into three segments. She noted that buffering measurements are consistent with live ordinances
43 being more restricted. The matter was reviewed by the Planning Commission in February 2022
44 at which time feedback was provided. It was requested that requirements from other agencies,
45 measurement protocols, Staff review processes, and all system mapping analyses be further
46 reviewed. Changes within the current draft were detailed. Ms. DeSeelhorst reported that they

1 intend to coordinate with the Federal Emergency Management Agency (“FEMA”) to require a
2 similar feedback process as it can impact the flood plain.

3
4 Ms. DeSeelhorst stated that measurement protocols were updated and require measurements be
5 considered from the top of the bank. The clarification also included that Staff review process
6 should flow through the large area Development Review Committee (“DRC”) to provide more
7 flexibility and language allowing for third-party experts if needed. Staff coordinated with the
8 GIS department to prepare an estimate of structures impacted by the buffer areas. Geologic
9 hazard areas were reviewed. Ms. DeSeelhorst confirmed that she will provide clarity regarding
10 the threshold for requiring the standards. It was anticipated that public comment will be received
11 during a May 2022 meeting. The Commission was favorable to understanding primary versus
12 secondary structures.

13
14 Tim Thompson from GeoStrata Engineering reported that he is a Professional Geologist and has
15 been consulting with the City since its incorporation. He was involved with the original SLEDS
16 Ordinance and has been assisting with the current update.

17
18 Mr. Hulka reported that the current draft includes multiple changes and addressed the
19 Commission’s concern with the 45-day requirement, steep slopes, preparation of a newsletter
20 article, and an extended Work Session. A redline draft was included in the Staff Report
21 highlighting the substantive changes. The appendix now references major sections of the Utah
22 Geological Survey (“UGS”) guidelines including mapping information, fault studies, slope
23 stability, landslides, debris flow, and rockfall studies. They pulled from conservative standards
24 with the requirement that a Geologist or Engineer provide stamped certification to verify that
25 safety standards and hazards have been addressed. They also are required to provide liability
26 insurance of up to \$2 million.

27
28 Mr. Thompson stated that while the UGS makes great recommendations, they do not practice in
29 the field and their ideas may be ahead of the curve of the actual practice. He explained that
30 providing a warranty, guarantee, or certification would void his insurance coverage. It is illegal
31 in the State of Utah to provide a warranty as a licensed professional. The stamp of certification
32 is provided to establish that everything has been completed to ensure compliance. He noted that
33 the requirement to provide a certain level of insurance has not been determined in the State and
34 limited liability may be based on each project that remains negotiable. It was his opinion that the
35 unintended consequence of liability costs is that many top consultants often turn away smaller
36 projects. The remaining consultants charge an exorbitant amount for the same work due to a
37 lack of competition. It is their standard of practice to negotiate the amount of liability to be
38 covered for a particular project. The negotiation process was reviewed.

39
40 Ms. DeSeelhorst stated that Staff has noted that this topic will require continued discussion and
41 refinement.

42
43 Chair Mills stated that the public comment period will be forthcoming. He believed that
44 determining who is responsible for both private and commercial is extremely critical in terms of
45 the City’s liability.

1 Slope issues were next reviewed. Mr. Hulka stated that the new ordinance specifies that no
2 development, including structures and retaining walls, is permitted on slope areas above 30%.
3 Exceptions were described. They intended to allow smaller slopes around local locations that
4 may impact adjacent properties. Concerns were addressed while still allowing limited
5 disturbances on properties of one acre or less. He confirmed that there is an appeal process that
6 applies to any language in the chapter.
7

8 Mr. Thompson noted that as a consultant, he does not practice in Cottonwood Heights. He
9 expressed concern with trying to rectify two distinct portions of the ordinance that allow cuts and
10 fills of up to 2:1 or 50% slopes. He stated that a natural slope of 30% cannot be touched.
11 Bridging the issues to create a more cohesive ordinance was desired. It was his opinion that
12 most communities strive to protect their viewsheds. This is done by restricting how high they
13 are allowed to go on a hillside by limiting the slope. He believed that they are more of a
14 viewshed issue and should be addressed separately under another City Code. Modification of
15 slopes was discussed. He encouraged discernment between slope stability issues and suggested
16 that the quality of community issues be dealt with separately.
17

18 The avalanche appendix was next discussed. Mr. Hulka stated that the model ordinance was
19 referenced that detailed elevations of 5,000 feet with adequate snow supply to produce
20 avalanches, which include slopes greater than 47%. An elevation map was displayed.
21

22 Mr. Hulka referenced structural fill and stated that compaction criteria are required beneath
23 structures with required percentages. He was notified that several changes were incorrect and
24 offered reassurance that updated language will be provided to ensure accuracy in the final
25 version.
26

27 Changes to the ordinance's Architectural Design will include the removal of the Planning
28 Commission's role to ensure consistency with current architectural review standards. Mr. Hulka
29 explained that in addition to the City's normal design guidelines, additional sensitive area
30 requirements will be included and clarified.
31

32 The appeals process was next discussed. The original Code provided standards with the last
33 draft being revised to specify that instead of relying solely on the Appeals Hearing Officer, the
34 City will assemble a panel of experts to hear appeals on technical disputes regarding sensitive
35 lands issues. Mr. Hulka confirmed that the two have been merged and clarified that the City's
36 Appeals Hearing Officer is the appeal authority for disputes, however, the City may assemble a
37 panel to assist with technical disputes. Details regarding the appeals process were discussed. It
38 was confirmed that if a decision becomes complicated and includes complex technical geologic
39 requirements, the City may assemble an Appeals Board.
40

41 Mr. Hulka reported that the revised language specifies that the review shall not exceed 45 days.
42 The intent of putting a number to the review eliminates an argument over the previous language
43 that stated that the City will act diligently in its review. Time frame options were discussed.
44

1 **2.0 Adjournment.**

2

3 *Commissioner Bevan moved to adjourn. Commissioner Ebbeler seconded the motion. The*
4 *motion passed with the unanimous consent of the Commission.*

5

6 The Work Meeting adjourned at 6:30 p.m.

1 Senior City Planner, Andy Hulka, presented the Staff Report and stated that the proposed one-
2 acre property is located at 2217 East Cottonwood Cove Lane. A zoning map of the property was
3 displayed. The RR-1-43 zone is a one-acre minimum lot size residential zone surrounded in part
4 by residential zones. He defined an ADU as a permanent residential dwelling unit meant for one
5 additional family located in a separate dwelling unit on the same lot as a single-family dwelling
6 unit, either within the same building as the single-family dwelling unit or in a detached accessory
7 building. Mobile homes or other portable structures do not qualify as an ADU. Additionally, an
8 ADU may not be located within a mobile home or other portable structure. ADUs became legal
9 in Cottonwood Heights with the passage of Ordinance Number 368, an ordinance enacting and
10 codifying Chapter 19.75 (“Accessory Dwelling Units”) of the Cottonwood Heights Code of
11 Ordinances. It was approved by the City Council in September 2021.

12
13 Mr. Hulka reported that the ordinance was adopted in compliance with House Bill 82 (HB 82 –
14 Single-Family Housing Modifications) during the 2021 General Session of the Utah State
15 Legislature, which required municipalities to allow internal ADUs in single-family residential
16 zones. The City Council decided to also allow detached ADUs as a conditional use when
17 adopting the City’s ADU ordinance. Prior to adoption of Ordinance 368, ADUs were prohibited
18 in Cottonwood Heights. However, guesthouses have been allowed if they comply with the bulk
19 and massing requirements for accessory buildings and with the condition that rental of the
20 guesthouse is prohibited (19.76.030.A). A permit to expand the existing guesthouse on the
21 subject property was approved by the City in 2019.

22
23 Mr. Hulka explained that the renting or leasing of the guesthouse is prohibited as are separate
24 utility meters. All other bulk and massing requirements must be met. The existing building on
25 the proposed lot was reviewed in 2019 according to the standards allowing the issuance of the
26 Building Permit. A visual depiction of the proposed site plan was displayed. Mr. Hulka
27 explained that the parking requirement for detached ADUs is two additional spaces that do not
28 block the required parking for the primary dwelling. Required setbacks are to be a minimum of
29 10 feet and must include a buffer zone. Staff recommended approval with conditions set forth in
30 the Staff Report.

31
32 The applicant, Brian Allen, referenced parking along the driveway and confirmed that there is
33 enough room to provide three cars with adequate egress into the rear of the property. There is
34 also a garage with space for three more vehicles.

35
36 Screening and buffering issues were discussed. City Attorney, Shane Topham, stated that it is a
37 precedent-setting process and emphasized the importance of ensuring that parking and buffering
38 are addressed.

39
40 Chair Mills opened the public hearing.

41
42 Mr. Hulka read into the record a comment received from *Tony Escobar*, a member of the
43 Homeowners Association (“HOA”). Mr. Escobar was concerned that the proposed application
44 will set a precedent and allow other similar units within the development. The application is
45 concerning since an ADU allows rental units on the property and sets a precedent for the other
46 properties within the HOA. He asked if the lack of advance notice was due to the applicant’s

1 position as a City Lobbyist. He encouraged the HOA Members to attend the hearing to voice
2 their opinions.

3
4 *Kennedy Nate* indicated that he lives directly west of the subject property and did not necessarily
5 see any issues or concerns with the ADU. He stressed the need to clarify that there is not a
6 formal HOA. Mr. Allen is not the President because there is none and only heads up the
7 informal group. He did not consider what is proposed to be an issue and understood that the
8 applicable Code only allows for a single unit as part of the ADU process. He expressed support
9 for the request and did not foresee any issues with the existing vegetation and buffering.

10
11 There were no additional public comments. The public hearing was closed.

12
13 Commissioner Bevan remarked that extensive consideration and time were spent contemplating
14 ADU issues. He was surprised when the State stepped in and allowed for an applicable
15 ordinance or implementation of requirements established by the State. He considered the
16 proposed application to be a prime example of the intent of the ADU Ordinance and stated that
17 someone should be living in the structure. He expressed support for the request.

18
19 Commissioner Ebbeler agreed with Commissioner Bevan's comments and believed the request
20 complies with the current Code. He expressed his support.

21
22 It was the consensus of the Commission that the existing fencing and landscaping buffer are
23 sufficient to mitigate the impact of the parking areas.

24
25 ***Commissioner Coutts moved to recommend APPROVAL of Project ADU-22-002 a public***
26 ***hearing to receive comments on a request from Brian Allen for a Conditional Use Permit for a***
27 ***detached Accessory Dwelling Unit ("ADU") at 2217 East Cottonwood Cove Lane in the Rural***
28 ***Residential (RR-1-43) zone subject to the following:***

29
30 ***Conditions:***

- 31
32 ***1. The property's record owner must occupy either the primary dwelling unit or***
33 ***the approved ADU as such owner's permanent residence and at no time receive***
34 ***rent for the owner-occupied unit.***
35
36 ***2. The ADU shall not be used for short-term rentals.***
37
38 ***3. A final building inspection must be approved by the city's building department.***

39
40 ***Findings:***

- 41
42 ***1. The proposed use described in the report is allowed as a conditional use in the***
43 ***RR-1-43 (Rural Residential) zone.***
44

- 1 2. *The proposed use will be required to continually meet the applicable provisions*
2 *of Chapter 19.75, "Accessory Dwelling Units," of the Cottonwood Heights*
3 *zoning ordinance.*
- 4
- 5 3. *The proposed use will be required to continually meet the applicable provisions*
6 *of Chapter 19.84, "Conditional Uses," of the Cottonwood Heights zoning*
7 *ordinance.*
- 8
- 9 4. *A public hearing was held in accordance with local and state requirements.*
- 10
- 11 5. *Proper notice of the public hearing was given.*
- 12
- 13 6. *Landscaping and fencing have been provided to mitigate the impact of parking*
14 *areas and ADU entrances from adjoining property owners.*
- 15
- 16 7. *The proposed use will not be detrimental to the health, safety, comfort, order, or*
17 *general welfare of persons residing or working in the vicinity.*
- 18
- 19 8. *The proposed use will comply with the intent, spirit, and regulations of the city*
20 *zoning ordinance and general plan.*
- 21
- 22 9. *Nuisances related to traffic, parking, lighting, and noise will be abated by the*
23 *conditions imposed.*
- 24
- 25 10. *The applicant will be required to comply with all imposed conditions.*
- 26
- 27 11. *The protection of property values, the environment, and the tax base for the*
28 *City will be assured.*
- 29

30 *Commissioner Wilde seconded the motion.*

31

32 *Commissioner Ebbeler moved to amend the motion to add the front parking space to the rear*
33 *west side of the unit. Commissioner Coutts accepted the friendly amendment.*

34

35 *Vote on motion: Commissioner Ebbeler-Aye, Commissioner Bevan-Aye, Commissioner Wilde-*
36 *Aye, Commissioner Coutts-Aye, and Chair Mills-Aye. The motion passed unanimously*

37

38 **4.0 Consent Agenda.**

39

40 **4.1 Approval of Planning Commission Minutes.**

41

42 **4.1.1 March 2, 2022, Planning Commission Minutes.**

43

44 *Commissioner Ebbeler moved to APPROVE the Planning Commission Minutes of March 2,*
45 *2022. Commissioner Wilde seconded the motion. Vote on motion: Commissioner Ebbeler-*

1 *Aye, Commissioner Bevan-Aye, Commissioner Wilde-Aye, Commissioner Coutts-Abstained,*
2 *and Chair Mills-Aye. The motion passed unanimously with one abstention.*
3

4 **5.0 Adjournment.**
5

6 *Commissioner Ebbeler moved to adjourn. Commissioner Bevan seconded the motion. The*
7 *motion passed with the unanimous consent of the Commission.*
8

9 The Planning Commission Meeting adjourned at 7:09 p.m.

1 *I hereby certify that the foregoing represents a true, accurate, and complete record of the*
2 *Cottonwood Heights City Planning Commission Meeting held Wednesday, April 6, 2022.*
3

4 Teri Forbes

5 Teri Forbes

6 T Forbes Group

7 Minutes Secretary

8

9 Minutes Approved: _____